IRON BELLE TRAIL SECTION K VAN BUREN TOWNSHIP WAYNE COUNTY, MICHIGAN

PERMIT / APPROVAL SUMMARY			
DATE SUBMITTED	DATE APPROVED	PERMIT / APPROVAL	

WAYNE COUNTY DPS GENERAL NOTES:

- 1. ALL WORK WITHIN THE WAYNE COUNTY ROAD RIGHT-OF-WAY (ROW) AND DRAIN EASEMENT SHALL BE IN ACCORDANCE WITH THE CURRENT STANDARDS AND GENERAL SPECIFICATIONS, INCLUDING SOIL EROSION AND SEDIMENTATION CONTROL OF THE WAYNE COUNTY DEPARTMENT OF PUBLIC SERVICES, AND MDOT 2012 SPECIFICATIONS FOR CONSTRUCTION.
- 2. THESE PLANS ARE NOT VALID WITHOUT ATTACHMENT OF THE WAYNE COUNTY PERMIT SPECIFICATIONS FOR CONSTRUCTION WITHIN THE ROAD ROW, PARKS, DRAIN EASEMENT OR SANITARY SEWER UNDER JURISDICTION OF THE WAYNE COUNTY (07/01/93) REVISED 12/15/2004
- 3. CONTRACTOR SHALL CONTACT <u>MISS DIG AT 811</u> TO IDENTIFY AND FLAG / MARK THE LOCATIONS OF ALL UNDERGROUND UTILITIES AT THE PROPOSED CONSTRUCTION AREAS PRIOR TO START OF CONSTRUCTION, AND SHALL BE RESPONSIBLE FOR DETERMINING THE EXACT LOCATIONS AND ELEVATIONS OF ALL UNDERGROUND UTILITIES, AND RESOLVE ANY CONFLICT BETWEEN THE PROPOSED WORK AND THE EXISTING UNDERGROUND OR ABOVEGROUND UTILITIES.
- 4. CONTRACTOR SHALL MAINTAIN 18" MINIMUM VERTICAL CLEARANCE AND 3 FEET MINIMUM HORIZONTAL CLEARANCE BETWEEN THE PROPOSED AND EXISTING UTILITIES. ANY PROPOSED UTILITY PERMITTED TO CROSS UNDER THE ROAD OR DRAIN, MUST BE PLACED A MINIMUM OF 7 FEET BELOW THE LOWEST POINT OF THE ROAD, OR 6 FEET BELOW THE DRAIN BOTTOM. OVERHEAD WIRES/CABLES MUST BE INSTALLED 18 FEET MINIMUM ABOVE THE ROAD CENTERLINE. TO RELOCATE ANY UTILITY WITHIN THE ROAD ROW, THE CONTRACTOR SHALL COORDINATE THE RELOCATION WITH THE UTILITY COMPANY AND AS DIRECTED BY THE WAYNE COUNTY ENGINEER.
- 5. ALL SURVEY MONUMENTS / CORNERS AND BENCH MARKS LOCATED WITHIN THE CONSTRUCTION AREA MUST BE PRESERVED IN ACCORDANCE WITH PUBLIC ACT 74 AS AMENDED (INCLUDING ACT 34, P.A. 2000) AND AS PER WAYNE COUNTY PERMIT RULE 1.5. THE PERMIT HOLDER AND CONTRACTOR SHALL COORDINATE THE WORK WITH A PROFESSIONAL SURVEYOR LICENSED IN THE STATE OF MICHIGAN DURING CONSTRUCTION ACTIVITIES FOR THE PURPOSE OF WITNESSING, PRESERVING OR REPLACING SURVEY MONUMENT AND MONUMENT BOXES.
- 6. EXPOSURE OF ANY UTILITIES UNDER THE PAVEMENT WILL NOT BE PERMITTED, UNLESS APPROVED BY THE WAYNE COUNTY ENGINEER. PAVEMENT REMOVAL AND REPLACEMENT SHALL BE PERFORMED PER APPLICABLE WAYNE COUNTY STANDARD DETAILS AN AS DIRECTED BY THE WAYNE COUNTY ENGINEER.
- 7. CONTRACTOR SHALL RESTORE ALL DISTURBED AREAS WITHIN THE WAYNE COUNTY ROAD ROW AND DRAIN EASEMENT WITH 3" TOPSOIL, THM SEED MIX AND MULCH. SLOPES STEEPER THAN 1 ON 3 SHALL BE RESTORED BY PLACING SOD ON 2" TOPSOIL.
- 8. ALL BACKFILLS UNDER OR WITHIN 3 FEET OF THE PROPOSED OR EXISTING PAVEMENT, CURB OR SIDEWALK SHALL CONFORM TO THE WAYNE COUNTY TRENCH "B" BACKFILL REQUIREMENTS. TRENCH "A" BACKFILL MAY BE USED WITHIN THE ROAD ROW AREAS UNDER CONDITIONS OTHER THAN THOSE SPECIFIED FOR TRENCH "B".
- 9. CONTRACTOR IS RESPONSIBLE FOR RESTORING OR REPLACING ALL DISTURBED LANDSCAPED AREAS, SPRINKLER SYSTEMS, FENCES, SIGNS, MAIL BOXES, ETC. WITHIN THE WAYNE COUNTY ROAD ROW AND / OR AS DIRECTED BY THE COUNTY ENGINEER.
- 10. CONTRACTOR SHALL MAINTAIN TWO-WAY TRAFFIC AT ALL TIMES. OTHERWISE, DETOURING TRAFFIC MUST BE PER APPROVED PLANS. ALL SIGNING AND TRAFFIC CONTROL DEVICES SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF M.M.U.T.C.D.
- 11. MAINTAIN A SAFE AND ADEQUATE TRAVEL ROUTE FOR PEDESTRIANS AT ALL TIMES THROUGHOUT THE PROJECT DURATION.
- 12. TUNNELING, BORING AND JACKING OPERATIONS SHALL BE IN ACCORDANCE WITH THE WAYNE COUNTY SPECIFICATIONS AND DETAILS. BORE PITS SHALL BE PLACED AT MINIMUM 10 FEET FROM THE BACK OF CURB OR EDGE OF PAVEMENT.
- 13. REMOVE ALL ABANDONED CONDUITS FROM THE COUNTY ROADS ROW OR AS DIRECTED BY THE WAYNE COUNTY ENGINEER.
- 14. CONTRACTOR SHALL PROVIDE COLD WEATHER PROTECTION FOR ALL PROPOSED CONCRETE WORK (PAVEMENTS, SIDEWALKS, DRIVE APPROACHES, ETC.) AS DIRECTED BY THE WAYNE COUNTY ENGINEER.
- 15. OVERNIGHT VEHICLE PARKING AND STORAGE OF CONSTRUCTION MATERIALS AND EQUIPMENTS ARE NOT PERMITTED WITHIN THE WAYNE COUNTY ROADS RIGHTS-OF-WAY.
- 16. CONTRACTOR SHOULD OBTAIN SOIL EROSION AND SEDIMENTATION CONTROL PERMIT FROM THE WAYNE COUNTY DPS. CONTACT THE WAYNE COUNTY SOIL EROSION OFFICE AT (734) 326-3936, OR THE COMMUNITY HAVING JURISDICTION OVER THE SOIL EROSION PERMIT.
- CONTRACTOR SHALL NOTIFY THE WAYNE COUNTY TRAFFIC SIGNAL SHOP AT (734) 955-2161 AT LEAST 72 HOURS PRIOR TO START OF WORK AT OR NEAR ANY SIGNALIZED INTERSECTIONS.
- 18. CONTRACTOR SHALL NOTIFY WAYNE COUNTY 72 HOURS PRIOR TO START OF CONSTRUCTION. CONTACT THE PERMIT OFFICE AT (734) 858-2761.

WAYNE COUNTY NOTE:

1. WAYNE COUNTY R 23-0084 REVIEW NUMBER.

DESIGN TEAM

OWNER/APPLICANT/DEVELOPER CIVIL ENGINEER


VAN BUREN TOWNSHIP 46425 TYLER ROAD VAN BUREN TWP, MI 48111 CONTACT: ELIZABETH RENAUD PHONE: (734) 699 - 8900 EXT. 9258 CELL: (734) 787-0542 EMAIL: ERENAUD@VANBUREN-MI.ORG

PEA GROUP 7927 NEMCO WAY, STE. 115 BRIGHTON, MI 48116 CONTACT: JILL RICKARD, PE PHONE: 844.813.2949 EMAIL: JRICKARD@PEAGROUP.COM

LANDSCAPE ARCHITECT

PEA GROUP 7927 NEMCO WAY, STE. 115 BRIGHTON, MI 48116 CONTACT: JEFF SMITH, PLA, LEED AP PHONE: 844.813.2949 EMAIL: JSMITH@PEAGROUP.COM CONSTRUCTION PLANS





LOCATION MAP

PEX. GROUP

Sheet List Table		
Sheet Number	Sheet Title	
C-0.0	COVER SHEET	
C-1.1	OVERALL SHEET	
C-2.1	TOPOGRAPHICAL SURVEY AND DEMOLITION PLAN	
C-2.2	TOPOGRAPHICAL SURVEY AND DEMOLITION PLAN	
C-2.3	TOPOGRAPHICAL SURVEY AND DEMOLITION PLAN	
C-2.4	TOPOGRAPHICAL SURVEY AND DEMOLITION PLAN	
C-3.1	DIMENSIONAL PAVING PLAN	
C-3.2	DIMENSIONAL PAVING PLAN	
C-3.3	DIMENSIONAL PAVING PLAN	
C-3.4	DIMENSIONAL PAVING PLAN	
C-4.1	GRADING PLAN	
C-4.2	GRADING PLAN	
C-4.3	GRADING PLAN	
C-4.4	GRADING PLAN	
C-5.1	DETAIL SHEET	
C-5.2	DETAIL SHEET	

PROJECT DESCRIPTION:

THIS PROJECT IS PART OF THE IRON BELLE TRAIL PROJECT. IT CONSISTS OF CONSTRUCTING APPROXIMATELY 10,984 SFT (.25 AC) OF SIDEWALK ALONG EAST HURON RIVER DRIVE AND 1000 SFT OF ASPHALT PATH ALONG METROPOLITAN PARKWAY. MODIFICATIONS TO THE TRAFFIC SIGNAL AT THE INTERSECTION ARE INCLUDED WITH THIS PROJECT. THIS PROJECT WILL CONNECT INTO SECTION J (PREVIOUSLY APPROVED) WHEN THE TRAFFIC LIGHT AT EAST HURON RIVER DRIVE AND HAGGERTY ROAD IS INSTALLED AT A FUTURE DATE.

REVISIONS


DESCRIPTION ORIGINAL ISSUE DATE REVISIONS PER TOWNSHIP REVISIONS PER WAYNE COUNTY REVIEW

DATE 12/12/2022 8/8/2023 8/24/2023



S


NOT FOR CONSTRUCTION



- IO. ON-SITE FILL CAN BE USED IF THE SPECIFIED COMPACTION REQUIREMENTS CAN BE ACHIEVED. IF ON-SITE SOIL IS USED, IT SHOULD BE CLEAN AND FREE OF FROZEN SOIL, ORGANICS, OR OTHER DELETERIOUS MATERIALS.
- THE FINAL SUBGRADE / EXISTING AGGREGATE BASE SHOULD BE THOROUGHLY PROOFROLLED USING A FULLY LOADED TANDEM AXLE TRUCK OR FRONT END LOADER UNDER THE OBSERVATION OF A GEOTECHNICAL/PAVEMENT ENGINEER. LOOSE OR YIELDING AREAS THAT CANNOT BE MECHANICALLY STABILIZED SHOULD BE REINFORCED USING GEOGRIDS OR REMOVED AND REPLACED WITH ENGINEERED FILL OR AS DICTATED BY FIELD CONDITIONS.
- 12. SUBGRADE UNDERCUTTING, INCLUDING BACKFILLING SHALL BE PERFORMED TO REPLACE MATERIALS SUSCEPTIBLE TO FROST HEAVING AND UNSTABLE SOIL CONDITIONS. ANY EXCAVATIONS THAT MAY BE REQUIRED BELOW THE TOPSOIL IN FILL AREAS OR BELOW SUBGRADE IN CUT AREAS WILL BE CLASSIFIED AS SUBGRADE UNDERCUTTING.

13. SUBGRADE UNDERCUTTING SHALL BE PERFORMED WHERE NECESSARY AND THE EXCAVATED MATERIAL SHALL BECOME THE PROPERTY OF THE CONTRACTOR. ANY SUBGRADE UNDERCUTTING SHALL BE BACKFILLED AS RECOMMENDED IN THE GEOTECHNICAL ENGINEERING REPORT FOR THE PROJECT.

14. ANY SUB-GRADE WATERING REQUIRED TO ACHIEVE REQUIRED DENSITY SHALL BE CONSIDERED INCIDENTAL TO THE JOB.



ALL WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH THE STANDARDS AND SPECIFICATIONS OF THE TOWNSHIP/COUNTY. ALL TRENCHES UNDER OR WITHIN THREE (3) FEET OR THE FORTY-FIVE (45) DEGREE ZONE OF INFLUENCE LINE OF EXISTING AND/OR PROPOSED PAVEMENT, BUILDING PAD OR DRIVE APPROACH SHALL BE BACKFILLED WITH SAND COMPACTED TO AT LEAST NINETY-FIVE (95) PERCENT OF MAXIMUM UNIT WEIGHT (ASTM D-1557). ALL OTHER TRENCHES TO BE COMPACTED TO 90% OR BETTER.

WHERE EXISTING MANHOLES OR SEWER PIPE ARE TO BE TAPPED, DRILL HOLES 4" CENTER TO CENTER, AROUND PERIPHERY OF OPENING TO CREATE A PLANE OF WEAKNESS JOINT BEFORE BREAKING SECTION OUT.

THE LOCATIONS AND DIMENSIONS SHOWN ON THE PLANS FOR EXISTING UTILITIES ARE IN ACCORDANCE WITH AVAILABLE INFORMATION WITHOUT UNCOVERING AND MEASURING. THE DESIGN ENGINEER DOES NOT GUARANTEE THE ACCURACY OF THIS INFORMATION OR THAT ALL EXISTING UNDERGROUND FACILITIES ARE SHOWN. CONTRACTOR SHALL FIELD VERIFY UTILITIES.

THE CONTRACTOR SHALL COORDINATE TO ENSURE ALL REQUIRED PIPES, CONDUITS, CABLES AND SLEEVES ARE PROPERLY PLACED FOR THE INSTALLATION OF GAS, ELECTRIC, PHONE, CABLE, IRRIGATION, ETC. IN SUCH A MANNER THAT WILL FACILITATE THEIR PROPER INSTALLATION PRIOR TO THE PLACEMENT OF THE PROPOSED PAVEMENT AND LANDSCAPING.

6. PIPE LENGTHS INDICATED ARE FROM CENTER OF STRUCTURE AND TO END OF FLARED END SECTION UNLESS NOTED OTHERWISE. CONTRACTOR SHALL INSPECT ALL EXISTING PUBLIC STORM SEWER, SANITARY SEWER AND WATER MAIN STRUCTURES WITHIN THE LIMITS OF CONSTRUCTION AND WITH THE GOVERNING AGENCY INSPECTOR PRIOR TO ESTABLISHING FINAL GRADE. NOTIFY THE ENGINEER, OWNER/DEVELOPER, AND GOVERNING AGENCY IF STRUCTURE IS DEEMED TO BE STRUCTURALLY UNSOUND AND/OR IN NEED OF REPAIR.

ALL STORM SEWER 12" DIAMETER OR LARGER SHALL BE REINFORCED CONCRETE PIPE (RCP C-76) CLASS IV WITH MODIFIED TONGUE AND GROOVE JOINT WITH RUBBER GASKETS UNLESS SPECIFIED OTHERWISE (ASTM C-443).

IN AREAS WHERE NEW PAVEMENTS ARE BEING CONSTRUCTED, THE TOPSOIL AND SOIL CONTAINING ORGANIC MATTER SHALL BE REMOVED PRIOR TO PAVEMENT CONSTRUCTION.

CONSTRUCTION TRAFFIC SHOULD BE MINIMIZED ON THE NEW PAVEMENT. IF CONSTRUCTION TRAFFIC IS ANTICIPATED ON THE PAVEMENT STRUCTURE, THE INITIAL LIFT THICKNESS COULD BE INCREASED AND PLACEMENT OF THE FINAL LIFT COULD BE DELAYED UNTIL THE MAJORITY OF THE CONSTRUCTION ACTIVITIES HAVE BEEN COMPLETED. THIS ACTION WILL ALLOW REPAIR OF LOCALIZED FAILURE, IF ANY DOES OCCUR, AS WELL AS REDUCE LOAD DAMAGE ON THE PAVEMENT SYSTEM.

ALL EXPANSION JOINTS AND CONCRETE PAVEMENT JOINTS TO BE SEALED.

CONCRETE PAVEMENT JOINTING - UNLESS SHOWN OTHERWISE IN THE PLANS OR REQUIRED BY THE AUTHORITY HAVING JURISDICTION; 4.1. WHERE PROPOSED CONCRETE ABUTS A STRUCTURE, PROVIDE A MINIMUM 1/2" EXPANSION JOINT. THE JOINT FILLER BOARD MUST BE AT LEAST THE FULL DEPTH OF THE CONCRETE AND HELD DOWN A 1/2" TO ALLOW FOR SEALING. 4.2. WHERE PROPOSED CONCRETE ABUTS EXISTING CONCRETE OR IN BETWEEN POURS OF PROPOSED CONCRETE (CONSTRUCTION JOINT), PROVIDE 5/8" DOWELS EVERY 30" CENTER TO CENTER HALF WAY ALONG THE THICKNESS OF THE PROPOSED PAVEMENT. ALTERNATE DOWELS SIZES AND SPACING MUST BE APPROVED THE ENGINEER PRIOR TO COMMENCING WORK AND VIA THE

4.3. WHERE PROPOSED CONCRETE ABUTS EXISTING OR PROPOSED SIDEWALK OR CURBING, PROVIDE A MINIMUM 1/2" EXPANSION JOINT. 4.4. CONTROL, LONGITUDINAL AND/OR TRANSVERSE JOINTS SHALL BE PLACED TO PROVIDE PANELS WITHIN THE PAVEMENT AS SQUARE AS POSSIBLE WITH THE FOLLOWING MAXIMUM SPACING PARAMETERS: 4.4.1. 6-INCH THICK CONCRETE PAVEMENT: 12' X 12'

4.4.2. 8-INCH THICK CONCRETE PAVEMENT: 15' X 15'

4.5. IRREGULAR-SHAPED PANELS MAY REQUIRE THE USE OF REINFORCING MESH OR FIBER MESH AS DETERMINED BY THE ENGINEER. THE USE OF MESH MUST BE APPROVED THE ENGINEER PRIOR TO COMMENCING WORK AND VIA THE SUBMITTAL PROCESS. 4.6. IF A JOINT PLAN IS NOT PROVIDED IN THE PLANS, THE CONTRACTOR SHALL SUBMIT ONE TO THE ENGINEER FOR REVIEW PRIOR TO COMMENCING WORK AND VIA THE SUBMITTAL PROCESS.

CONCRETE CURBING JOINTING - UNLESS SHOWN OTHERWISE IN THE PLANS OR REQUIRED BY THE AUTHORITY HAVING JURISDICTION 5.1. JOINTS WHEN ADJACENT TO ASPHALT PAVEMENT 5.1.1. PLACE CONTRACTION JOINTS AT 10' INTERVALS

5.1.2. PLACE 1/2" EXPANSION JOINT AT CATCH BASINS, EXISTING AND PROPOSED SIDEWALK OR EXISTING CURBING.

5.1.3.1. AT SPRING POINTS OF INTERSECTIONS OR ONE OF THE END OF RADIUS LOCATIONS IN A CURVE

5.1.3.2. AT 400' MAXIMUM INTERVALS ON STRAIGHT RUNS 5.1.3.3. AT THE END OF RADIUS AT OPPOSITE ENDS IN A CURBED LANDSCAPE ISLAND

5.2. JOINTS WHEN TIED TO CONCRETE PAVEMENT 5.2.1. PLACE CONTRACTION JOINTS OPPOSITE ALL TRANSVERSE CONTRACTION JOINTS IN PAVEMENT

5.2.2. PLACE 1/2" EXPANSION JOINT AT CATCH BASINS, EXISTING AND PROPOSED SIDEWALK OR EXISTING CURBING.

5.2.3. PLACE 1" EXPANSION JOINT OPPOSITE ALL TRANSVERSE EXPANSION JOINTS IN PAVEMENT 5.2.4. CURB AND GUTTER AND CONCRETE SHALL BE TIED TOGETHER SIMILAR TO A LONGITUDINAL LANE TIE JOINT (MDOT B1 JOINT)

5.3. IN BETWEEN POURS OF PROPOSED CONCRETE CURBING (CONSTRUCTION JOINT): 5.3.1. CARRY THE REBAR CONTINUOUSLY BETWEEN POURS

5.3.2. IF THE REBAR IS NOT LONG ENOUGH TO CARRY CONTINUOUSLY, THEN TIE TWO PIECES OF REBAR PER THE LATEST MDOT SPECIFICATIONS

CONCRETE SIDEWALK JOINTING - UNLESS SHOWN OTHERWISE IN THE PLANS OR REQUIRED BY THE AUTHORITY HAVING JURISDICTION 6.1. PLACE TRANSVERSE CONTRACTION JOINTS EQUAL TO THE WIDTH OF THE WALK WHEN WIDTH IS LESS THAN 8' 6.2. PLACE TRANSVERSE AND LONGITUDINAL CONTRACTION JOINTS EQUAL TO 1/2 THE WIDTH OF THE WALK WHEN WIDTH IS EQUAL TO OR GREATER THAN 8'

6.3. PLACE 1" EXPANSION JOINT WHERE ABUTTING SIDEWALK RAMP AND/OR RADIUS IN INTERSECTION 6.4. PLACE TRANSVERSE 1/2" EXPANSION JOINT AT MAXIMUM OF 100' SPACING

6.5. PLACE 1/2" EXPANSION JOINT WHEN ABUTTING A FIXED STRUCTURE, OTHER PAVEMENT (CONCRETE PAVEMENT AND DRIVE APPROACHES), UTILITY STRUCTURES, LIGHT POLE BASES AND COLUMNS

CONSTRUCTION MATERIAL SUBMITTALS

UNLESS REQUIRED OTHERWISE IN THE PROJECT SPECIFICATIONS, THE CONTRACTOR SHALL ONLY SUBMIT THE FOLLOWING CONSTRUCTION MATERIAL SUBMITTALS, AS APPLICABLE TO THE PLANS, FOR REVIEW BY THE ENGINEER. UNLESS APPROVED IN ADVANCE AND IN WRITING BY THE ENGINEER, ANY MATERIAL SUBMITTALS PROVIDED TO THE ENGINEER FOR REVIEW IN ADDITION TO THIS LIST SHALL BE RETURNED TO THE CONTRACTOR WITHOUT A REVIEW BEING PERFORMED.

- SOIL EROSION AND SEDIMENTATION CONTROL MEASURES 2. UTILITY TRENCH BACKFILL MATERIAL WITH ALL MATERIAL DATA INCLUDED IN THE SUBMITTAL BEING DATED WITHIN 60 DAYS OF THE SUBMITTAL UNLESS APPROVED OTHERWISE BY THE ENGINEER
- RIP RAP MATERIAL WITH ALL MATERIAL DATA INCLUDED IN THE SUBMITTAL BEING DATED WITHIN 60 DAYS OF THE SUBMITTAL UNLESS APPROVED OTHERWISE BY THE ENGINEER
- I. STORM AND SANITARY SEWER PIPING INCLUDING JOINTS
- 5. STORM AND SANITARY SEWER STRUCTURES
- 6. STORM AND SANITARY SEWER STRUCTURE FRAME AND COVERS INCLUDING CLEAN OUTS . PAVEMENT AGGREGATE BASE MATERIAL WITH ALL MATERIAL DATA INCLUDED IN THE SUBMITTAL BEING DATED WITHIN 60 DAYS OF THE SUBMITTAL UNLESS APPROVED OTHERWISE BY THE ENGINEER
- PAVEMENT UNDERDRAIN MATERIAL AND BACKFILL WITH ALL BACKFILL MATERIAL DATA INCLUDED IN THE SUBMITTAL BEING DATED WITHIN 60 DAYS OF THE SUBMITTAL UNLESS APPROVED OTHERWISE BY THE ENGINEER
- PAVEMENT MIX DESIGNS SUBMITTED FOR REVIEW BY THE ENGINEER MUST FOLLOW THE CURRENT MOOT REVIEW CHECKLISTS AS SUMMARIZED BELOW AND ALL MATERIAL DATA INCLUDED IN THE SUBMITTAL BEING DATED WITHIN 60 DAYS OF THE SUBMITTAL UNLESS APPROVED OTHERWISE BY THE ENGINEER: •8.1. CONCRETE MIX DESIGN REVIEW CHECKLIST (FORM 2000) •8.2. SUPERPAVE MIX DESIGN CHECKLIST (FORM 1862) •8.3. MARSHALL MIX DESIGN CHECKLIST (FORM 1849)
- 10. SITE FENCING AND GATES INCLUDING FOOTINGS
- 1. SITE RAILINGS INCLUDING FOOTING OR EMBEDMENTS
- 12. ANY ITEMS SHOWN IN THE PLANS OR DETAIL SHEETS THAT SPECIFICALLY STATE FOR THE CONTRACTOR TO SUBMIT A SHOP DRAWING TO THE ENGINEER FOR REVIEW. THESE ITEMS INCLUDE, BUT ARE NOT LIMITED TO:
- RETAINING WALL MATERIAL AND STRUCTURAL CALCULATIONS
- TRENCH DRAIN MATERIAL AND SHOP DRAWING DEPICTING THE LAYOUT OF THE SYSTEM

ANY SPECIALITY ITEMS SHOWN IN THE PLANS OR DETAIL SHEETS THAT SPECIFICALLY DO NOT STATE FOR THE CONTRACTOR SHALL SUBMIT A SHOP DRAWING TO THE ENGINEER FOR REVIEW BUT THE CONTRACTOR REQUESTS TO BE REVIEWED. THE CONTRACTOR'S REQUEST FOR REVIEW MUST BE IN WRITING AND APPROVED BY THE ENGINEER PRIOR TO SUBMITTING THE INFORMATION.

NOT FOR CONSTRUCTION

PEA JOB NO.	2022-0652
P.M.	JTS
DN.	JMR
DES.	JMR
DRAWING NUMBER:	

DRAWING TITLE OVERALI SHEET


ORIGINAL ISSUE DATE: **DECEMBER 12, 2022**

ORIGINAL ISSUE 12-12-2022 REVISED PER TOWNSHIP 8-8-2023 REVISED PER WC REVIEW 8-24-2023




VAN BUREN TOWNSHIF VAN BUREN, MICHIGAN

PROJECT TITLE **IRON BELLE TRAIL** SECTION K





CLIENT VAN BUREN TOWNSHIP




DETERMINING THE EXACT UTILITY LOCATIONS AND ELEVATIONS

PRIOR TO THE START OF CONSTRUCTION.









FLOODPLAIN:

(Per Flood Insurance Rate Map Number 26163C0358E. effective February 2, 2012) BY GRAPHICAL PLOTTING, THE SITE LIES WITHIN:

SPECIAL FLOOD HAZARD AREAS SUBJECT TO INUNDATION BY THE 1% ANNUAL CHANCE FLOOD The 1% annual chance flood (100 year flood), also known as the base flood, is the flood that has a 1% chance of being equaled or exceeded in any given year. The Special Flood Hazard Area is the area subject to flooding by the 1% annual chance flood. Areas of Special Flood Hazard include Zones A, AE, AH, AO, AR, A99, V and VE. The Base Flood Elevation is the water—surface elevation of the 1% annual chance flood.

ZONE A — No Base Flood Elevations determined.


OTHER AREAS —— ZONE X — Area to be determined outside of the 0.2% annual chance floodplain.

BENCHMARKS

(GPS DERIVED - NAVD88)

BM #300 TOP OF SANITARY MANHOLE, 58 FEET SOUTH OF THE CENTER LINE OF EAST HURON RIVER DR. AND 45 FEET WEST OF THE CENTER LINE OF HAGGERTY RD. ELEV. – 656.26

MAG NAIL IN THE NORTH FACE OF A POWER POLE LOCATED AT THE SOUTH CORNER OF HURON RIVER DR & HAGGERTY RD/METRO PKWY. ELEV. – 652.80



GENERAL DEMOLITION NOTES:

- THESE NOTES APPLY TO ALL CONSTRUCTION ACTIVITIES ON THIS PROJECT:
- ALL MATERIAL TO BE REMOVED, WHETHER SPECIFICALLY NOTED IN THE PLANS OR NOT, SHALL BE REMOVED FROM THE SITE BY THE CONTRACTOR AND DISPOSED OF OFF-SITE IN A LEGAL MANNER. NO ON-SITE BURY OR BURN PITS SHALL BE ALLOWED.
- 2. ALL DEMOLITION WORK SHALL CONFORM TO ALL LOCAL CODES AND ORDINANCES.
- 3. STAGING/PHASING OF DEMOLITION AND CONSTRUCTION IS TO BE COORDINATED WITH THE OWNER AND THE CONTRACTOR PRIOR TO CONSTRUCTION.
- . SPECIFIC DEMOLITION ITEMS HAVE BEEN INDICATED ON THE PLANS AS A GUIDE TO THE GENERAL SCOPE OF THE WORK. IT IS THE INTENT THAT THESE ITEMS SHALL BE COMPLETELY REMOVED BY THE CONTRACTOR ABOVE AND BELOW GROUND, UNLESS SPECIFICALLY NOTED OTHERWISE, AND THAT DEMOLITION WILL INCLUDE BUT WILL NOT NECESSARILY BE LIMITED TO THESE ITEMS. CONTRACTOR SHALL VISIT SITE TO VERIFY EXISTING CONDITIONS AND EXTENTS OF THE DEMOLITION THAT WILL BE REQUIRED PRIOR TO SUBMITTING A BID.
- 5. REMOVE ALL STRUCTURES DESIGNATED FOR REMOVAL ACCORDING TO THE DEMOLITION PLAN. THIS INCLUDES FOUNDATIONS, FOOTINGS, FOUNDATION WALLS, FLOOR SLABS, UNDERGROUND UTILITIES, CONCRETE, ASPHALT, TREES,
- 6. REFER TO SHEET C-5.2 FOR TREE PROTECTION DETAILS.
- THE CONTRACTOR SHALL, AS A MINIMUM, PROVIDE TREE PROTECTION FENCING AROUND EXISTING TREES TO BE SAVED THAT ARE WITHIN 15 FEET OF CONSTRUCTION ACTIVITIES AND AS INDICATED IN THE PLANS OR PER LOCAL AGENCY REQUIREMENTS.
- 3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEAN UP, NOISE, DUST CONTROL, STREET SWEEPING AND HOURS OF OPERATION IN ACCORDANCE WITH THE LOCAL CODES.
- D. THE CONTRACTOR SHALL PROVIDE ALL NECESSARY BARRICADES, SIGNAGE, MARKINGS, LIGHTS AND OTHER TRAFFIC CONTROL DEVICES TO PROTECT THE WORK ZONE AND SAFELY MAINTAIN TRAFFIC PER AGENCY REQUIREMENTS AND IN ACCORDANCE WITH THE LATEST EDITION OF THE STATE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.
- 10. THE CONTRACTOR SHALL CONTACT THE APPROPRIATE UTILITY COMPANIES TO CONFIRM THAT UTILITY LEADS HAVE BEEN TAKEN OUT OF SERVICE PRIOR TO DEMOLITION.
- 11. ALL BUILDING GAS LEADS, METERS AND ASSOCIATED EQUIPMENT SHALL BE REMOVED AS SHOWN ON THE PLANS. COORDINATE ALL ASSOCIATED WORK WITH THE APPROPRIATE UTILITY COMPANY.
- 12. REMOVE ALL OVERHEAD AND UNDERGROUND ELECTRICAL LINES WITHIN THE AREA OF CONSTRUCTION AS SHOWN ON THE PLANS. COORDINATE SHUTDOWNS AND REMOVALS WITH ELECTRICAL SERVICE PROVIDER OR THE APPROPRIATE UTILITY COMPANY. (NOTE: PHONE AND CABLE T.V. SERVICES MAY ALSO BE LOCATED ON OVERHEAD LINES.)
- 13. THE CONTRACTOR IS RESPONSIBLE FOR THE REMOVAL AND REPLACEMENT OF SIGNS AND SUPPORTS WITHIN THE WORK AREA, AS NECESSARY TO FACILITATE CONSTRUCTION. SIGNS SHALL BE PROTECTED OR STOCKPILED FOR REUSE AS SPECIFIED IN THE PLANS OR AS REQUIRED BY THE AGENCY OF JURISDICTION. THE CONTRACTOR SHALL REPLACE ANY DAMAGED SIGNS AND SUPPORTS AT NO ADDITIONAL COST TO THE OWNER.
- 14. THE CONTRACTOR SHALL NOTIFY THE APPROPRIATE 811/ONE CALL UTILITY LOCATING CENTER, THE CITY ENGINEER AND/OR THE AUTHORITY HAVING JURISDICTION 3 BUSINESS DAYS PRIOR TO THE BEGINNING OF CONSTRUCTION.


TRAIL PLAN-E. HURON RIVER DR.

STA 0+000 STA 4+08

TREE REMOVAL

SAWCUT LINE






C-2.1

TOPOGRAPHICAL SURVEY AND DEMOLITION PLAN

ORIGINAL ISSUE DATE: DECEMBER 12, 2022 DRAWING TITLE






IRON BELLE TRAIL SECTION K VAN BUREN TOWNSHIF VAN BUREN, MICHIGAN





VAN BUREN TOWNSHIP 46425 TYLER ROAD VAN BUREN, MICHIGAN


CLIENT




























PEV


GROUP


t: 844.813.2949


www.peagroup.com














NO INFORMATION AS OF 11/03/22

DTE GAS EMAIL DATED 10/27/22

AT&T DATED 3/19/20

COMCAST DATED 3/19/20

DTE DATED 4/08/20

WAYNE COUNTY PLAT DATED 4/11/68

REFERENCE DRAWINGS:

GRAVEL

WATER MAIN

STORM SEWER

ELECTRIC

GAS

RIGHT OF WAY

ASPHALT

4+50


HURON CLINTON METRO AUTH

PARCEL NO. 83 095 99 0006 000

SANITARY SEWER

COMMUNICATION





OR

LLI

H U H U H

< O

ΣŪ

4+00

- RIM 651.21 24"W 641.66 24"NE 641.61

12"SW_646_71

GATE

LEGEND:

FLOODPLAIN:

(Per Flood Insurance Rate Map Number 26163C0358E. effective February 2, 2012)

BY GRAPHICAL PLOTTING, THE SITE LIES WITHIN:

SPECIAL FLOOD HAZARD AREAS SUBJECT TO INUNDATION BY THE 1% ANNUAL CHANCE FLOOD The 1% annual chance flood (100 year flood), also known as the base flood, is the flood that has a 1% chance of being equaled or exceeded in any given year. The Special Flood Hazard Area is the area subject to flooding by the 1% annual chance flood. Areas of Special Flood Hazard include Zones A, AE, AH, AO, AR, A99, V and VE. The Base Flood Elevation is the water—surface elevation of the 1% annual chance flood.


ZONE A — No Base Flood Elevations determined.

OTHER AREAS ZONE X — Area to be determined outside of the 0.2% annual chance floodplain.

BENCHMARKS

(GPS DERIVED - NAVD88)

BM #301 MAG NAIL IN THE NORTH FACE OF A POWER POLE LOCATED AT THE SOUTH CORNER OF HURON RIVER DR & HAGGERTY RD/METRO PKWY. ELEV. – 652.80



NOT FOR CONSTRUCTION

PEA JOB NO.	2022-0652
P.M.	JTS
DN.	JMF
DES.	JMF
DRAWING NUMBER:	
C-2.	2

TOPOGRAPHICAL SURVEY AND DEMOLITION PLAN

ORIGINAL ISSUE DATE: DECEMBER 12, 2022 DRAWING TITLE

REVISIONS ORIGINAL ISSUE 12-12-2022 REVISED PER TOWNSHIP 8-8-2023 REVISED PER WC REVIEW 8-24-2023




IRON BELLE TRAIL SECTION K VAN BUREN TOWNSHIP VAN BUREN, MICHIGAN




VAN BUREN TOWNSHIP 46425 TYLER ROAD VAN BUREN, MICHIGAN


CLIENT




NO INFORMATION AS OF 11/03/22 WAYNE COUNTY PLAT DATED 4/11/68 COMCAST DATED 3/19/20 DTE GAS EMAIL DATED 10/27/22


CAUTION!! THE LOCATIONS AND ELEVATIONS OF EXISTING UNDERGROUND UTILITIES AS SHOWN ON THIS DRAWING ARE ONLY APPROXIMATE. NO GUARANTEE IS EITHER EXPRESSED OR IMPLIED AS TO THE COMPLETENESS OR ACCURACY THEREOF. THE CONTRACTOR SHALL BE EXCLUSIVELY RESPONSIBLE FOR DETERMINING THE EXACT UTILITY LOCATIONS AND ELEVATIONS PRIOR TO THE START OF CONSTRUCTION.




































ΡΞΛ

GROUP

t: 844.813.2949

www.peagroup.com



لن

-S ♡ -> @ EX. HYDRANT, GATE VALVE & POST INDICATOR VALVE

EX. COMBINED SEWER MANHOLE

-UG-ELEC-E-E-EX. U.G. ELEC,MANHOLE, METER & HANDHOLE

T II EX. TRANSFORMER & IRRIGATION VALVE

© GAS EX. GAS VALVE & GAS LINE MARKER

◎ 👋 EX. WATER VALVE BOX & SHUTOFF

S EX. SANITARY CLEANOUT & MANHOLE

EX. CLEANOUT & MANHOLE

O^{Y.D.} ® EX. YARD DRAIN & ROOF DRAIN

🔟 🕁 🔆 🛛 EX. MAILBOX, SIGN & LIGHTPOLE

EX. SPOT ELEVATION - EX. CONTOUR

NAIL FOUND / NAIL & CAP SET

🖽 🌐 🌐 EX. SQUARE, ROUND, & BEEHIVE CATCH BASIN

EX. UNIDENTIFIED STRUCTURE

-UG-CATV-EX. U.G. CABLE TV & PEDESTAL

— – — – — EX. GAS LINE

— — — — EX. WATER MAIN

C

© §T

?

ø ø

• • • • EX. GUARD RAIL

🛎 🛓 🛎 🛓 🏝 🖿 🛛 EX. WETLAND

IRON FOUND / SET

------ EX. SANITARY SEWER

——— – – —— EX. STORM SEWER

FLOODPLAIN:

(Per Flood Insurance Rate Map Number 26163C0358E. effective February 2, 2012) BY GRAPHICAL PLOTTING, THE SITE LIES WITHIN:

SPECIAL FLOOD HAZARD AREAS SUBJECT TO INUNDATION BY THE 1% ANNUAL CHANCE FLOOD The 1% annual chance flood (100 year flood), also known as the base flood, is the flood that has a 1% chance of being equaled or exceeded in any given year. The Special Flood Hazard Area is the area subject to flooding by the 1% annual chance flood. Areas of Special Flood Hazard include Zones A, AE, AH, AO, AR, A99, V and VE. The Base Flood Elevation is the water-surface elevation of the 1% annual chance flood.

ZONE A — No Base Flood Elevations determined.


OTHER AREAS

ZONE X — Area to be determined outside of the 0.2% annual chance floodplain.

BENCHMARKS (GPS DERIVED - NAVD88)

BM #300 TOP OF SANITARY MANHOLE, 58 FEET SOUTH OF THE CENTER LINE OF EAST HURON RIVER DR. AND 45 FEET WEST OF THE CENTER LINE OF HAGGERTY RD. ELEV. — 656.26

BM #301 MAG NAIL IN THE NORTH FACE OF A POWER POLE LOCATED AT THE SOUTH CORNER OF HURON RIVER DR & HAGGERTY RD/METRO PKWY. ELEV. - 652.80




TREE REMOVAL SAWCUT LINE

CONC WALL

13+00

CONCRETE



TRAIL PLAN-E. HURON RIVER DR. STA 8+59 TO STA 13+00

NOT FOR CONSTRUCTION

P.M.	JTS
DN.	JMR
DES.	JMR
DRAWING NUMBER:	
C-2.3	

PEA JOB NO. 2022-0652

TOPOGRAPHICAL SURVEY AND DEMOLITION PLAN

DECEMBER 12, 2022

ORIGINAL ISSUE DATE: DRAWING TITLE

REVISED PER WC REVIEW 8-24-2023

REVISIONS ORIGINAL ISSUE 12-12-2022 REVISED PER TOWNSHIP 8-8-2023





IRON BELLE TRAIL SECTION K VAN BUREN TOWNSHIP VAN BUREN, MICHIGAN





VAN BUREN TOWNSHIP 46425 TYLER ROAD VAN BUREN, MICHIGAN


CLIENT

































VAL	· [·]·]·]·]·]·]·]·]·]·]·
D	
	$\times\!\!\!\times\!\!\!\times\!\!\!\times$
	\times

LEGEND:

EX. OH. ELEC, POLE & GUY WIRE
EX. U.G. CABLE TV & PEDESTAL
EX. U.G. COMMUNICATION LINE, PEDESTAL & MANHO
EX. U.G. ELEC, MANHOLE, METER & HANDHOLE
EX. GAS LINE
EX. GAS VALVE & GAS LINE MARKER
EX. TRANSFORMER & IRRIGATION VALVE
EX. WATER MAIN
EX. HYDRANT, GATE VALVE & POST INDICATOR VALV
EX. WATER VALVE BOX & SHUTOFF
EX. SANITARY SEWER
EX. SANITARY CLEANOUT & MANHOLE
EX. COMBINED SEWER MANHOLE
EX. STORM SEWER
EX. CLEANOUT & MANHOLE
EX. SQUARE, ROUND, & BEEHIVE CATCH BASIN
EX. YARD DRAIN & ROOF DRAIN
EX. UNIDENTIFIED STRUCTURE
EX. MAILBOX, SIGN & LIGHTPOLE
EX. FENCE
EX. GUARD RAIL
EX. SPOT ELEVATION
EX. CONTOUR
EX. WETLAND
IRON FOUND / SET
NAIL FOUND / NAIL & CAP SET
BRASS PLUG SET
MONUMENT FOUND / SET
SECTION CORNER FOUND
RECORDED / MEASURED / CALCULATED


WATER MAIN SANITARY SEWER STORM SEWER ELECTRIC COMMUNICATION


GAS

NO INFORMATION AS OF 11/03/22 WAYNE COUNTY PLAT DATED 4/11/68 COMCAST DATED 3/19/20 DTE GAS EMAIL DATED 10/27/22

AT&T DATED 3/19/20 DTE DATED 4/08/20

REFERENCE DRAWINGS:





DEMOLITION LEGEND: ITEM TO BE PROTECTED ITEM TO BE REMOVED FENCE/CURB/GUARD RAIL REMOV AREA OR ITEMS TO BE REMOVED UTILITY REMOVAL ASPHALT REMOVAL

FLOODPLAIN: (Per Flood Insurance Rate Map Number 26163C0358E. effective February 2, 2012)		
BY GRAPHICAL PLOTTING, THE SITE LIES WITHIN:		
SPECIAL FLOOD HAZARD AREAS SUBJECT TO INUNDATION BY THE 1% ANNUAL CHANCE FLOOT The 1% annual chance flood (100 year flood), also known as the base flood, is the flood that has a 1% chance of being equaled or exceeded in any given year. The Special Flood Hazar Area is the area subject to flooding by the 1% annual chance flood. Areas of Special Flood Hazard include Zones A, AE, AH, AO, AR, A99, V and VE. The Base Flood Elevation is the water-surface elevation of the 1% annual chance flood.		
ZONE A — No Base Flood Elevations determined.		
OTHER AREAS ZONE X — Area to be determined outside of the 0.2% annual chance floodplain.		
DEMOLITION LEGEND:		
ITEM TO BE PROTECTED		
ITEM TO BE REMOVED		
FENCE/CURB/GUARD RAIL REMOVAL . /././././.		

 \times

 \mathbf{X}

__ __ __

AREA OR ITEMS TO BE REMOVED

UTILITY REMOVAL

ASPHALT REMOVAL


TREE REMOVAL


SAWCUT LINE

LEGAL DESCRIPTION (Per on-line Assessing)


PARCEL ID 83 096 99 0004 000 Land in the Township of Van Buren, Wayne County, Michigan, described as follows:

THAT PT OF THE S 1/2 OF SEC 24 DESC AS BEG AT THE S 1/4 COR OF SEC 24 AND PROC TH S89DEG 41M 35S E ALONG THE S SEC LINE 1473.05FT TH N23DEG 59M 15S E 896.18FT TH N42DEG 01M 15S E 462.72FT TH S85DEG 34M 45S E 92.80FT TH N1DEG 37M E 172.38FT TH S 8DEG 30M E 213.78FT TH N1DEG 30M E 134.23FT TH N59DEG 22M 30S E 35.55FT TH S87DEG 55M E 300FT TH N1DEG 30M E ALONG THE E SEC LINE 150FT TH N88DEG 30M W 609.20FT TH S71DEG W 307FT TH N1DEG 30M E 143.37FT TH N88DEG 30M W 316.15FT TH S69DEG 23M 15S W 353.80FT TH N39DEG 28M 30S W 1120.22FT TH ALONG THE SELY LINE OF NEWLY ESTABLISHED HURON RIVER DR S42DEG 36M 43S W 244. 7FT AND ON A TANGENT CURVE TO THE RIGHT RAD 1710.97FT TO THE N AND S 1/4 SEC LINE TH SODEG 18M 20S E ALONG SAID LINE TO THE SE COR OF LOT 232 SUPERS VAN BUREN PLAT NO 7 AS REC IN L73 OF PLATS P45 WCR TH N89DEG 45M W ALONG THE S LINE OF SAID LOT 205.63FT TH SWLY ALONG THE SELY LINE OF SAID HURON RIVER DR ON A CURVE CONC TO THE NW RAD 1660.97FT ARC 94.73FT TH S43DEG 34M OS E 506.40FT TH S1DEG 30M 45S W 726.46FT TH S25DEG 10M W 512.39FT TH S60DEG 38M 45S W 400FT TH S88DEG 45M 15S E ALONG THE S SEC LINE 524.17FT TO THE POB 77.27 AC





 CO
 SANITARY SEWER, CLEANOUT & MANHOLE
 O
 O
 STORM SEWER, CLEANOUT & MANHOLE O B MII



POST INDICATOR VALVE WATER VALVE BOX/HYDRANT VALVE BOX, SERVICE SHUTOFF MAILBOX, TRANSFORMER, IRRIGATION CONTROL VALVE UNIDENTIFIED STRUCTURE SPOT ELEVATION CONTOUR LINE STREET LIGHT SIGN CONCRETE ASPHALT

GRAVEL GRAVEL SHOULDER

REFERENCE DRAWINGS BP PIPELINE MAP TPR 12574, DATED MARCH 23, 2021 GAS


SANITARY SEWER VAN BUREN TOWNSHIP MAP, EMAIL DATED 03/12/021 DTE ELECTRIC FACILITY MAP #244-258, 244-260 & 241-260, DATED ./29/2021 ELECTRIC

BENCHMARKS (GPS DERIVED - NAVD88)

BM #300 BENCH TIE IN THE WEST SIDE OF A 24" TREE, LOCATED APPROX. 100' EAST FROM THE CENTERLINE OF S. METRO PKWY & APPROX. 500' NORTH FROM GAS SUB-STATION,. ELEV. - 656.45


BM #301 MAG NAIL IN THE NORTH FACE OF A POLWER POLE LOCATED AT THE SOUTH CORNER OF HURON RIVER DR & HAGGERTY RD/METRO PKWY. ELEV. – 652.80







CAUTION!! THE LOCATIONS AND ELEVATIONS OF EXISTING UNDERGROUND UTILITIES AS SHOWN ON THIS DRAWING ARE ONLY APPROXIMATE. NO GUARANTEE IS EITHER EXPRESSED OR IMPLIED AS TO THE COMPLETENESS OR ACCURACY THEREOF. THE CONTRACTOR SHALL BE EXCLUSIVELY RESPONSIBLE FOR DETERMINING THE EXACT UTILITY LOCATIONS AND ELEVATIONS PRIOR TO THE START OF CONSTRUCTION.



HURON CLINTON METROPARKS 13000 HIGH RIDGE DRIVE BRIGHTON, MICHIGAN 48114

PROJECT TITLE **HURON RIVER**

DRIVE SIDEWALK PART OF THE SOUTH 1/2 OF SECTION 24 BELLEVILLE, MICHIGAN

REVISIONS

ORIGINAL ISSUE DATE:

AUGUST 30, 2021

DRAWING TITLE TOPOGRAPHICAL SURVEY AND DEMOLITION PLAN


PEA JOB NO.	2021-0108
P.M.	JS
DN.	JMR
DES.	JMR
DRAWING NUMBER	:

C-2.4

WAYNE COUNTY CONSTRUCTION NOTES:

SAWCUT FULL DEPTH THE EXISTING PAVEMENT TO THE NEAREST JOINT WITHIN WAYNE COUNTY ROAD RIGHT-OF-WAY AND REMOVE THE EXISTING PAVEMENT AND CURBS AS DIRECTED BY WAYNE COUNTY ENGINEER.

- 2. CONSTRUCT WAYNE COUNTY ROAD PAVEMENT PER WAYNE COUNTY STANDARDS DETAIL "PR-1" OR "PR-2" AS APPLICABLE, OR AS DIRECTED BY THE WAYNE COUNTY ENGINEER.
- 3. PLACE 9" OF 21AA AGGREGATE COMPACTED TO MINIMUM 95% DENSITY OF MAXIMUM UNIT WEIGHT OR AS DIRECTED BY WAYNE COUNTY ENGINEER.
- . CONSTRUCT WAYNE COUNTY ROAD PAVEMENT REPAIRS WITH MINIMUM OF 2.0" HMA TOP (F) ON MINIMUM 10" NON-REINFORCED CONCRETE WC 35 P MIX (3500 PSI AT 28 DAYS) AND INTEGRAL STRAIGHT CURB TYPE "4" AS PER WAYNE COUNTY STANDARD DETAIL "RS-3" OR AS DIRECTED BY WAYNE COUNTY ENGINEER.
- 5. THE THE NEW PAVEMENT TO THE EXISTING PAVEMENT WITH #5 EPOXY COATED BARS AT MAXIMUM 43-INCH ON CENTER LONGITUDINALLY AND AT 18-INCH ON CENTER TRANSVERSELY AS PER WAYNE COUNTY STANDARD DETAIL "RS-2" OR AS DIRECTED BY THE COUNTY ENGINEER.
- 6. PLACE THE CONSTRUCTION JOINTS OF THE NEW PAVEMENT TO MATCH THE EXISTING PAVEMENT JOINTS OR AS DIRECTED BY THE WAYNE COUNTY ENGINEER.
- 7. REPLACE ANY DAMAGED CURBS AS A RESULT OF THIS PROJECT ACTIVITY AS PER WAYNE COUNTY STANDARD DETAIL "D-7" OR AS DIRECTED BY THE COUNTY ENGINEER.
- 8. ANY DAMAGED UNDERDRAIN AS A RESULT OF THIS PROJECT ACTIVITY SHALL BE RECONSTRUCTED AS PER WAYNE COUNTY DETAIL "S-14" OR AS DIRECTED BY THE COUNTY ENGINEER.
- 9. ANY DAMAGED SIDEWALK AS A RESULT OF THIS PROJECT ACTIVITY SHALL BE RECONSTRUCTED AS PER WAYNE COUNTY DETAIL "RS-5" OR AS DIRECTED BY THE COUNTY ENGINEER.
- 10. MAINTAIN A MAXIMUM 2% TRANSVERSE SLOPE ON THE SIDEWALK.
- 11. ANY DAMAGED SIDEWALK RAMPS SHOULD BE REPLACED TO MATCH THE ADA REQUIREMENTS AS PER MDOT STANDARD DETAIL "R-28-1".
- 12. STRUCTURE ADJUSTMENT SHALL BE DETERMINED AT THE SITE BY WAYNE COUNTY ENGINEER.
- 13. RELOCATE, RESTORE, OR REPLACE ANY TRAFFIC SIGNS THAT ARE AFFECTED BY THIS CONSTRUCTION AS DIRECTED BY THE WAYNE COUNTY ENGINEER. 14. RELOCATE ANY EXISTING UTILITY THAT IS IN CONFLICT WITH THE PROPOSED WORK AS DIRECTED BY THE COUNTY ENGINEER AND UTILITY COMPANY REPRESENTATIVE.



GENERAL NOTES:

THESE NOTES APPLY TO ALL CONSTRUCTION ACTIVITIES ON THIS PROJECT. ALL DIMENSIONS SHOWN ARE TO BACK OF CURB, FACE OF SIDEWALK, OUTSIDE FACE OF BUILDING, PROPERTY LINE, CENTER OF MANHOLE/CATCH BASIN OR CENTERLINE OF PIPE UNLESS OTHERWISE NOTED.

- . WAYNE COUNTY ENGINEER WILL DETERMINE THE LOCATION OF ALL SIGNS THAT ARE REMOVED AND RELOCATED AS PART OF THIS PROJECT.
- REFER TO NOTES & DETAILS SHEET FOR ON-SITE PAVING DETAILS.
- REFER TO NOTES & DETAILS SHEET FOR ON-SITE SIDEWALK RAMP DETAILS

SIDEWALK RAMP LEGEND: SIDEWALK RAMP 'TYPE R' SIDEWALK RAMP 'TYPE F SIDEWALK RAMP 'TYPE P' SIDEWALK RAMP 'TYPE SIDEWALK RAMP 'TYPE D CURB DROP ONLY REFER TO LATEST MDOT RAMP AND DETECTABLE


SIGN LEGEND: REMOVED AND RELOCATE REFER TO DETAIL SHEET FOR SIGN DETAILS


<u>TRAIL PLAN-E. HURON RIVER DR.</u> STA 0+00 TO STA 4+08

NOT FOR CONSTRUCTION

PEA JOB NO.	2022-0652
P.M.	JTS
DN.	JMR
DES.	JMR
DRAWING NUMB	ER:

C-3.1






CLIENT


46425 TYLER ROAD VAN BUREN, MICHIGAN

VAN BUREN TOWNSHIP


VAN BUREN CHARTER TOWNSHI



	28 STA	NDARD DETAILS		L
⁻ R—2	28 STA	NDARD		
	\otimes			Γ
D '	D			
C '	\bigcirc			S D
P'	P			
F'	Ð			s D









- ALL DIMENSIONS SHOWN ARE TO BACK OF CURB, FACE OF SIDEWALK, OUTSIDE FACE OF BUILDING, PROPERTY LINE, CENTER OF MANHOLE/CATCH BASIN OR CENTERLINE OF PIPE UNLESS OTHERWISE NOTED.
- 2. REFER TO NOTES & DETAILS SHEET FOR ON-SITE PAVING DETAILS.
- . REFER TO NOTES & DETAILS SHEET FOR ON-SITE SIDEWALK RAMP DETAILS

SIDEWALK RAMP LEGEND: SIDEWALK RAMP 'TYPE F' SIDEWALK RAMP 'TYPE P' SIDEWALK RAMP 'TYPE C' SIDEWALK RAMP 'TYPE D' CURB DROP ONLY

SIGN LEGEND: REMOVED AND RELOCATED SIGN [] REFER TO DETAIL SHEET FOR SIGN DETAILS


NOT FOR CONSTRUCTION

PEA JOB NO.	2022-0652
P.M.	JTS
DN.	JMR
DES.	JMR
DRAWING NUMBER:	

C-3.2

DRAWING TITLE DIMENSIONAL **PAVING PLAN**

ORIGINAL ISSUE DATE: DECEMBER 12, 2022







PROJECT TITLE **IRON BELLE TRAIL** SECTION K VAN BUREN TOWNSHIP VAN BUREN, MICHIGAN



CLIENT VAN BUREN TOWNSHIP 46425 TYLER ROAD VAN BUREN, MICHIGAN








LEGEND:	
STD HEAVY R.O.W. DUTY DUTY ONLY	CONCRETE PAVEMENT
STD HEAVY DEEP DUTY DUTY STRENGTH	ASPHALT PAVEMENT
	GRAVEL
ىلتى يۇر بىلتى يۈر بىلتى	WETLAND
	CONCRETE CURB AND GUTTER
	REVERSE GUTTER PAN
	SETBACK LINE
* *	SIGN LIGHTPOLE FENCE GUARD RAIL





PIE

8+50

南


 \cap

لى

S -

9







THESE NOTES APPLY TO ALL CONSTRUCTION ACTIVITIES ON THIS PROJECT.

- ALL DIMENSIONS SHOWN ARE TO BACK OF CURB, FACE OF SIDEWALK, OUTSIDE FACE OF BUILDING, PROPERTY LINE, CENTER OF MANHOLE/CATCH BASIN OR CENTERLINE OF PIPE UNLESS OTHERWISE NOTED.
- 2. REFER TO NOTES & DETAILS SHEET FOR ON-SITE PAVING DETAILS.
- . REFER TO NOTES & DETAILS SHEET FOR ON-SITE SIDEWALK RAMP DETAILS


NOT FOR CONSTRUCTION

PEA JOB NO.	2022-0652
P.M.	JTS
DN.	JMR
DES.	JMR
DRAWING NUMBER	R:

C-3.3

DRAWING TITLE DIMENSIONAL **PAVING PLAN**

ORIGINAL ISSUE DATE: DECEMBER 12, 2022




REVISIONS ORIGINAL ISSUE 12-12-2022





PROJECT TITLE IRON BELLE TRAIL SECTION K VAN BUREN TOWNSHIP VAN BUREN, MICHIGAN




CLIENT VAN BUREN TOWNSHIP 46425 TYLER ROAD VAN BUREN, MICHIGAN












ΡΞΛ

GROUP

t: 844.813.2949


www.peagroup.com



REMOVED AND RELOCATED SIGN []

REFER TO DETAIL SHEET FOR SIGN DETAILS

SIGN LEGEND:




13+00


GENERAL NOTES:

THESE NOTES APPLY TO ALL CONSTRUCTION ACTIVITIES ON THIS PROJECT.

- 1. ALL DIMENSIONS SHOWN ARE TO BACK OF CURB, FACE OF SIDEWALK, OUTSIDE FACE OF BUILDING, PROPERTY LINE, CENTER OF MANHOLE/CATCH BASIN OR CENTERLINE OF PIPE UNLESS OTHERWISE NOTED.
- 2. REFER TO NOTES & DETAILS SHEET FOR ON-SITE PAVING DETAILS.
- 3. REFER TO NOTES & DETAILS SHEET FOR ON-SITE SIDEWALK RAMP DETAILS

SIDEWALK RAMP LEGEND: SIDEWALK RAMP 'TYPE R' R SIDEWALK RAMP 'TYPE F' F SIDEWALK RAMP 'TYPE P' P SIDEWALK RAMP 'TYPE C' CO SIDEWALK RAMP 'TYPE D' D CURB DROP ONLY REFER TO LATEST MDOT R-28 STANDARD RAMP AND DETECTABLE WARNING DETAILS






BENCHMARKS (GPS DERIVED - NAVD88)

BM #300 TOP OF SANITARY MANHOLE, 58 FEET SOUTH OF THE CENTER LINE OF EAST HURON RIVER DR. AND 45 FEET WEST OF THE CENTER LINE OF HAGGERTY RD. ELEV. - 656.26

BM #301 MAG NAIL IN THE NORTH FACE OF A POWER POLE LOCATED AT THE SOUTH CORNER OF HURON RIVER DR & HAGGERTY RD/METRO PKWY. ELEV. – 652.80

SYMBOLS: EROSION CONTROL - I SILT FENCE (REFER TO DETAIL ON SHEET C-6.1 SHEET) INLET FILTER (REFER TO DETAIL ON SHEET C-6.1 SHEET) APPROXIMATE SEEDING RESTORATION LOCATIONS LIMITS OF DISTURBANCE

- GENERAL SITE CONDITIONS:
- . TOTAL DISTURBED AREA = \pm 0.48 ACRES
- SOIL EROSION CONTROL NOTES:
- ALL EROSION AND SEDIMENT CONTROL WORK SHALL CONFORM TO STANDARDS AND SPECIFICATIONS OF THE WAYNE COUNTY.
- DAILY INSPECTIONS SHALL BE MADE BY THE CONTRACTOR FOR EFFECTIVENESS OF EROSION AND SEDIMENTATION CONTROL MEASURES, AND ANY REPAIRS SHALL BE PERFORMED WITHOUT
- EROSION AND ANY SEDIMENTATION FROM WORK ON THIS SITE SHALL BE CONTAINED ON THE SITE AND NOT ALLOWED TO COLLECT ON ANY OFF-SITE AREAS OR IN WATERWAYS. WATERWAYS INCLUDE BOTH NATURAL AND MAN-MADE OPEN DITCHES, STREAMS, STORM DRAINS, LAKES AND PONDS.
- CONTRACTOR SHALL APPLY TEMPORARY EROSION AND SEDIMENTATION CONTROL MEASURES WHEN REQUIRED AND AS DIRECTED ON THESE PLANS. REMOVE TEMPORARY MEASURES AS SOON AS PERMANENT STABILIZATION OF SLOPES, DITCHES, AND OTHER EARTH CHANGES HAVE BEEN ACCOMPLISHED AND A CERTIFICATE OF COMPLETION HAS BEEN ISSUED BY THE WAYNE COUNTY FOR THE SESC PERMIT.
- STAGING THE WORK SHALL BE DONE BY THE CONTRACTOR AS DIRECTED IN THESE PLANS AND AS REQUIRED TO ENSURE PROGRESSIVE STABILIZATION OF DISTURBED EARTH.
- SOIL EROSION CONTROL PRACTICES SHALL BE ESTABLISHED IN EARLY STAGES OF CONSTRUCTION BY THE CONTRACTOR. SEDIMENT CONTROL PRACTICES SHALL BE APPLIED AS A PERIMETER DEFENSE AGAINST ANY TRANSPORTING OF SILT OFF THE SITE.



SOIL EROSION MAINTENANCE SCHEDULE AND NOTES:

THE CONTRACTOR SHALL INSPECT THE SOIL EROSION AND SEDIMENTATION CONTROL DEVICES ONCE EACH WEEK AND/OR WITHIN 24 HOURS OF A RAINFALL EVENT WHICH RESULTS IN A STORM WATER DISCHARGE FROM THE SITE. THE FOLLOWING STEPS SHALL BE IMPLEMENTED IF ANY DAMAGE HAS OCCURRED.

ANY DEBRIS OR DIRT ON ANY PAVED AREA RESULTING FROM CONSTRUCTION TRAFFIC SHALL BE CLEANED IN A PROMPT MANNER BY THE CONTRACTOR. THE CONSTRUCTION DRIVE SHALL BE CLEANED AT THE END OF EACH DAY. ALL DIRT AND MUD TRACKED ONTO PAVED AREAS SHALL BE REMOVED DAILY BY SCRAPING. STREET SWEEPING IS REQUIRED WEEKLY.

3. SILT FENCE MAINTENANCE SHALL INCLUDE THE REMOVAL OF ANY BUILT UP SEDIMENT WHEN THE SEDIMENT HEIGHT ACCUMULATES TO 1/3 TO 1/2 OF THE HEIGHT OF THE FENCE. THE CONTRACTOR IS RESPONSIBLE TO REMOVE, REPLACE, RETRENCH OR REBACKFILL THE SILTATION FENCE SHOULD IT FALL OR BE DAMAGED DURING CONSTRUCTION.

INLET FILTER MAINTENANCE SHALL INCLUDE THE REMOVAL OF ANY ACCUMULATED SILT OR OTHER DEBRIS. THE REMOVAL OF SILT SHOULD BE WITH THE USE OF A STIFF BRISTLE BROOM OR SQUARE POINT SHOVEL. IF INLET FILTERS CAN NOT BE CLEANED OR ARE DAMAGED, THEN THE FABRIC MUST BE REPLACED.

A WATER TRUCK SHALL BE AVAILABLE TO WATER DOWN THE SITE ON A DAILY BASIS AS REQUIRED TO MAINTAIN DUST CONTROL.

STREET CLEANING SCHEDULE

	SUNDAY	MONDAY	TUESDAY	WEDNESDAY	THURSDAY	FRIDAY	SATURDAY
SCRAPE STREETS		×	×	×	×	×	×
SWEEP STREETS				×			

TRAIL PLAN-E. HURON RIVER DR. STA 0+00 TO STA 4+08


NOT FOR CONSTRUCTION

PEA JOB NO.	2022-0652
P.M.	JTS
DN.	JMR
DES.	JMR
DRAWING NUMBER:	

C-4.1

DRAWING TITLE **GRADING PLAN**


ORIGINAL ISSUE DATE: DECEMBER 12, 2022







PROJECT TITLE **IRON BELLE TRAIL** SECTION K VAN BUREN TOWNSHIF


VAN BUREN, MICHIGAN




CLIENT VAN BUREN TOWNSHIP

































PΞΛ

GROUP

t: 844.813.2949

www.peagroup.com

EARTHWORK BALANCING NOTE: THE CONTRACTOR SHALL BE RESPONSIBLE FOR IMPORTING OR EXPORTING ALL MATERIALS AS REQUIRED TO PROPERLY GRADE THIS PROJECT TO THE FINISHED ELEVATIONS SHOWN ON THE APPROVED PLANS. THE CONTRACTOR SHALL MAKE THEIR OWN DETERMINATION OF CUT AND FILL QUANTITIES AND ALLOW FOR REMOVAL OF EXCESS OR IMPORTATION OF ADDITIONAL MATERIAL AT NO ADDITIONAL COST TO THE OWNER.

T/S = TOP OF SIDEWALK RIM = RIM ELEVATION T/W = TOP OF WALL B/W = BOTTOM OF WALL REFER TO GRADING NOTES ON SHEET C-1.1.

ABBREVIATIONS G = GUTTER GRADE T/C = TOP OF CURB T/P = TOP OF PAVEMENT F.G. = FINISH GRADE

GRADING LEGEND:

EXISTING SPOT ELEVATION PROPOSED SPOT ELEVATION: TYPICALLY TOP OF PAVEMENT IN PAVED AREAS, GUTTER GRADE IN CURB LINES. - EXISTING CONTOUR PROPOSED REVERSE GUTTER PAN - - - - PROPOSED RIDGE LINE ----- PROPOSED SWALE/DITCH

622.50 ----670--

ĹIJ

ΥĘ

ر کر م

CATCH BASIN INSERTS AT ALL CATCH BASINS, INLETS AND YARD DRAINS. SEE DETAIL SHEET C-5.2.

4+00

EROSION CONTROL QUANTITIES: AREA DISTURBED = .71 AC. 1655 LF 5 EA. 3" TOPSOIL, SEED & MULCH 1855 S.Y

FINAL INSPECTION AND CERTIFICATE OF

ALL ITEMS ON APPROVED SESC PLAN AND PERMIT

ALL DISTURBED EARTH MUST BE PERMANENTLY

STABILIZED WITH VEGETATION OR HARD SURFACE.

ACCUMULATED SEDIMENT MUST BE REMOVED FROM

ACCUMULATED SEDIMENT MUST BE REMOVED FROM

ALL TEMPORARY SESC DEVICES MAY BE REMOVED

THE ENTIRE STORM SEWER SYSTEM.

AFTER CERTIFICATE OF COMPLETION.

COMPLETION REQUIREMENTS:

THE SEDIMENTATION BASIN.

MUST BE COMPLETED.

SILT FENCE

INLET FILTERS


BENCHMARKS (GPS DERIVED - NAVD88)


BM #300 TOP OF SANITARY MANHOLE, 58 FEET SOUTH OF THE CENTER LINE OF EAST HURON RIVER DR. AND 45 FEET WEST OF THE CENTER LINE OF HAGGERTY RD. ELEV. - 656.26

BM #301

MAG NAIL IN THE NORTH FACE OF A POWER POLE LOCATED AT THE SOUTH CORNER OF HURON RIVER DR & HAGGERTY RD/METRO PKWY. ELEV. – 652.80

SYMBOLS: EROSION CONTROL





NOT FOR CONSTRUCTION

PEA JOB NO.	2022-0652
P.M.	JTS
DN.	JMR
DES.	JMR
DRAWING NUMBER:	

C-4.2

DECEMBER 12, 2022 DRAWING TITLE **GRADING PLAN**

ORIGINAL ISSUE DATE:


REVISIONS ORIGINAL ISSUE 12-12-2022 REVISED PER TOWNSHIP 8-8-2023 REVISED PER WC REVIEW 8-24-2023




PROJECT TITLE **IRON BELLE TRAIL** SECTION K VAN BUREN TOWNSHIP



CLIENT





THE CONTRACTOR SHALL BE RESPONSIBLE FOR IMPORTING OR EXPORTING ALL MATERIALS AS REQUIRED TO PROPERLY GRADE THIS PROJECT TO THE FINISHED ELEVATIONS SHOWN ON THE APPROVED PLANS. THE CONTRACTOR SHALL MAKE THEIR OWN DETERMINATION OF CUT AND FILL QUANTITIES AND ALLOW FOR REMOVAL OF EXCESS OR IMPORTATION OF ADDITIONAL MATERIAL AT NO ADDITIONAL COST TO THE OWNER.

REFER TO GRADING NOTES ON SHEET C-1.1.

EARTHWORK BALANCING NOTE:

GRADING LEGEND: EXISTING SPOT ELEVATION PROPOSED SPOT ELEVATION: 622.50 PROPOSED SPOT ELEVATION: TYPICALLY TOP OF PAVEMENT IN PAVED AREAS, GUTTER GRADE IN CURB LINES. _____670____ EXISTING CONTOUR PROPOSED REVERSE GUTTER PAN – – – – – PROPOSED RIDGE LINE ----- PROPOSED SWALE/DITCH ABBREVIATIONS G = GUTTER GRADE T/C = TOP OF CURB T/P = TOP OF PAVEMENT F.G. = FINISH GRADE T/S = TOP OF SIDEWALK RIM = RIM ELEVATION

T/W = TOP OF WALL B/W = BOTTOM OF WALL






MATCH


BENCHMARKS (GPS DERIVED - NAVD88)


BM #300 TOP OF SANITARY MANHOLE, 58 FEET SOUTH OF THE CENTER LINE OF EAST HURON RIVER DR. AND 45 FEET WEST OF THE CENTER LINE OF HAGGERTY RD. ELEV. — 656.26

BM #301 MAG NAIL IN THE NORTH FACE OF A POWER POLE LOCATED AT THE SOUTH CORNER OF HURON RIVER DR & HAGGERTY RD/METRO PKWY. ELEV. — 652.80

SYMBOLS: EROSION CONTROL








TRAIL PLAN-E. HURON RIVER DR. STA 8+59 TO STA 13+00

NOT FOR CONSTRUCTION

PEA JOB NO.	2022-0652
P.M.	JTS
DN.	JMR
DES.	JMR
DRAWING NUMBER:	
C-4	.3


DRAWING TITLE **GRADING PLAN**

ORIGINAL ISSUE DATE: DECEMBER 12, 2022







PROJECT TITLE IRON BELLE TRAIL SECTION K VAN BUREN TOWNSHIP VAN BUREN, MICHIGAN



CLIENT VAN BUREN TOWNSHIP 46425 TYLER ROAD VAN BUREN, MICHIGAN







THE CONTRACTOR SHALL BE RESPONSIBLE FOR IMPORTING OR EXPORTING ALL MATERIALS AS REQUIRED TO PROPERLY GRADE THIS PROJECT TO THE FINISHED ELEVATIONS SHOWN ON THE APPROVED PLANS. THE CONTRACTOR SHALL MAKE THEIR OWN DETERMINATION OF CUT AND FILL QUANTITIES AND ALLOW FOR REMOVAL OF EXCESS OR IMPORTATION OF ADDITIONAL MATERIAL AT NO ADDITIONAL COST TO THE OWNER.

13+00

T/W = TOP OF WALL B/W = BOTTOM OF WALL REFER TO GRADING NOTES ON SHEET C-1.1. EARTHWORK BALANCING NOTE:

GRADING LEGEND:

622.50

PROPOSED REVERSE GUTTER PAN – – – – – PROPOSED RIDGE LINE ----- PROPOSED SWALE/DITCH ABBREVIATIONS T/C = TOP OF CURB G = GUTTER GRADE T/P = TOP OF PAVEMENT F.G. = FINISH GRADE T/S = TOP OF SIDEWALK RIM = RIM ELEVATION

IN CURB LINES.

-----670------ EXISTING CONTOUR

EXISTING SPOT ELEVATION PROPOSED SPOT ELEVATION: TYPICALLY TOP OF PAVEMENT IN PAVED AREAS, GUTTER GRADE



BENCHMARKS

(GPS DERIVED - NAVD88)

BM #300 TOP OF SANITARY MANHOLE, 58 FEET SOUTH OF THE CENTER LINE OF EAST HURON RIVER DR. AND 45 FEET WEST OF THE CENTER LINE OF HAGGERTY RD. ELEV. — 656.26

BM #301 MAG NAIL IN THE NORTH FACE OF A POWER POLE LOCATED AT THE SOUTH CORNER OF HURON RIVER DR & HAGGERTY RD/METRO PKWY. ELEV. — 652.80

SYMBOLS: EROSION CONTROL SILT FENCE

 LIMITS OF DISTURBANCE
APPROXIMATE SEEDING RESTORATION LOCATIONS
INLET FILTER (REFER TO DETAIL ON SHEET C-6.1 SHEET)
 (REFER TO DETAIL ON SHEET C-6.1 SHEET)

GRADING LEGEND:

×090.01	EXISTIN	IG SPOT ELEVATION	
¥ 622.50	TYPICA IN PAVE	SED SPOT ELEVATION: LLY TOP OF PAVEMENT ED AREAS, GUTTER GRADE 3 LINES.	
670	EXISTIN	EXISTING CONTOUR	
922	- PROPO	SED CONTOUR	
	PROPO	SED REVERSE GUTTER PAN	
	- PROPO	SED RIDGE LINE	
	PROPOSED SWALE/DITCH		
ABBREVIATIONS			
T/C = TOP OF CURBG = GUTTER GRADET/P = TOP OF PAVEMENTF.G. = FINISH GRADET/S = TOP OF SIDEWALKRIM = RIM ELEVATIONT/W = TOP OF WALLB/W = BOTTOM OF WALL			
REFER TO GRADING NOTES ON SHEET C-1.1.			


EARTHWORK BALANCING NOTE:


THE CONTRACTOR SHALL BE RESPONSIBLE FOR IMPORTING OR EXPORTING ALL MATERIALS AS REQUIRED TO PROPERLY GRADE THIS PROJECT TO THE FINISHED ELEVATIONS SHOWN ON THE APPROVED PLANS. THE CONTRACTOR SHALL MAKE THEIR OWN DETERMINATION OF CUT AND FILL QUANTITIES AND ALLOW FOR REMOVAL OF EXCESS OR IMPORTATION OF ADDITIONAL MATERIAL AT NO ADDITIONAL COST TO THE OWNER.

RETAINING WALL NOTE: TOP OF WALL (T/W) AND BOTTOM OF WALL (B/W) GRADES ARE THE FINISH GRADE AT THE TOP AND BOTTOM OF THE RETAINING WALL, NOT ACTUAL TOP AND BOTTOM OF THE WALL STRUCTURE.

REFER TO GRADING NOTES ON SHEET C-1.1

JN METRO AUTHORITY √0. 83 096 99 0022 000





TRAIL PLAN-E. HURON RIVER DR. STA 15+00 TO STA 20+00

NOT FOR CONSTRUCTION

BM #300 BENCH TIE IN THE WEST SIDE OF A 24" TREE, LOCATED APPROX. 100' EAST FROM THE CENTERLINE OF S. METRO PKWY & APPROX. 500' NORTH FROM GAS SUB-STATION,. ELEV. - 656.45 BM #301 MAG NAIL IN THE NORTH FACE OF A POLWER POLE LOCATED AT THE SOUTH CORNER OF HURON RIVER DR & HAGGERTY RD/METRO PKWY. ELEV. – 652.80

BENCHMARKS (GPS DERIVED - NAVD88)

PEA JOB NO.	2022-0652
P.M.	JTS
DN.	JMR
DES.	JMR
DRAWING NUMBER:	

C-4.4

DRAWING TITLE **GRADING PLAN**

ORIGINAL ISSUE DATE: DECEMBER 12, 2022

ORIGINAL ISSUE 12-12-2022 REVISED PER TOWNSHIP 8-8-2023 REVISED PER WC REVIEW 8-24-2023


REVISIONS





IRON BELLE TRAIL SECTION K VAN BUREN TOWNSHIP




CLIENT VAN BUREN TOWNSHIP 46425 TYLER ROAD VAN BUREN, MICHIGAN

















US PATENT D 620,999, OTHER PATENTS PENDING

INLET PROTECTION SHALL BE INSTALLED AT THE TIME THE STRUCTURE IS SET.
 TO INSTALL; TUCK FABRIC UNDER GRATE.
 REMOVE SEDIMENT IF IT ACCUMULATES TO ONE HALF THE HEIGHT OF THE SedCage[®]
 THE AREA AROUND THE SedCage[®] SHOULD BE AS FLAT AS POSSIBLE TO INCREASE EFFECTIVENESS AND REDUCE

MAINTENANCE REQUIREMENTS. 5. AS WITH ALL INLET PROTECTION DEVICES, CHECK TO SEE HOW DEEP THE WATER COULD RISE IF THE INLET WERE BLOCKED ENTIRELY. DO NOT INSTALL IN LOCATIONS THAT COULD CAUSE PROPERTY DAMAGE OR POSE A SAFETY HAZARD TO TRAFFIC.

IZING INSTRUCTIONS:	

OOD WATER	CLEAR	OPENING:

"	SedCage	230 sq.in.
39	SedCage	515 sq.in.
39	SedCage	1075 sq.in.
	SadCago	1320 og in

SedCatch® Environmental Products www.SedCatch.com

8" MDOT 21AA LIMESTONE COURSE COMPACTED TO 95% MAX. DRY UNIT		
PROOF-ROLLED/COMPACTED SUBGRADE OR ENGINEERED FILL COMPACTED TO 95% OF MAX. DRY UNIT WEIGHT PER ASTM D-1557.		
GRAVEL SHOULDER SECTION DETAIL NOT TO SCALE		

PEA JOB NO.	2021-0108
P.M.	JS
DN.	JMR
DES.	JMR
DRAWING NUMBER	

C-5.2