

GENERAL LANDSCAPE NOTES:

A. PLANT TREES AND SHRUBS GENERALLY NO CLOSER THAN THE FOLLOWING DISTANCES APART OR WORK WITH ARCHITECT TO HAVE SPACING REFLECT THE DESIGN INTENT AS SHOWN ON THE PLAN:

SHADE TREES:	20' O.C. MIN.
SHRUBS:	SPACED TO CREATE SCREEN/BUFFER. SEE PLAN.
ORNAMENTAL & EVERGREEN TREES (CRAB, PINE, SPRUCE)	10' 0.C. MIN.

- B. DIG SHRUB PITS 1'-0" LARGER THAN THE SHRUB ROOT BALLS. TREE PITS 2'-0" LARGER THAN THE ROOT BALLS. BACK FILL W/ 1 PART TOPSOIL - 1 PART SOIL FROM EXCAVATED PLANT HOLES.
- C. REMOVE ALL TWINE, WIRE, AND BURLAP FROM TOP OF ALL SHRUB EARTH BALLS AND TREE TRUNKS
- D. LAWN TREES TO BE MULCHED W/ 2'-0" WIDE BY 6" MINIMUM SHREDDED BARK RING OR APPROVED ALTERNATE DESIGN FOR TREE TRUNK PROTECTION.
- E. ALL LANDSCAPE BEDS TO BE MULCHED WITH 4" OF SHREDDED WOOD MULCH AND BORDERED WITH METAL LANDSCAPE EDGING.
- F. INSTALLATION OF PLANT MATERIAL SHALL BE IN ACCORDANCE WITH THE AMERICAN ASSOCIATION OF NURSERYMEN LANDSCAPE STANDARDS AND WITH THE GENERAL PLANTING SPECIFICATIONS AS SET FORTH BY THE CITY OF FERNDALE DEPARTMENT OF PUBLIC SERVICES.
- G. ALL TREES TO BE STAKED, WRAPPED, AND MULCHED ACCORDING TO CITY STANDARDS.
- H. ALL ERICACIOUS PLANT MATERIAL AND OTHER ACID LOVING PLANTS SHALL BE PLANTED IN PLANTING MIX OF 1 PART TOPSOIL - 1 PART PEAT.
- I. ALL LAWN AREAS TO BE FINE GRADED AND TOP DRESSED WITH 3" OF TOP SOIL BEFORE SODDING.
- J. ALL QUANTITIES ON PLANS HAVE BEEN FIGURED AS CLOSELY AS POSSIBLE. IT REMAINS THE RESPONSIBILITY OF THE LANDSCAPE CONTRACTOR TO COMPLETE THE PROJECT AS INDICATED ON THE DRAWINGS.
- K. ALL GROUND COVER BEDS SHALL RECEIVE 3" OF PLANT MIX (1/3 TOPSOIL, 1/3 SAND, 1/3 PEAT) ROTOTILLED INTO THE UPPER 6" OF SOIL, MULCH WITH 2" OF MICHIGAN PEAT MULCH.
- ALL LAWN/LANDSCAPING AREAS HAVE AN EXISTING IRRIGATION SYSTEM. M. PLANTS SHALL BE WATERED/IRRIGATED AS NECESSARY TO
- PROMOTE PROPER AND HEALTHY PLANT GROWTH. GC IS RESPONSIBLE TO DO SO UNTIL THE PROJECT IS COMPLETED AND OFFICIALLY TURNED OVER TO THE OWNER.
- N. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORING AREAS DISTURBED DURING CONSTRUCTION, NOT IN THE CONTRACT LIMITS, T EQUAL OR GREATER CONDITION.
- 0. ALL LANDSCAPE AREAS SHALL HAVE PROPER DRAINAGE THAT PREVENTS EXCESSIVE WATER FROM PONDING ON LAWN AREAS OR AROUND TREES/SHRUBS.

SHRUBS					
TAG	COMMON NAME	BOTANICAL NAME	PLANTING SIZE	MATURE SIZE	QUANTITY
JS	WHITE GOLD JAPANESE SPIRAEA	SPIRAEA JAPONICA	2' - 0' HT	3' - 0' HT	
ОН	OAKLEAF HYDRANGEA	HYDRANGEA QUERCIFOLIA	2' - 0' HT	10' - 0' HT	-
PL	SIEBOLD'S PLANTAIN LILY	HOSTA SIEBOLDIANA	1' - 0' HT	2' - 6' HT	-
тв	THREADLEAF BLUESTAR	AMSONIA HUBRICHTII	2' - 0' HT	4' - 5' HT	-
НҮ	HICKS YEW	TAXUS X MEDIA HICKSII	2' - 6' HT	18' - 0' HT	-

LANDSCAPE KEYNOTES:

(1) NEW LAWN/LANDSCAPING AREAS TO RECEIVE NEW LANDSCAPING AND \smile MULCH. MODIFY THE EXISTING LAWN IRRIGATION SYSTEM AS REQUIRED.

TOTAL:

(2) EXISTING LAWN/LANDSCAPING AREA TO REMAIN.

 $\sim \sim \sim$

(3) EXISTING LAWN/LANDSCAPING AREA TO BE REMOVED FOR NEW BUILDING ADDITIONS. REMOVE AND CAP ALL EXISTING IRRIGATION LINES AS REQUIRED.

(4) EXISTING MAIN IRRIGATION LINE TO BE RELOCATED TO THE EAST OF THE NEW BUILDING ADDITION. REMOVE AND PROVIDE NEW SPRINKLER LINE AND HEADS AS REQUIRED FOR NEW LANDSCAPING.



Corporate Headquarters 45650 Grand River Ave. Novi, Michigan 48374 Ph: (248)349-4500 • Fax: (248)349-1429

Novi • Wyandotte • Muskegon Lansing • Gaylord • Sault Ste. Marie Williamsport, PA • Tampa, FL www.sidockgroup.com

Client: Brownstown Township

Project:

Brownstown Community Center Rennovation & Addition


21311 Telegraph Rd. Brownstown, MI

Seal:

ate	Issued For
3/09/2025	DESIGN DEVELOPMENT
1/05/2024	PROGRESS SET
2/09/2024	90% OWNER REVIEW
2/20/2024	100% CD
1/07/2025	IFC
/21/2025	ADDENDUM 2

Drawn:	AM/KN/NC
Checked:	KN
Approved:	MR

Sheet Title: LANDSCAPE PLAN



L-100 Sheet Number: THIS MATERIAL IS THE EXCLUSIVE PROPERTY OF SIDOCK GROUP, INC. AND CANNOT BE REPRODUCED, COPIED, OR USED IN ANY MANNER WITHOUT THE PRIOR WRITTEN CONSENT OF SIDOCK GROUP, INC. ① 2024