50% CONSTRUCTION DOCUMENTS APRIL 11, 2025 FRAMEWORK E, LLC PROJ. NO. 2024007

PROJECT MANUAL

LAHC

WORKFORCE EDUCATION RESOURCE & DEVELOPMENT CENTER

5273 KENILWORTH ~ DEARBORN, MICHIGAN

DETROIT, MI 48210



ARCHITECT: FRAMEWORK E, LLC 155 W CONGRESS ST ~ SUITE 602 DETROIT, MI 48226

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025 FRAMEWORK E, LLC PROJ. NO. 2024007

END OF SECTION 000101

THIS PAGE INTENTIONALLY LEFT BLANK

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 000110 TABLE OF CONTENTS

PROCUREMENT AND CONTRACTING REQUIREMENTS

1.01 DIVISION 00 -- PROCUREMENT AND CONTRACTING REQUIREMENTS

- A. 000101 Project Title Page
- B. 000110 Table of Contents
- C. 004325 Substitution Request Form During Procurement
- D. 006325 Substitution Request Form During Construction

SPECIFICATIONS

2.01 DIVISION 01 -- GENERAL REQUIREMENTS

- A. 011000 Summary
- B. 012000 Price and Payment Procedures
- C. 012500 Substitution Procedures
- D. 013000 Administrative Requirements
- E. 013216 Construction Progress Schedule
- F. 013553 Security Procedures
- G. 014000 Quality Requirements
- H. 015000 Temporary Facilities and Controls
- I. 016000 Product Requirements
- J. 016116 Volatile Organic Compound (VOC) Content Restrictions
- K. 017000 Execution and Closeout Requirements
- L. 017419 Construction Waste Management and Disposal
- M. 017800 Closeout Submittals

2.02 DIVISION 02 -- EXISTING CONDITIONS

A. 024100 - Demolition

2.03 DIVISION 03 -- CONCRETE

A. 031000 - Concrete Forming and Accessories

2.04 DIVISION 04 -- MASONRY

- A. 042000 Unit Masonry
- B. 047200 Cast Stone Masonry

2.05 DIVISION 05 -- METALS

- A. 051200 Structural Steel Framing
- B. 052100 Steel Joist Framing
- C. 053100 Steel Deck
- D. 054000 Cold-Formed Metal Framing
- E. 055000 Metal Fabrications
- F. 055100 Metal Stairs
- G. 055133 Metal Ladders
- H. 055213 Pipe and Tube Railings

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

2.06 DIVISION 06 -- WOOD, PLASTICS, AND COMPOSITES

- A. 061000 Rough Carpentry
- B. 061600 Sheathing
- C. 064100 Architectural Wood Casework

2.07 DIVISION 07 -- THERMAL AND MOISTURE PROTECTION

- A. 072100 Thermal Insulation
- B. 072700 Air Barriers
- C. 075300 Elastomeric Membrane Roofing
- D. 076200 Sheet Metal Flashing and Trim
- E. 077100 Roof Specialties
- F. 077200 Roof Accessories
- G. 079100 Preformed Joint Seals
- H. 079200 Joint Sealants
- I. 079513 Expansion Joint Cover Assemblies

2.08 DIVISION 08 -- OPENINGS

- A. 080671 Door Hardware Schedule
- B. 081113 Hollow Metal Doors and Frames
- C. 081416 Flush Wood Doors
- D. 083100 Access Doors and Panels
- E. 084313 Aluminum-Framed Storefronts
- F. 084435 Protective Framed Glazing Assemblies
- G. 087100 Door Hardware
- H. 088000 Glazing
- I. 088813 Fire-Rated Glazing

2.09 DIVISION 09 -- FINISHES

- A. 092116 Gypsum Board Assemblies
- B. 092216 Non-Structural Metal Framing
- C. 093000 Tiling
- D. 095100 Acoustical Ceilings
- E. 096500 Resilient Flooring
- F. 096813 Tile Carpeting
- G. 099123 Interior Painting

2.10 DIVISION 10 -- SPECIALTIES

- A. 102800 Toilet, Bath, and Laundry Accessories
- B. 104400 Fire Protection Specialties

2.11 DIVISION 11 -- EQUIPMENT

2.12 DIVISION 12 -- FURNISHINGS

A. 123600 - Countertops

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- 2.13 DIVISION 13 -- SPECIAL CONSTRUCTION
- 2.14 DIVISION 14 -- CONVEYING EQUIPMENT
- 2.15 DIVISION 21 -- FIRE SUPPRESSION
- 2.16 DIVISION 22 -- PLUMBING
- 2.17 DIVISION 23 -- HEATING, VENTILATING, AND AIR-CONDITIONING (HVAC)
- 2.18 DIVISION 25 -- INTEGRATED AUTOMATION
- 2.19 DIVISION 26 -- ELECTRICAL
- 2.20 DIVISION 27 -- COMMUNICATIONS
- 2.21 DIVISION 28 -- ELECTRONIC SAFETY AND SECURITY
- 2.22 DIVISION 31 -- EARTHWORK
- 2.23 DIVISION 32 -- EXTERIOR IMPROVEMENTS
 - A. 323113 Chain Link Fences and Gates
- 2.24 DIVISION 33 -- UTILITIES
- 2.25 DIVISION 34 -- TRANSPORTATION
- 2.26 DIVISION 40 -- PROCESS INTEGRATION
- 2.27 DIVISION 46 -- WATER AND WASTEWATER EQUIPMENT

APPENDIX A -- LAHC WALL PAC LIGHTING CUTSHEET

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 004325 SUBSTITUTION REQUEST FORM - DURING PROCUREMENT END OF SECTION 004325

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

Substitution Request Form - During Procurement

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 006325 SUBSTITUTION REQUEST FORM - DURING CONSTRUCTION END OF SECTION 006325

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

Substitution Request Form - During Construction

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 011000 SUMMARY

PART 1 GENERAL

1.01 PROJECT

- A. Project Name: LAHC Workforce Education Resource and Development Center.
- B. Owner's Name: Leaders Advancing and Helping Communities, Inc. .
- C. Architect's Name: Framework E, LLC.
- D. The Project consists of the demolition of the Rectory Building and construction of a new 6500sf work force development building called the New LAHC Workforce Development Annex.

1.02 CONTRACT DESCRIPTION

A. Contract Type: A single prime contract based on a Stipulated Price as described in Document 005200 - Agreement Form.

1.03 DESCRIPTION OF ALTERATIONS WORK

- A. Scope of demolition and removal work is indicated on drawings and specified in Section 024100.
- B. Scope of alterations work is indicated on drawings.
- C. Plumbing: Alter existing system and add new construction, keeping existing in operation.
- D. HVAC: Alter existing system and add new construction, keeping existing in operation.
- E. Electrical Power and Lighting: Alter existing system and add new construction, keeping existing in operation.
- F. Fire Alarm: Alter existing system and add new construction, keeping existing in operation.
- G. Security System: Alter existing system and add new construction, keeping existing in operation.

1.04 OWNER OCCUPANCY

- A. Owner intends to continue to occupy adjacent portions of the existing building during the entire construction period.
- B. Owner intends to occupy the Project upon Substantial Completion.
- C. Cooperate with Owner to minimize conflict and to facilitate Owner's operations.
- D. Schedule the Work to accommodate Owner occupancy.

1.05 CONTRACTOR USE OF SITE AND PREMISES

- A. Arrange use of site and premises to allow:
 - 1. Owner occupancy.
 - 2. Work by Owner.
 - 3. Use of site and premises by the public.
- B. Provide access to and from site as required by law and by Owner:
 - 1. Emergency Building Exits During Construction: Keep all exits required by code open during construction period; provide temporary exit signs if exit routes are temporarily altered.
 - 2. Do not obstruct roadways, sidewalks, or other public ways without permit.
- C. Existing building spaces may not be used for storage.
- D. Utility Outages and Shutdown:
 - 1. Limit disruption of utility services to hours the building is unoccupied.
 - 2. Prevent accidental disruption of utility services to other facilities.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

1.06 SPECIFICATION SECTIONS APPLICABLE TO EVERY CONTRACT

- A. Unless otherwise noted, provisions of the sections listed below apply to every contract. Specific items of work listed under individual contract descriptions constitute exceptions.
- B. Section 012500 Substitution Procedures.
- C. Section 013000 Administrative Requirements.
- D. Section 014000 Quality Requirements.
- E. Section 015000 Temporary Facilities and Controls.
- F. Section 016000 Product Requirements.
- G. Section 017800 Closeout Submittals.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION - NOT USED

END OF SECTION 011000

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 012000 PRICE AND PAYMENT PROCEDURES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Procedures for preparation and submittal of applications for progress payments.

1.02 SCHEDULE OF VALUES

- A. Electronic media printout including equivalent information will be considered in lieu of standard form specified; submit draft to Architect for approval.
- B. Forms filled out by hand will not be accepted.
- C. Submit Schedule of Values in duplicate within 15 days after date of Owner-Contractor Agreement.
- D. Format: Utilize the Table of Contents of this Project Manual. Identify each line item with number and title of the specification section. Identify site mobilization.
- E. Include in each line item, the amount of Allowances specified in this section. For unit cost Allowances, identify quantities taken from Contract Documents multiplied by the unit cost to achieve the total for the item.
- F. Include separately from each line item, a direct proportional amount of Contractor's overhead and profit.
- G. Revise schedule to list approved Change Orders, with each Application For Payment.

1.03 APPLICATIONS FOR PROGRESS PAYMENTS

- A. Payment Period: Submit at intervals stipulated in the Agreement.
- B. Electronic media printout including equivalent information will be considered in lieu of standard form specified; submit sample to Architect for approval.
- C. Forms filled out by hand will not be accepted.
- D. For each item, provide a column for listing each of the following:
 - 1. Item Number.
 - 2. Description of work.
 - 3. Scheduled Values.
 - 4. Previous Applications.
 - 5. Work in Place and Stored Materials under this Application.
 - 6. Authorized Change Orders.
 - 7. Total Completed and Stored to Date of Application.
 - 8. Percentage of Completion.
 - 9. Balance to Finish.
 - 10. Retainage.
- E. Execute certification by signature of authorized officer.
- F. Use data from approved Schedule of Values. Provide dollar value in each column for each line item for portion of work performed and for stored products.
- G. List each authorized Change Order as a separate line item, listing Change Order number and dollar amount as for an original item of work.
- H. Submit one electronic and three hard-copies of each Application for Payment.
- I. Include the following with the application:
 - 1. Transmittal letter as specified for submittals in Section 013000.
 - 2. Construction progress schedule, revised and current as specified in Section 013000.
 - 3. Current construction photographs specified in Section 013000.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- 4. Partial release of liens from major subcontractors and vendors.
- 5. Project record documents as specified in Section 017800, for review by Owner which will be returned to the Contractor.
- 6. Affidavits attesting to off-site stored products.
- J. When Architect requires substantiating information, submit data justifying dollar amounts in question. Provide one copy of data with cover letter for each copy of submittal. Show application number and date, and line item by number and description.

1.04 MODIFICATION PROCEDURES

- A. Submit name of the individual authorized to receive change documents and who will be responsible for informing others in Contractor's employ or subcontractors of changes to Contract Documents.
- B. For minor changes not involving an adjustment to the Contract Sum or Contract Time, Architect will issue instructions directly to Contractor.
- C. For other required changes, Architect will issue a document signed by Owner instructing Contractor to proceed with the change, for subsequent inclusion in a Change Order.
 - 1. The document will describe the required changes and will designate method of determining any change in Contract Sum or Contract Time.
 - 2. Promptly execute the change.
- D. For changes for which advance pricing is desired, Architect will issue a document that includes a detailed description of a proposed change with supplementary or revised drawings and specifications, a change in Contract Time for executing the change with a stipulation of any overtime work required and the period of time during which the requested price will be considered valid. Contractor shall prepare and submit a maximum price quotation within 6 days.
- E. Contractor may propose a change by submitting a request for change to Architect, describing the proposed change and its full effect on the work, with a statement describing the reason for the change, and the effect on the Contract Sum and Contract Time with full documentation. Document any requested substitutions in accordance with Section 016000.
- F. Computation of Change in Contract Amount: As specified in the Agreement and Conditions of the Contract.
 - 1. For change requested by Architect for work falling under a fixed price contract, the amount will be based on Contractor's price quotation.
 - 2. For change requested by Contractor, the amount will be based on the Contractor's request for a Change Order as approved by Architect.
 - 3. For pre-determined unit prices and quantities, the amount will based on the fixed unit prices.
- G. Substantiation of Costs: Provide full information required for evaluation.
 - 1. On request, provide the following data:
 - a. Quantities of products, labor, and equipment.
 - b. Taxes, insurance, and bonds.
 - c. Overhead and profit.
 - d. Justification for any change in Contract Time.
 - e. Credit for deletions from Contract, similarly documented.
 - 2. Support each claim for additional costs with additional information:
 - a. Origin and date of claim.
 - b. Dates and times work was performed, and by whom.
 - c. Time records and wage rates paid.
 - d. Invoices and receipts for products, equipment, and subcontracts, similarly documented.

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- 3. For Time and Material work, submit itemized account and supporting data after completion of change, within time limits indicated in the Conditions of the Contract.
- H. Execution of Change Orders: Architect will issue Change Orders for signatures of parties as provided in the Conditions of the Contract.
- I. After execution of Change Order, promptly revise Schedule of Values and Application for Payment forms to record each authorized Change Order as a separate line item and adjust the Contract Sum.
- J. Promptly revise progress schedules to reflect any change in Contract Time, revise subschedules to adjust times for other items of work affected by the change, and resubmit.
- K. Promptly enter changes in Project Record Documents.

1.05 APPLICATION FOR FINAL PAYMENT

- A. Prepare Application for Final Payment as specified for progress payments, identifying total adjusted Contract Sum, previous payments, and sum remaining due.
- B. Application for Final Payment will not be considered until the following have been accomplished:
 - 1. All closeout procedures specified in Section 017000.

END OF SECTION 012000

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 012500 SUBSTITUTION PROCEDURES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Procedural requirements for proposed substitutions.

1.02 RELATED REQUIREMENTS

- A. Section 004325 Substitution Request Form During Procurement: Required form for substitution requests made prior to award of contract (During procurement).
- B. Section 006325 Substitution Request Form During Construction: Required form for substitution requests made after award of contract (During construction).

1.03 DEFINITIONS

- A. Substitutions: Changes from Contract Documents requirements proposed by Contractor to materials, products, assemblies, and equipment.
 - 1. Substitutions for Cause: Proposed due to changed Project circumstances beyond Contractor's control.
 - a. Unavailability.
 - b. Regulatory changes.
 - 2. Substitutions for Convenience: Proposed due to possibility of offering substantial advantage to the Project.
 - a. Substitution requests offering advantages solely to the Contractor will not be considered.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 GENERAL REQUIREMENTS

- A. A Substitution Request for products, assemblies, materials, and equipment constitutes a representation that the submitter:
 - 1. Has investigated proposed product and determined that it meets or exceeds the quality level of the specified product, equipment, assembly, or system.
 - 2. Agrees to provide the same warranty for the substitution as for the specified product.
 - 3. Agrees to provide same or equivalent maintenance service and source of replacement parts, as applicable.
 - 4. Agrees to coordinate installation and make changes to other work that may be required for the work to be complete, with no additional cost to Owner.
 - 5. Waives claims for additional costs or time extension that may subsequently become apparent.
 - 6. Agrees to reimburse Owner and Architect for review or redesign services associated with re-approval by authorities.
- B. A Substitution Request for specified installer constitutes a representation that the submitter:
 - 1. Has acted in good faith to obtain services of specified installer, but was unable to come to commercial, or other terms.
- C. Document each request with complete data substantiating compliance of proposed substitution with Contract Documents. Burden of proof is on proposer.
- D. Content: Include information necessary for tracking the status of each Substitution Request, and information necessary to provide an actionable response.
 - 1. Forms indicated in the Project Manual are adequate for this purpose, and must be used.
- E. Limit each request to a single proposed substitution item.

LAHC – WORKFORCE
EDUCATION RESOURCE AND
DEVELOPMENT CENTER

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

1. Submit an electronic document, combining the request form with supporting data into single document.

3.02 SUBSTITUTION PROCEDURES DURING PROCUREMENT

- A. Submittal Time Restrictions:
 - 1. Instructions to Bidders specifies time restrictions and the documents required for submitting substitution requests during the bidding period.
- B. Submittal Form (before award of contract):
 - 1. Submit substitution requests by completing the form in Section 004325; see this section for additional information and instructions. Use only this form; other forms of submission are unacceptable.
- C. Substitution Review Fee All substitution requests during procurement shall be submitted to Architect for review with a check in the amount of \$1,500 payable to "Framework E, LLC".

3.03 SUBSTITUTION PROCEDURES DURING CONSTRUCTION

- A. Submittal Form (after award of contract):
 - 1. Submit substitution requests by completing the form in Section 006325; see this section for additional information and instructions. Use only this form; other forms of submission are unacceptable.
- B. Submit request for Substitution for Cause within 14 days of discovery of need for substitution, but not later than 14 days prior to time required for review and approval by Architect, in order to stay on approved project schedule.
- C. Substitution Review Fee All substitution requests dushall be submitted to Architect for review with a check in the amount of \$1,500 payable to "Framework E, LLC".
- D. Submit request for Substitution for Convenience within 14 days of discovery of its potential advantage to the project, but not later than 14 days prior to time required for review and approval by Architect, in order to stay on approved project schedule.
 - 1. In addition to meeting general documentation requirements, document how the requested substitution benefits the Owner through cost savings, time savings, greater energy conservation, or in other specific ways.
 - 2. Document means of coordinating of substitution item with other portions of the work, including work by affected subcontractors.
 - 3. Bear the costs engendered by proposed substitution of:
 - a. Owner's compensation to the Architect for any required redesign, time spent processing and evaluating the request.
 - b. Other construction by Owner.
 - c. Other unanticipated project considerations.

3.04 RESOLUTION

- A. Architect may request additional information and documentation prior to rendering a decision. Provide this data in an expeditious manner.
- B. Architect will notify Contractor in writing of decision to accept or reject request.
 - 1. Architect's decision following review of proposed substitution will be noted on the submitted form.
- C. No substitutions shall be approved without prior payment of Substitution Review Fee paid to Architect as per sections 3.02 C and 3.03 C above.

3.05 ACCEPTANCE

A. Accepted substitutions change the work of the Project. They will be documented and incorporated into work of the project by Change Order, Construction Change Directive, Architectural Supplementary Instructions, or similar instruments provided for in the Conditions of the Contract.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

3.06 CLOSEOUT ACTIVITIES

- A. See Section 017800 Closeout Submittals, for closeout submittals.
- B. Include completed Substitution Request Forms as part of the Project record. Include both approved and rejected Requests.

END OF SECTION 012500

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 013000 ADMINISTRATIVE REQUIREMENTS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. General administrative requirements.
- B. Web-based project software service.
- C. Electronic document submittal service.
- D. Preconstruction meeting.
- E. Site mobilization meeting.
- F. Progress meetings.
- G. Construction progress schedule.
- H. Progress photographs.
- I. Submittals for review, information, and project closeout.
- J. Number of copies of submittals.
- K. Requests for Interpretation (RFI) procedures.
- L. Submittal procedures.

1.02 RELATED REQUIREMENTS

A. Section 016000 - Product Requirements: General product requirements.

1.03 GENERAL ADMINISTRATIVE REQUIREMENTS

- A. Comply with requirements of Section 017000 Execution and Closeout Requirements for coordination of execution of administrative tasks with timing of construction activities.
- B. Make the following types of submittals to Architect:
 - 1. Requests for Interpretation (RFI).
 - 2. Requests for substitution.
 - 3. Shop drawings, product data, and samples.
 - 4. Test and inspection reports.
 - 5. Design data.
 - 6. Manufacturer's instructions and field reports.
 - 7. Applications for payment and change order requests.
 - 8. Progress schedules.
 - 9. Coordination drawings.
 - 10. Correction Punch List and Final Correction Punch List for Substantial Completion.
 - 11. Closeout submittals.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 WEB-BASED PROJECT SOFTWARE SERVICE

- A. Web-Based Project Software Service: Provide, administer, and use web-based project software to host and manage project communication and documentation.
 - 1. Include, at minimum, the following features:
 - a. Project directory, including Owner, Contractor, subcontractors, Architect, Architect's consultants, and other entities involved in the project. Include names of contact persons and contact information for each entity.
 - b. Access control for each entity and for each workflow process to determine each entity's digital rights to create, modify, view, and print documents.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- c. Workflow planning, allowing customization of workflow for each project entity.
- d. Creation, logging, tracking, and notification for project communications.
- e. Tracking of project communication statuses in real time, including timestamped response log.
- f. Procedures for viewing PDFs or similar file formats, allowing markups by each entity. Provide security features to lock markups against changes once submitted.
- g. Processing and tracking of payment applications.
- h. Processing and tracking of contract modifications.
- i. Creation and distribution of meeting minutes.
- j. Document management for drawings, specifications, and coordination drawings, including revision control.
- k. Management of construction progress photographs.
- I. Mobile device compatibility.
- m. Creation of data analytics reports.
- n. Creation and export of editable logs for software functions. Provide Owner, Architect, and Architect's consultants with rights and ability to download logs when requested.
- 2. Cost: Pay cost of service. Include the cost of the service in the contract sum.
- 3. Provide up to 20 user licenses for use by Owner, Architect, Architect's consultants, and other entities involved in the project.
- 4. Comply with the software service's current published licensing agreements.
- 5. Training: Provide one-hour, web-based training session for users of software service. Further training is the responsibility of the user.
 - a. Representatives of Owner are scheduled and included in this training.
- 6. Project Closeout: Architect determines when to terminate the software service for the project and is responsible for obtaining archive copies of files for Owner.
- 7. Web-Based Project Software Services: The selected service is:

3.02 ELECTRONIC DOCUMENT SUBMITTAL SERVICE

- A. All documents transmitted for purposes of administration of the contract are to be in electronic (PDF, MS Word, or MS Excel) format, as appropriate to the document, and transmitted via an Internet-based submittal service that receives, logs and stores documents, provides electronic stamping and signatures, and notifies addressees via email.
 - 1. Besides submittals for review, information, and closeout, this procedure applies to Requests for Interpretation (RFIs), progress documentation, contract modification documents (e.g. supplementary instructions, change proposals, change orders), applications for payment, field reports and meeting minutes, Contractor's correction punchlist, and any other document any participant wishes to make part of the project record.
 - 2. Contractor and Architect are required to use this service.
 - 3. It is Contractor's responsibility to submit documents in allowable format.
 - 4. Subcontractors, suppliers, and Architect's consultants will be permitted to use the service at no extra charge.
 - 5. Users of the service need an email address, internet access, and PDF review software that includes ability to mark up and apply electronic stamps (such as Adobe Acrobat, www.adobe.com, or Bluebeam PDF Revu, www.bluebeam.com), unless such software capability is provided by the service provider.
 - 6. Paper document transmittals will not be reviewed; emailed electronic documents will not be reviewed.
 - 7. All other specified submittal and document transmission procedures apply, except that electronic document requirements do not apply to samples or color selection charts.
- B. Submittal Service: The selected service is:

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- C. Training: One, one-hour, web-based training session will be arranged for all participants, with representatives of Architect and Contractor participating; further training is the responsibility of the user of the service.
- D. Project Closeout: Architect will determine when to terminate the service for the project and is responsible for obtaining archive copies of files for Owner.

3.03 PRECONSTRUCTION MEETING

- A. Schedule meeting after Notice of Award.
- B. Attendance Required:
 - 1. Owner.
 - 2. Architect.
 - 3. Contractor.
- C. Agenda:
 - 1. Execution of Owner-Contractor Agreement.
 - 2. Submission of executed bonds and insurance certificates.
 - 3. Distribution of Contract Documents.
 - 4. Submission of list of subcontractors, list of products, schedule of values, and progress schedule.
 - 5. Designation of personnel representing the parties to Contract and Architect.
 - 6. Procedures and processing of field decisions, submittals, substitutions, applications for payments, proposal request, Change Orders, and Contract closeout procedures.
 - 7. Scheduling.
- D. Record minutes and distribute copies within two days after meeting to participants, with two copies to Architect, Owner, participants, and those affected by decisions made.

3.04 SITE MOBILIZATION MEETING

- A. Schedule meeting at the Project site prior to Contractor occupancy.
- B. Attendance Required:
 - 1. Contractor.
 - 2. Owner.
 - 3. Architect.
 - 4. Contractor's superintendent.
 - 5. Major subcontractors.
- C. Agenda:
 - 1. Use of premises by Owner and Contractor.
 - 2. Owner's requirements.
 - 3. Construction facilities and controls provided by Owner.
 - 4. Temporary utilities provided by Owner.
 - 5. Survey and building layout.
 - 6. Security and housekeeping procedures.
 - 7. Schedules.
 - 8. Application for payment procedures.
 - 9. Procedures for testing.
 - 10. Procedures for maintaining record documents.
 - 11. Requirements for start-up of equipment.
 - 12. Inspection and acceptance of equipment put into service during construction period.
- D. Record minutes and distribute copies within two days after meeting to participants, with two copies to Architect, Owner, participants, and those affected by decisions made.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

3.05 PROGRESS MEETINGS

- A. Attendance Required:
 - 1. Contractor.
 - 2. Owner.
 - 3. Architect.
 - 4. Contractor's superintendent.
 - 5. Major subcontractors.

B. Agenda:

- 1. Review minutes of previous meetings.
- 2. Review of work progress.
- 3. Field observations, problems, and decisions.
- 4. Identification of problems that impede, or will impede, planned progress.
- 5. Review of submittals schedule and status of submittals.
- 6. Maintenance of progress schedule.
- 7. Corrective measures to regain projected schedules.
- 8. Planned progress during succeeding work period.
- 9. Maintenance of quality and work standards.
- 10. Effect of proposed changes on progress schedule and coordination.
- 11. Other business relating to work.
- C. Record minutes and distribute copies within two days after meeting to participants, with two copies to Architect, Owner, participants, and those affected by decisions made.

3.06 CONSTRUCTION PROGRESS SCHEDULE

- A. If preliminary schedule requires revision after review, submit revised schedule within 10 days.
- B. Within 20 days after review of preliminary schedule, submit draft of proposed complete schedule for review.
 - 1. Include written certification that major contractors have reviewed and accepted proposed schedule.
- C. Within 10 days after joint review, submit complete schedule.
- D. Submit updated schedule with each Application for Payment.

3.07 PROGRESS PHOTOGRAPHS

3.08 REQUESTS FOR INTERPRETATION (RFI)

- A. Definition: A request seeking one of the following:
 - 1. An interpretation, amplification, or clarification of some requirement of Contract Documents arising from inability to determine from them the exact material, process, or system to be installed; or when the elements of construction are required to occupy the same space (interference); or when an item of work is described differently at more than one place in Contract Documents.
 - 2. A resolution to an issue which has arisen due to field conditions and affects design intent.
- B. Preparation: Prepare an RFI immediately upon discovery of a need for interpretation of Contract Documents. Failure to submit a RFI in a timely manner is not a legitimate cause for claiming additional costs or delays in execution of the work.
 - 1. Prepare a separate RFI for each specific item.
 - 2. Prepare using software provided by the Electronic Document Submittal Service.
- C. Reason for the RFI: Prior to initiation of an RFI, carefully study all Contract Documents to confirm that information sufficient for their interpretation is definitely not included.
 - 1. Include in each request Contractor's signature attesting to good faith effort to determine from Contract Documents information requiring interpretation.
 - 2. Unacceptable Uses for RFIs: Do not use RFIs to request the following::

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- a. Approval of submittals (use procedures specified elsewhere in this section).
- b. Approval of substitutions (see Section 016000 Product Requirements)
- c. Changes that entail change in Contract Time and Contract Sum (comply with provisions of the Conditions of the Contract).
- 3. Improper RFIs: Requests not prepared in compliance with requirements of this section, and/or missing key information required to render an actionable response. They will be returned without a response, with an explanatory notation.
- 4. Frivolous RFIs: Requests regarding information that is clearly indicated on, or reasonably inferable from, Contract Documents, with no additional input required to clarify the question. They will be returned without a response, with an explanatory notation.
 - a. The Owner reserves the right to assess the Contractor for the costs (on time-andmaterials basis) incurred by the Architect, and any of its consultants, due to processing of such RFIs.
- D. Content: Include identifiers necessary for tracking the status of each RFI, and information necessary to provide an actionable response.
 - 1. Official Project name and number, and any additional required identifiers established in Contract Documents.
 - 2. Owner's, Architect's, and Contractor's names.
 - 3. Discrete and consecutive RFI number, and descriptive subject/title.
 - 4. Issue date, and requested reply date.
 - 5. Reference to particular Contract Document(s) requiring additional information/interpretation. Identify pertinent drawing and detail number and/or specification section number, title, and paragraph(s).
 - 6. Annotations: Field dimensions and/or description of conditions which have engendered the request.
 - 7. Contractor's suggested resolution: A written and/or a graphic solution, to scale, is required in cases where clarification of coordination issues is involved, for example; routing, clearances, and/or specific locations of work shown diagrammatically in Contract Documents. If applicable, state the likely impact of the suggested resolution on Contract Time or the Contract Sum.
- E. Attachments: Include sketches, coordination drawings, descriptions, photos, submittals, and other information necessary to substantiate the reason for the request.
- F. RFI Log: Prepare and maintain a tabular log of RFIs for the duration of the project.
 - 1. Indicate current status of every RFI. Update log promptly and on a regular basis.
 - 2. Note dates of when each request is made, and when a response is received.
 - 3. Highlight items requiring priority or expedited response.
 - 4. Highlight items for which a timely response has not been received to date.
- G. Review Time: Architect will respond and return RFIs to Contractor within seven calendar days of receipt. For the purpose of establishing the start of the mandated response period, RFIs received after 12:00 noon will be considered as having been received on the following regular working day.
 - 1. Response period may be shortened or lengthened for specific items, subject to mutual agreement, and recorded in a timely manner in progress meeting minutes.
- H. Responses: Content of answered RFIs will not constitute in any manner a directive or authorization to perform extra work or delay the project. If in Contractor's belief it is likely to lead to a change to Contract Price or Contract Time, promptly issue a notice to this effect, and follow up with an appropriate Change Order request to Owner.
 - 1. Response may include a request for additional information, in which case the original RFI will be deemed as having been answered, and an amended one is to be issued forthwith. Identify the amended RFI with an R suffix to the original number.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 2. Do not extend applicability of a response to specific item to encompass other similar conditions, unless specifically so noted in the response.
- 3. Upon receipt of a response, promptly review and distribute it to all affected parties, and update the RFI Log.
- 4. Notify Architect within seven calendar days if an additional or corrected response is required by submitting an amended version of the original RFI, identified as specified above.

3.09 SUBMITTAL SCHEDULE

- A. Submit to Architect for review a schedule for submittals in tabular format.
 - 1. Coordinate with Contractor's construction schedule and schedule of values.
 - 2. Format schedule to allow tracking of status of submittals throughout duration of construction.
 - 3. Contractor's submittal numbering format shall be subject to Architect's approval. Individual Submittal numbers shall have a six digit prefix corresponding to the Project Specifications.
 - 4. Arrange information to include scheduled date for initial submittal, specification number and title, submittal category (for review or for information), description of item of work covered, and role and name of subcontractor.
 - 5. Account for time required for preparation, review, manufacturing, fabrication and delivery when establishing submittal delivery and review deadline dates.
 - a. For assemblies, equipment, systems comprised of multiple components and/or requiring detailed coordination with other work, allow for additional time to make corrections or revisions to initial submittals, and time for their review.

3.10 SUBMITTALS FOR REVIEW

- A. When the following are specified in individual sections, submit them for review:
 - 1. Shop drawings.
 - 2. Samples for selection.
 - 3. Samples for verification.
- B. Submit to Architect for review for the limited purpose of checking for compliance with information given and the design concept expressed in Contract Documents.
- C. Samples will be reviewed for aesthetic, color, or finish selection.
- D. After review, provide copies and distribute in accordance with SUBMITTAL PROCEDURES article below and for record documents purposes described in Section 017800 Closeout Submittals.

3.11 SUBMITTALS FOR INFORMATION

- A. When the following are specified in individual sections, submit them for information:
 - 1. Design data.
 - 2. Product Data
 - 3. Certificates.
 - 4. Test reports.
 - 5. Inspection reports.
 - 6. Manufacturer's instructions.
 - 7. Manufacturer's field reports.
 - 8. Other types indicated.
- B. Submit for Architect's knowledge as contract administrator or for Owner.
- C. The product data of all specified products and equipment shall be submitted and stored in the electronic project management software platform and not submitted to the Architect for review. It may be reviewed upon request of the Architect. Deviations from the Project Specifications in submitted product data which are not approved as substitutions in advance and are used in The Work shall cause the Contractor to be in default of the Contract Documents and The

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

Owner shall have all remedies at their disposal including liquidated damages for delays.

3.12 SUBMITTALS FOR PROJECT CLOSEOUT

- A. Submit Correction Punch List for Substantial Completion.
- B. Submit Final Correction Punch List for Substantial Completion.
- C. When the following are specified in individual sections, submit them at project closeout in compliance with requirements of Section 017800 Closeout Submittals:
 - 1. Project record documents.
 - 2. Operation and maintenance data.
 - 3. Warranties.
 - 4. Bonds.
 - 5. Other types as indicated.
- D. Submit for Owner's benefit during and after project completion.

3.13 NUMBER OF COPIES OF SUBMITTALS

- A. Electronic Documents: Submit one electronic copy in PDF format; an electronically-marked up file will be returned. Create PDFs at native size and right-side up; illegible files will be rejected.
- B. Samples: Submit the number specified in individual specification sections; one of which will be retained by Architect.
 - 1. After review, produce duplicates.
 - 2. Retained samples will not be returned to Contractor unless specifically so stated.

3.14 SUBMITTAL PROCEDURES

- A. General Requirements:
 - 1. Identify: Project; Contractor; subcontractor or supplier; pertinent drawing and detail number; and specification section number and article/paragraph, as appropriate on each copy. Specification secton number shall be the first number of each individual submittal identification number.
 - 2. Apply Contractor's stamp, signed or initialed certifying that review, approval, verification of products required, field dimensions, adjacent construction work, and coordination of information is in accordance with the requirements of the work and Contract Documents.
 - a. Submittals from sources other than the Contractor, or without Contractor's stamp will not be acknowledged, reviewed, or returned.
 - 3. Schedule submittals to expedite the Project, and coordinate submission of related items.
 - a. For each submittal for review, allow 15 days.
 - b. For sequential reviews involving Architect's consultants, Owner, or another affected party, allow an additional 7 days.
 - c. For sequential reviews involving approval from authorities having jurisdiction (AHJ), in addition to Architect's approval, allow an additional 30 days.
 - 4. Identify variations from Contract Documents and product or system limitations that may be detrimental to successful performance of the completed work.
 - 5. Provide space for Contractor and Architect review stamps.
 - 6. When revised for resubmission, identify all changes made since previous submission.
 - 7. Distribute reviewed submittals. Instruct parties to promptly report inability to comply with requirements.
 - 8. Incomplete submittals will not be reviewed, unless they are partial submittals for distinct portion(s) of the work, and have received prior approval for their use.
 - 9. Submittals not requested will not be recognized or processed.
- B. Product Data Procedures:
 - 1. Submit only information required by individual specification sections.
 - 2. Collect required information into a single submittal.
 - 3. Submit concurrently with related shop drawing submittal.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 4. Do not submit (Material) Safety Data Sheets for materials or products.
- C. Shop Drawing Procedures:
 - 1. Prepare accurate, drawn-to-scale, original shop drawing documentation by interpreting Contract Documents and coordinating related work.
 - 2. Generic, non-project-specific information submitted as shop drawings do not meet the requirements for shop drawings.
- D. Samples Procedures:
 - 1. Transmit related items together as single package.
 - 2. Identify each item to allow review for applicability in relation to shop drawings showing installation locations.
 - 3. Include with transmittal high-resolution image files of samples to facilitate electronic review and approval. Provide separate submittal page for each item image.

END OF SECTION 013000

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 013216 CONSTRUCTION PROGRESS SCHEDULE

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Preliminary schedule.
- B. Construction progress schedule, bar chart type.

1.02 REFERENCE STANDARDS

- A. AGC (CPSM) Construction Planning and Scheduling Manual; 2004.
- B. M-H (CPM) CPM in Construction Management Project Management with CPM; 2016.

1.03 SUBMITTALS

- A. Within 10 days after date of Agreement, submit preliminary schedule.
- B. If preliminary schedule requires revision after review, submit revised schedule within 10 days.
- C. Within 20 days after review of preliminary schedule, submit draft of proposed complete schedule for review.
 - 1. Include written certification that major contractors have reviewed and accepted proposed schedule.
- D. Within 10 days after joint review, submit complete schedule.
- E. Submit updated schedule with each Application for Payment.
- F. Submit in PDF format.

1.04 QUALITY ASSURANCE

- A. Scheduler: Contractor's personnel or specialist Consultant specializing in CPM scheduling with one years minimum experience in scheduling construction work of a complexity comparable to this Project, and having use of computer facilities capable of delivering a detailed graphic printout within 48 hours of request.
- B. Contractor's Administrative Personnel: 3 years minimum experience in using and monitoring CPM schedules on comparable projects.

1.05 SCHEDULE FORMAT

- A. Listings: In chronological order according to the start date for each activity. Identify each activity with the applicable specification section number.
- B. Diagram Sheet Size: Maximum 22 x 17 inches (560 x 432 mm).

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 PRELIMINARY SCHEDULE

A. Prepare preliminary schedule in the form of a horizontal bar chart.

3.02 CONTENT

- A. Show complete sequence of construction by activity, with dates for beginning and completion of each element of construction.
- B. Identify each item by specification section number.
- C. Identify work of separate stages and other logically grouped activities.
- D. Provide sub-schedules to define critical portions of the entire schedule.
- E. Include conferences and meetings in schedule.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- F. Show accumulated percentage of completion of each item, and total percentage of Work completed, as of the first day of each month.
- G. Provide separate schedule of submittal dates for shop drawings, product data, and samples, owner-furnished products, products identified under Allowances, and dates reviewed submittals will be required from Architect. Indicate decision dates for selection of finishes.
- H. Indicate delivery dates for owner-furnished products.
- I. Coordinate content with schedule of values specified in Section 012000 Price and Payment Procedures.
- J. Provide legend for symbols and abbreviations used.

3.03 BAR CHARTS

- A. Include a separate bar for each major portion of Work or operation.
- B. Identify the first work day of each week.

3.04 NETWORK ANALYSIS

- A. Prepare network analysis diagrams and supporting mathematical analyses using the Critical Path Method.
- B. Illustrate order and interdependence of activities and sequence of work; how start of a given activity depends on completion of preceding activities, and how completion of the activity may restrain start of subsequent activities.
- C. Mathematical Analysis: Tabulate each activity of detailed network diagrams, using calendar dates, and identify for each activity:
 - 1. Preceding and following event numbers.
 - 2. Activity description.
 - 3. Estimated duration of activity, in maximum 15 day intervals.
 - 4. Earliest start date.
 - 5. Earliest finish date.
 - 6. Actual start date.
 - 7. Actual finish date.
 - 8. Latest start date.
 - 9. Latest finish date.
 - 10. Total and free float; float time shall accrue to Owner and to Owner's benefit.
 - 11. Monetary value of activity, keyed to Schedule of Values.
 - 12. Percentage of activity completed.
 - 13. Responsibility.
- D. Analysis Program: Capable of compiling monetary value of completed and partially completed activities, accepting revised completion dates, and recomputation of all dates and float.
- E. Required Reports: List activities in sorts or groups:
 - 1. By preceding work item or event number from lowest to highest.
 - 2. By amount of float, then in order of early start.

3.05 REVIEW AND EVALUATION OF SCHEDULE

- A. Participate in joint review and evaluation of schedule with Architect at each submittal.
- B. Evaluate project status to determine work behind schedule and work ahead of schedule.
- C. After review, revise as necessary as result of review, and resubmit within 10 days.

3.06 UPDATING SCHEDULE

- A. Maintain schedules to record actual start and finish dates of completed activities.
- B. Indicate progress of each activity to date of revision, with projected completion date of each activity.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- C. Annotate diagrams to graphically depict current status of Work.
- D. Identify activities modified since previous submittal, major changes in Work, and other identifiable changes.
- E. Indicate changes required to maintain Date of Substantial Completion.
- F. Submit reports required to support recommended changes.

3.07 DISTRIBUTION OF SCHEDULE

- A. Distribute copies of updated schedules to Contractor's project site file, to subcontractors, suppliers, Architect, Owner, and other concerned parties.
- B. Instruct recipients to promptly report, in writing, problems anticipated by projections indicated in schedules.

END OF SECTION 013216

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 013553 SECURITY PROCEDURES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Security measures including entry control and personnel identification.

1.02 SECURITY PROGRAM

- A. Protect Work , existing premises and Owner's operations from theft, vandalism, and unauthorized entry.
- B. Initiate program in coordination with Owner's existing security system at project mobilization.
- C. Maintain program throughout construction period until Owner occupancy.

1.03 ENTRY CONTROL

- A. Restrict entrance of persons and vehicles into Project site and existing facilities.
- B. Allow entrance only to authorized persons with proper identification.
- C. Maintain log of workers and visitors, make available to Owner on request.
- D. Owner will control entrance of persons and vehicles related to Owner's operations.

1.04 PERSONNEL IDENTIFICATION

- A. Provide identification badge to each person authorized to enter premises.
- B. Badge To Include: Personal photograph, name, assigned number, expiration date and employer.
- C. Require return of badges at expiration of their employment on the Work.

1.05 RESTRICTIONS

- A. Do no work on Sundays.
- PART 2 PRODUCTS NOT USED
- PART 3 EXECUTION NOT USED

END OF SECTION 013553

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 014000 QUALITY REQUIREMENTS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Submittals.
- B. Quality assurance.
- C. References and standards.
- D. Testing and inspection agencies and services.
- E. Contractor's construction-related professional design services.
- F. Contractor's design-related professional design services.
- G. Control of installation.
- H. Mock-ups.
- I. Manufacturers' field services.
- J. Defect Assessment.

1.02 RELATED REQUIREMENTS

A. Section 012100 - Allowances: Allowance for payment of testing services.

1.03 REFERENCE STANDARDS

- A. ASTM C1021 Standard Practice for Laboratories Engaged in Testing of Building Sealants; 2008 (Reapproved 2023).
- B. ASTM C1077 Standard Practice for Agencies Testing Concrete and Concrete Aggregates for Use in Construction and Criteria for Testing Agency Evaluation; 2024.
- C. ASTM C1093 Standard Practice for Accreditation of Testing Agencies for Masonry; 2023.
- D. ASTM D3740 Standard Practice for Minimum Requirements for Agencies Engaged in Testing and/or Inspection of Soil and Rock as Used in Engineering Design and Construction; 2023.
- E. ASTM E329 Standard Specification for Agencies Engaged in Construction Inspection, Testing, or Special Inspection; 2023.
- F. ASTM E543 Standard Specification for Agencies Performing Nondestructive Testing; 2021.
- G. ASTM E699 Standard Specification for Agencies Involved in Testing, Quality Assurance, and Evaluating of Manufactured Building Components; 2016.

1.04 DEFINITIONS

- A. Contractor's Quality Control Plan: Contractor's management plan for executing the Contract for Construction.
- B. Contractor's Professional Design Services: Design of some aspect or portion of the project by party other than the design professional of record. Provide these services as part of the Contract for Construction.
 - 1. Design Services Types Required:
 - a. Construction-Related: Services Contractor needs to provide in order to carry out the Contractor's sole responsibilities for construction means, methods, techniques, sequences, and procedures.
 - b. Design-Related: Design services explicitly required to be performed by another design professional due to highly-technical and/or specialized nature of a portion of the project. Services primarily involve engineering analysis, calculations, and design, and are not intended to alter the aesthetic aspects of the design.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

C. Design Data: Design-related, signed and sealed drawings, calculations, specifications, certifications, shop drawings and other submittals provided by Contractor, and prepared directly by, or under direct supervision of, appropriately licensed design professional.

1.05 CONTRACTOR'S CONSTRUCTION-RELATED PROFESSIONAL DESIGN SERVICES

- A. Coordination: Contractor's professional design services are subject to requirements of project's Conditions for Construction Contract.
- B. Provide such engineering design services as may be necessary to plan and safely conduct certain construction operations, pertaining to, but not limited to the following:
 - 1. Temporary sheeting, shoring, or supports.
 - 2. Temporary scaffolding.
 - 3. Temporary bracing.
 - 4. Temporary falsework for support of spanning or arched structures.
 - 5. Temporary foundation underpinning.
 - 6. Temporary stairs or steps required for construction access only.
 - 7. Temporary hoist(s) and rigging.
 - 8. Investigation of soil conditions to support construction equipment.

1.06 CONTRACTOR'S DESIGN-RELATED PROFESSIONAL DESIGN SERVICES

- A. Coordination: Contractor's professional design services are subject to requirements of project's Conditions for Construction Contract.
- B. Base design on performance and/or design criteria indicated in individual specification sections.
 - 1. Submit a Request for Interpretation to Architect if the criteria indicated are not sufficient to perform required design services.
- C. Scope of Contractor's Professional Design Services: Provide for the following items of work:
 - 1. Structural Design of Formwork: As described in Section 031000 Concrete Forming and Accessories.
 - 2. Concrete Mix Design: As described in Section 033000 Cast-in-Place Concrete. No specific designer qualifications are required.
 - 3. Structural Design of Steel Connections: As described in Section 051200 Structural Steel Framing.
 - 4. Structural Design of Steel Connections: As described in Section 052100 Steel Joist Framing.
 - 5. Structural Design of Steel Decking: As described in Section 053100 Steel Decking.
 - 6. Structural Design of Metal Framing: As described in Section 054000 Cold-Formed Metal Framing.
 - 7. Structural Design of Metal Fabrications: As described in Section 055000 Metal Fabrications.
 - 8. Structural Design of Stairs: As described in Section 055100 Metal Stairs.
 - 9. Structural Design of Railings: As described in Section 055213 Pipe and Tube Railings.
 - 10. Structural Calculations: As described in Section 074223 Metal Composite Wall Panels.
 - 11. Fire Protection Design: As described in Section 078700 Smoke Containment Barriers.
 - 12. Structural Design: Include physical characteristics, engineering calculations, and resulting dimensional limitations as described in Section 084313 Aluminum-Framed Storefronts.
 - 13. Structural Design: Include calculations for resisting wind loads, anchor locations, loads at points of attachment to building structure, physical characteristics, resulting dimensional limitations as described in Section 084413 Glazed Aluminum Curtain Walls.
 - 14. Structural Design: Include calculations for resisting wind loads, physical characteristics, resulting dimensional limitations as described in Section 084500 Translucent Wall and Roof Assemblies.
LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- 15. Sprinkler Layout: Coordinate with ceiling installation, detailed pipe layout, and hydraulic calculations as described in Section 211313 Wet-Pipe Sprinkler Systems.
- 16. System Design: As described in Section 230923 Direct-Digital Control System for HVAC.
- 17. Written Sequence of Operation: Include entire HVAC system and each piece of equipment, as described in Section 230900 Instrumentation and Control for HVAC.

1.07 SUBMITTALS

- A. See Section 013000 Administrative Requirements, for submittal procedures.
- B. Designer's Qualification Statement: Submit for Architect's knowledge as contract administrator, or for Owner's information.
 - 1. Include information for each individual professional responsible for producing, or supervising production of, design-related professional services provided by Contractor.
 - a. Full name.
 - b. Professional licensure information.
 - c. Statement addressing extent and depth of experience specifically relevant to design of items assigned to Contractor.
- C. Design Data: Submit for Architect's knowledge as contract administrator for the limited purpose of assessing compliance with information given and the design concept expressed in the Contract Documents, or for Owner's information.
 - 1. Include calculations that have been used to demonstrate compliance to performance and regulatory criteria provided, and to determine design solutions.
 - 2. Include required product data and shop drawings.
 - 3. Include a statement or certification attesting that design data complies with criteria indicated, such as building codes, loads, functional, and similar engineering requirements.
 - 4. Include signature and seal of design professional responsible for allocated design services on calculations and drawings.
- D. Test Reports: After each test/inspection, promptly submit two copies of report to Architect and to Contractor.
 - 1. Include:
 - a. Date issued.
 - b. Project title and number.
 - c. Name of inspector.
 - d. Date and time of sampling or inspection.
 - e. Identification of product and specifications section.
 - f. Location in the Project.
 - g. Type of test/inspection.
 - h. Date of test/inspection.
 - i. Results of test/inspection.
 - j. Compliance with Contract Documents.
 - k. When requested by Architect, provide interpretation of results.
 - 2. Test report submittals are for Architect's knowledge as contract administrator for the limited purpose of assessing compliance with information given and the design concept expressed in the Contract Documents, or for Owner's information.
- E. Certificates: When specified in individual specification sections, submit certification by the manufacturer and Contractor or installation/application subcontractor to Architect, in quantities specified for Product Data.
 - 1. Indicate material or product complies with or exceeds specified requirements. Submit supporting reference data, affidavits, and certifications as appropriate.
 - 2. Certificates may be recent or previous test results on material or product, but must be acceptable to Architect.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- F. Manufacturer's Instructions: When specified in individual specification sections, submit printed instructions for delivery, storage, assembly, installation, start-up, adjusting, and finishing, for the Owner's information. Indicate special procedures, perimeter conditions requiring special attention, and special environmental criteria required for application or installation.
- G. Manufacturer's Field Reports: Submit reports for Architect's benefit as contract administrator or for Owner.
 - 1. Submit report within 30 days of observation to Architect for information.
 - 2. Submit for information for the limited purpose of assessing compliance with information given and the design concept expressed in the Contract Documents.
- H. Erection Drawings: Submit drawings for Architect's benefit as contract administrator or for Owner.
 - 1. Submit for information for the limited purpose of assessing compliance with information given and the design concept expressed in the Contract Documents.
 - 2. Data indicating inappropriate or unacceptable Work may be subject to action by Architect or Owner.

1.08 QUALITY ASSURANCE

- A. Testing Agency Qualifications:
 - 1. Prior to start of work, submit agency name, address, and telephone number, and names of full time registered Engineer and responsible officer.
 - 2. Submit copy of report of laboratory facilities inspection made by NIST Construction Materials Reference Laboratory during most recent inspection, with memorandum of remedies of any deficiencies reported by the inspection.
- B. Designer Qualifications: Where professional engineering design services and design data submittals are specifically required of Contractor by Contract Documents, provide services of a Professional Engineer experienced in design of this type of work and licensed in the State in which the Project is located.
- C. Contractor's Quality Control (CQC) Plan:
 - 1. Prior to start of work, submit a comprehensive plan describing how contract deliverables will be produced. Tailor CQC plan to specific requirements of the project. Include the following information:
 - a. Management Structure: Identify personnel responsible for quality. Include a chart showing lines of authority.
 - 1) Include qualifications (in resume form), duties, responsibilities of each person assigned to CQC function.
 - b. Management Approach: Define, describe, and include in the plan specific methodologies used in executing the work.
 - 1) Management and control of documents and records relating to quality.
 - 2) Communications.
 - 3) Coordination procedures.
 - 4) Resource management.
 - 5) Process control.
 - 6) Inspection and testing procedures and scheduling.
 - 7) Control of noncomplying work.
 - 8) Tracking deficiencies from identification, through acceptable corrective action, and verification.
 - 9) Control of testing and measuring equipment.
 - 10) Project materials certification.
 - 11) Managerial continuity and flexibility.
 - c. Owner will not make a separate payment for providing and maintaining a Quality Control Plan. Include associated costs in Bid price.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- d. Acceptance of the plan is required prior to start of construction activities not including mobilization work. Owner's acceptance of the plan will be conditional and predicated on continuing satisfactory adherence to the plan. Owner reserves the right to require Contractor to make changes to the plan and operations, including removal of personnel, as necessary, to obtain specified quality of work results.
- D. Quality-Control Personnel Qualifications. Engage a person with requisite training and experience to implement and manage quality assurance (QA) and quality control (QC) for the project.

1.09 REFERENCES AND STANDARDS

- A. For products and workmanship specified by reference to a document or documents not included in the Project Manual, also referred to as reference standards, comply with requirements of the standard, except when more rigid requirements are specified or are required by applicable codes.
- B. Comply with reference standard of date of issue current on date of Contract Documents, except where a specific date is established by applicable code.
- C. Obtain copies of standards where required by product specification sections.
- D. Maintain copy at project site during submittals, planning, and progress of the specific work, until Substantial Completion.
- E. Should specified reference standards conflict with Contract Documents, request clarification from Architect before proceeding.
- F. Neither the contractual relationships, duties, or responsibilities of the parties in Contract nor those of Architect shall be altered from Contract Documents by mention or inference otherwise in any reference document.

1.10 TESTING AND INSPECTION AGENCIES AND SERVICES

- A. Owner will employ services of an independent testing agency to perform certain specified testing; payment for cost of services will be derived from allowance specified in Section 012100; see Section 012100 and applicable sections for description of services included in allowance.
- B. Owner will employ and pay for services of an independent testing agency to perform other specified testing.
- C. As indicated in individual specification sections, Owner or Contractor shall employ and pay for services of an independent testing agency to perform other specified testing.
- D. Employment of agency in no way relieves Contractor of obligation to perform Work in accordance with requirements of Contract Documents.
- E. Contractor Employed Agency:
 - 1. Testing agency: Comply with requirements of ASTM E329, ASTM E543, ASTM E699, ASTM C1021, ASTM C1077, ASTM C1093, and ASTM D3740.
 - 2. Laboratory: Authorized to operate in the State in which the Project is located.
 - 3. Laboratory Staff: Maintain a full time registered Engineer on staff to review services.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 CONTROL OF INSTALLATION

- A. Monitor quality control over suppliers, manufacturers, products, services, site conditions, and workmanship, to produce work of specified quality.
- B. Comply with manufacturers' instructions, including each step in sequence.
- C. Should manufacturers' instructions conflict with Contract Documents, request clarification from Architect before proceeding.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- D. Comply with specified standards as minimum quality for the work except where more stringent tolerances, codes, or specified requirements indicate higher standards or more precise workmanship.
- E. Have work performed by persons qualified to produce required and specified quality.
- F. Verify that field measurements are as indicated on shop drawings or as instructed by the manufacturer.
- G. Secure products in place with positive anchorage devices designed and sized to withstand stresses, vibration, physical distortion, and disfigurement.

3.02 MOCK-UPS

- A. Before installing portions of the Work where mock-ups are required, construct mock-ups in location and size indicated for each form of construction and finish required to comply with the following requirements, using materials indicated for the completed Work. The purpose of mock-up is to demonstrate the proposed range of aesthetic effects and workmanship.
- B. Accepted mock-ups establish the standard of quality the Architect will use to judge the Work.
- C. Integrated Exterior Mock-ups: Construct integrated exterior mock-up as indicated on drawings. Coordinate installation of exterior envelope materials and products as required in individual Specification Sections. Provide adequate supporting structure for mock-up materials as necessary.
- D. Notify Architect fifteen (15) working days in advance of dates and times when mock-ups will be constructed.
- E. Tests shall be performed under provisions identified in this section and identified in the respective product specification sections.
- F. Assemble and erect specified items with specified attachment and anchorage devices, flashings, seals, and finishes.
- G. Obtain Architect's approval of mock-ups before starting work, fabrication, or construction.
 - 1. Architect will issue written comments within seven (7) working days of initial review and each subsequent follow up review of each mock-up.
 - 2. Make corrections as necessary until Architect's approval is issued.
- H. Architect will use accepted mock-ups as a comparison standard for the remaining Work.
- I. Where mock-up has been accepted by Architect and is specified in product specification sections to be removed, protect mock-up throughout construction, remove mock-up and clear area when directed to do so by Architect.

3.03 TESTING AND INSPECTION

- A. Testing Agency Duties:
 - 1. Provide qualified personnel at site. Cooperate with Architect and Contractor in performance of services.
 - 2. Perform specified sampling and testing of products in accordance with specified standards.
 - 3. Ascertain compliance of materials and mixes with requirements of Contract Documents.
 - 4. Promptly notify Architect and Contractor of observed irregularities or non-compliance of Work or products.
 - 5. Perform additional tests and inspections required by Architect.
 - 6. Submit reports of all tests/inspections specified.
- B. Limits on Testing/Inspection Agency Authority:
 - 1. Agency may not release, revoke, alter, or enlarge on requirements of Contract Documents.
 - 2. Agency may not approve or accept any portion of the Work.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 3. Agency may not assume any duties of Contractor.
- 4. Agency has no authority to stop the Work.
- C. Contractor Responsibilities:
 - 1. Deliver to agency at designated location, adequate samples of materials proposed to be used that require testing, along with proposed mix designs.
 - 2. Cooperate with laboratory personnel, and provide access to the Work and to manufacturers' facilities.
 - 3. Provide incidental labor and facilities:
 - a. To provide access to Work to be tested/inspected.
 - b. To obtain and handle samples at the site or at source of Products to be tested/inspected.
 - c. To facilitate tests/inspections.
 - d. To provide storage and curing of test samples.
 - 4. Notify Architect and laboratory 24 hours prior to expected time for operations requiring testing/inspection services.
 - 5. Employ services of an independent qualified testing laboratory and pay for additional samples, tests, and inspections required by Contractor beyond specified requirements.
 - 6. Arrange with Owner's agency and pay for additional samples, tests, and inspections required by Contractor beyond specified requirements.
- D. Re-testing required because of non-compliance with specified requirements shall be performed by the same agency on instructions by Architect.
- E. Re-testing required because of non-compliance with specified requirements shall be paid for by Contractor.

3.04 MANUFACTURERS' FIELD SERVICES

- A. When specified in individual specification sections, require material or product suppliers or manufacturers to provide qualified staff personnel to observe site conditions, conditions of surfaces and installation, quality of workmanship, start-up of equipment, test, adjust, and balance equipment as applicable, and to initiate instructions when necessary.
- B. Submit qualifications of observer to Architect 30 days in advance of required observations.
- C. Report observations and site decisions or instructions given to applicators or installers that are supplemental or contrary to manufacturers' written instructions.

3.05 DEFECT ASSESSMENT

A. Replace Work or portions of the Work not complying with specified requirements.

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 015000 TEMPORARY FACILITIES AND CONTROLS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Dewatering
- B. Temporary telecommunications services.
- C. Temporary sanitary facilities.
- D. Temporary Controls: Barriers, enclosures, and fencing.
- E. Security requirements.
- F. Waste removal facilities and services.
- G. Project identification sign.
- H. Field offices.

1.02 RELATED REQUIREMENTS

A. Section 015100 - Temporary Utilities.

1.03 DEWATERING

A. Provide temporary means and methods for dewatering all temporary facilities and controls.

1.04 TEMPORARY UTILITIES - SEE SECTION 015100

- A. Provide and pay for all electrical power, lighting, water, heating and cooling, and ventilation required for construction purposes.
- B. Existing facilities may not be used.

1.05 TELECOMMUNICATIONS SERVICES

- A. Provide, maintain, and pay for telecommunications services to field office at time of project mobilization.
- B. Telecommunications services shall include:
 - 1. Windows-based personal computer dedicated to project telecommunications, with necessary software and laser printer.
 - 2. Telephone Land Lines: One line, minimum; one handset per line.
 - 3. Internet Connections: Minimum of one; DSL modem or faster.

1.06 TEMPORARY SANITARY FACILITIES

- A. Provide and maintain required facilities and enclosures. Provide at time of project mobilization.
- B. Maintain daily in clean and sanitary condition.

1.07 BARRIERS

- A. Provide barriers to prevent unauthorized entry to construction areas, to prevent access to areas that could be hazardous to workers or the public, to allow for owner's use of site and to protect existing facilities and adjacent properties from damage from construction operations and demolition.
- B. Provide barricades and covered walkways required by governing authorities for public rights-ofway and for public access to existing building.
- C. Protect non-owned vehicular traffic, stored materials, site, and structures from damage.

1.08 FENCING

A. Provide 6 foot (1.8 m) high fence around construction site; equip with vehicular and pedestrian gates with locks.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

1.09 EXTERIOR ENCLOSURES

A. Provide temporary insulated weather tight closure of exterior openings to accommodate acceptable working conditions and protection for Products, to allow for temporary heating and maintenance of required ambient temperatures identified in individual specification sections, and to prevent entry of unauthorized persons. Provide access doors with self-closing hardware and locks.

1.10 INTERIOR ENCLOSURES

- A. Provide temporary partitions and ceilings as indicated to separate work areas from Owneroccupied areas, to prevent penetration of dust and moisture into Owner-occupied areas, and to prevent damage to existing materials and equipment.
- B. Construction: Framing and reinforced polyethylene sheet materials with closed joints and sealed edges at intersections with existing surfaces:

1.11 SECURITY

- A. Provide security and facilities to protect Work, existing facilities, and Owner's operations from unauthorized entry, vandalism, or theft.
- B. Coordinate with Owner's security program.

1.12 VEHICULAR ACCESS AND PARKING

- A. Coordinate access and haul routes with governing authorities and Owner.
- B. Provide and maintain access to fire hydrants, free of obstructions.
- C. Provide means of removing mud from vehicle wheels before entering streets.
- D. Provide temporary parking areas to accommodate construction personnel. When site space is not adequate, provide additional off-site parking.

1.13 WASTE REMOVAL

- A. Provide waste removal facilities and services as required to maintain the site in clean and orderly condition.
- B. Provide containers with lids. Remove trash from site periodically.
- C. If materials to be recycled or re-used on the project must be stored on-site, provide suitable non-combustible containers; locate containers holding flammable material outside the structure unless otherwise approved by the authorities having jurisdiction.
- D. Open free-fall chutes are not permitted. Terminate closed chutes into appropriate containers with lids.

1.14 PROJECT IDENTIFICATION

- A. Provide project identification sign of design and construction indicated on drawings.
- B. Erect on site at location established by Architect.
- C. No other signs are allowed without Owner permission except those required by law.

1.15 FIELD OFFICES

- A. Office: Weathertight, with lighting, electrical outlets, heating, cooling equipment, and equipped with sturdy furniture, drawing rack, and drawing display table.
- B. Provide space for Project meetings, with table and chairs to accommodate 6 persons.
- C. Locate offices a minimum distance of 30 feet (10 m) from existing and new structures.

1.16 REMOVAL OF UTILITIES, FACILITIES, AND CONTROLS

A. Remove temporary utilities, equipment, facilities, materials, prior to Date of Substantial Completion inspection.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- B. Remove underground installations to a minimum depth of 2 feet (600 mm). Grade site as indicated.
- C. Clean and repair damage caused by installation or use of temporary work.
- D. Restore existing facilities used during construction to original condition.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION - NOT USED

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 016000 PRODUCT REQUIREMENTS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Transportation, handling, storage and protection.
- B. Product option requirements.
- C. Substitution limitations.
- D. Maintenance materials, including extra materials, spare parts, tools, and software.

1.02 RELATED REQUIREMENTS

- A. Section 012500 Substitution Procedures: Substitutions made during procurement and/or construction phases.
- B. Section 016116 Volatile Organic Compound (VOC) Content Restrictions: Requirements for VOC-restricted product categories.
- C. Section 017419 Construction Waste Management and Disposal: Waste disposal requirements potentially affecting product selection, packaging and substitutions.

1.03 REFERENCE STANDARDS

1.04 SUBMITTALS

- A. Product Data Submittals: Submit manufacturer's standard published data. Mark each copy to identify applicable products, models, options, and other data. Supplement manufacturers' standard data to provide information specific to this Project.
- B. Shop Drawing Submittals: Prepared specifically for this Project; indicate utility and electrical characteristics, utility connection requirements, and location of utility outlets for service for functional equipment and appliances.
- C. Sample Submittals: Illustrate functional and aesthetic characteristics of the product, with integral parts and attachment devices. Coordinate sample submittals for interfacing work.
 - 1. For selection from standard finishes, submit samples of the full range of the manufacturer's standard colors, textures, and patterns.

PART 2 PRODUCTS

2.01 NEW PRODUCTS

- A. Provide new products unless specifically required or permitted by Contract Documents.
- B. Use of products having any of the following characteristics is not permitted:
- C. Where other criteria are met, Contractor shall give preference to products that:
 1. If used on interior, have lower emissions, as defined in Section 016116.
 - 2. If wet-applied, have lower VOC content, as defined in Section 016116.

2.02 PRODUCT OPTIONS

- A. Products Specified by Reference Standards or by Description Only: Use any product meeting those standards or description.
- B. Products Specified by Naming One or More Manufacturers: Use a product of one of the manufacturers named and meeting specifications, no options or substitutions allowed.
- C. Products Specified by Naming One or More Manufacturers with a Provision for Substitutions: Submit a request for substitution for any manufacturer not named.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

2.03 MAINTENANCE MATERIALS

PART 3 EXECUTION

3.01 SUBSTITUTION LIMITATIONS

A. See Section 012500 - Substitution Procedures.

3.02 TRANSPORTATION AND HANDLING

- A. Package products for shipment in manner to prevent damage; for equipment, package to avoid loss of factory calibration.
- B. If special precautions are required, attach instructions prominently and legibly on outside of packaging.
- C. Coordinate schedule of product delivery to designated prepared areas in order to minimize site storage time and potential damage to stored materials.
- D. Transport and handle products in accordance with manufacturer's instructions.
- E. Transport materials in covered trucks to prevent contamination of product and littering of surrounding areas.
- F. Promptly inspect shipments to ensure that products comply with requirements, quantities are correct, and products are undamaged.
- G. Provide equipment and personnel to handle products by methods to prevent soiling, disfigurement, or damage, and to minimize handling.
- H. Arrange for the return of packing materials, such as wood pallets, where economically feasible.

3.03 STORAGE AND PROTECTION

- A. Designate receiving/storage areas for incoming products so that they are delivered according to installation schedule and placed convenient to work area in order to minimize waste due to excessive materials handling and misapplication. See Section 017419.
- B. Store and protect products in accordance with manufacturers' instructions.
- C. Store with seals and labels intact and legible.
- D. Store sensitive products in weathertight, climate-controlled enclosures in an environment favorable to product.
- E. For exterior storage of fabricated products, place on sloped supports above ground.
- F. Protect products from damage or deterioration due to construction operations, weather, precipitation, humidity, temperature, sunlight and ultraviolet light, dirt, dust, and other contaminants.
- G. Comply with manufacturer's warranty conditions, if any.
- H. Cover products subject to deterioration with impervious sheet covering. Provide ventilation to prevent condensation and degradation of products.
- I. Prevent contact with material that may cause corrosion, discoloration, or staining.
- J. Provide equipment and personnel to store products by methods to prevent soiling, disfigurement, or damage.
- K. Arrange storage of products to permit access for inspection. Periodically inspect to verify products are undamaged and are maintained in acceptable condition.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 016116

VOLATILE ORGANIC COMPOUND (VOC) CONTENT RESTRICTIONS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Requirements for Indoor-Emissions-Restricted products.
- B. Requirements for VOC-Content-Restricted products.

1.02 RELATED REQUIREMENTS

- A. Section 013000 Administrative Requirements: Submittal procedures.
- B. Section 014000 Quality Requirements: Procedures for testing and certifications.
- C. Section 079200 Joint Sealants: Emissions-compliant sealants.

1.03 DEFINITIONS

- A. Indoor-Emissions-Restricted Products: All products in the following product categories, whether specified or not:
 - 1. Interior paints and coatings applied on site.
 - 2. Interior adhesives and sealants applied on site, including flooring adhesives.
 - 3. Flooring.
 - 4. Thermal and acoustical insulation.
- B. VOC-Content-Restricted Products: All products in the following product categories, whether specified or not:
 - 1. Interior paints and coatings applied on site.
 - 2. Interior adhesives and sealants applied on site, including flooring adhesives.
- C. Interior of Building: Anywhere inside the exterior weather barrier.
- D. Adhesives: All gunnable, trowelable, liquid-applied, and aerosol adhesives, whether specified or not; including flooring adhesives, resilient base adhesives, and pipe jointing adhesives.
- E. Sealants: All gunnable, trowelable, and liquid-applied joint sealants and sealant primers, whether specified or not; including firestopping sealants and duct joint sealers.
- F. Inherently Non-Emitting Materials: Products composed wholly of minerals or metals, unless they include organic-based surface coatings, binders, or sealants; and specifically the following:
 - 1. Concrete.
 - 2. Clay brick.
 - 3. Metals that are plated, anodized, or powder-coated.
 - 4. Glass.
 - 5. Ceramics.
 - 6. Solid wood flooring that is unfinished and untreated.

1.04 REFERENCE STANDARDS

- A. 40 CFR 59, Subpart D National Volatile Organic Compound Emission Standards for Architectural Coatings; U.S. Environmental Protection Agency; Current Edition.
- B. ASTM D3960 Standard Practice for Determining Volatile Organic Compound (VOC) Content of Paints and Related Coatings; 2005 (Reapproved 2018).
- C. CAL (CDPH SM) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers Version 1.2; 2017.
- D. CARB (SCM) Suggested Control Measure for Architectural Coatings; California Air Resources Board; 2020.
- E. CHPS (HPPD) High Performance Products Database; Current Edition.
- F. CRI (GLP) Green Label Plus Testing Program Certified Products; Current Edition.

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- G. SCAQMD 1113 Architectural Coatings; 1977, with Amendment (2016).
- H. SCAQMD 1168 Adhesive and Sealant Applications; 1989, with Amendment (2022).
- I. SCS (CPD) SCS Certified Products; Current Edition.
- J. UL (GGG) GREENGUARD Gold Certified Products; Current Edition.

1.05 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Product Data: For each VOC-restricted product used in the project, submit evidence of compliance.

1.06 QUALITY ASSURANCE

- A. Indoor Emissions Standard and Test Method: CAL (CDPH SM), using Standard Private Office exposure scenario and the allowable concentrations specified in the method, and range of total VOC's after 14 days.
 - 1. Wet-Applied Products: State amount applied in mass per surface area.
 - 2. Paints and Coatings: Test tinted products, not just tinting bases.
 - 3. Evidence of Compliance: Acceptable types of evidence are the following;
 - a. Current UL (GGG) certification.
 - b. Current SCS (CPD) Floorscore certification.
 - c. Current SCS (CPD) Indoor Advantage Gold certification.
 - d. Current listing in CHPS (HPPD) as a low-emitting product.
 - e. Current CRI (GLP) certification.
 - f. Test report showing compliance and stating exposure scenario used.
 - 4. Product data submittal showing VOC content is NOT acceptable evidence.
 - 5. Manufacturer's certification without test report by independent agency is NOT acceptable evidence.
- B. VOC Content Test Method: 40 CFR 59, Subpart D (EPA Method 24), or ASTM D3960, unless otherwise indicated.
 - 1. Evidence of Compliance: Acceptable types of evidence are:
 - a. Report of laboratory testing performed in accordance with requirements.
 - b. Published product data showing compliance with requirements.
 - c. Certification by manufacturer that product complies with requirements.
- C. Testing Agency Qualifications: Independent firm specializing in performing testing and inspections of the type specified in this section.

PART 2 PRODUCTS

2.01 MATERIALS

- A. All Products: Comply with the most stringent of federal, State, and local requirements, or these specifications.
- B. Indoor-Emissions-Restricted Products: Comply with Indoor Emissions Standard and Test Method, except for:
 - 1. Inherently Non-Emitting Materials.
- C. VOC-Content-Restricted Products: VOC content not greater than required by the following:
 - 1. Adhesives, Including Flooring Adhesives: SCAQMD 1168 Rule.
 - 2. Joint Sealants: SCAQMD 1168 Rule.
 - 3. Paints and Coatings: Each color; most stringent of the following:
 - a. 40 CFR 59, Subpart D.
 - b. SCAQMD 1113 Rule.
 - c. CARB (SCM).

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

4. Wet-Applied Roofing and Waterproofing: Comply with requirements for paints and coatings.

PART 3 EXECUTION

3.01 FIELD QUALITY CONTROL

- A. Owner reserves the right to reject non-compliant products, whether installed or not, and require their removal and replacement with compliant products at no extra cost to Owner.
- B. Additional costs to restore indoor air quality due to installation of non-compliant products will be borne by Contractor.

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

Volatile Organic Compound (VOC) Content Restrictions

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 017000 EXECUTION AND CLOSEOUT REQUIREMENTS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Examination, preparation, and general installation procedures.
- B. Requirements for alterations work, including selective demolition, except removal, disposal, and/or remediation of hazardous materials and toxic substances.
- C. Pre-installation meetings.
- D. Cutting and patching.
- E. Surveying for laying out the work.
- F. Cleaning and protection.
- G. Starting of systems and equipment.
- H. Demonstration and instruction of Owner personnel.
- I. Closeout procedures, including Contractor's Correction Punch List, except payment procedures.
- J. General requirements for maintenance service.

1.02 RELATED REQUIREMENTS

- A. Section 013000 Administrative Requirements: Submittals procedures, Electronic document submittal service.
- B. Section 014000 Quality Requirements: Testing and inspection procedures.
- C. Section 015000 Temporary Facilities and Controls: Temporary exterior enclosures.
- D. Section 015000 Temporary Facilities and Controls: Temporary interior partitions.
- E. Section 078400 Firestopping.

1.03 SUBMITTALS

- A. See Section 013000 Administrative Requirements, for submittal procedures.
- B. Survey work: Submit name, address, and telephone number of Surveyor before starting survey work.
 - 1. On request, submit documentation verifying accuracy of survey work.
 - 2. Submit a copy of site drawing signed by the Land Surveyor, that the elevations and locations of the work are in compliance with Contract Documents.
 - 3. Submit surveys and survey logs for the project record.
- C. Demolition Plan: Submit demolition plan as specified by OSHA and local authorities.
 - 1. Indicate extent of demolition, removal sequence, bracing and shoring, and location and construction of barricades and fences. Include design drawings and calculations for bracing and shoring.
 - 2. Identify demolition firm and submit qualifications.
 - 3. Include a summary of safety procedures.
- D. Cutting and Patching: Submit written request in advance of cutting or alteration that affects:
 - 1. Structural integrity of any element of Project.
 - 2. Integrity of weather exposed or moisture resistant element.
 - 3. Efficiency, maintenance, or safety of any operational element.
 - 4. Visual qualities of sight exposed elements.
 - 5. Work of Owner or separate Contractor.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

1.04 QUALIFICATIONS

- A. For demolition work, employ a firm specializing in the type of work required.1. Minimum of five years of documented experience.
- B. For surveying work, employ a land surveyor registered in the State in which the Project is located and acceptable to Architect. Submit evidence of surveyor's Errors and Omissions insurance coverage in the form of an Insurance Certificate. Employ only individual(s) trained and experienced in collecting and recording accurate data relevant to ongoing construction activities,
- C. For field engineering, employ a professional engineer of the discipline required for specific service on Project, licensed in the State in which the Project is located. Employ only individual(s) trained and experienced in establishing and maintaining horizontal and vertical control points necessary for laying out construction work on project of similar size, scope and/or complexity.
- D. For design of temporary shoring and bracing, employ a Professional Engineer experienced in design of this type of work and licensed in the State in which the Project is located.

1.05 PROJECT CONDITIONS

- A. Use of explosives is not permitted.
- B. Grade site to drain. Maintain excavations free of water. Provide, operate, and maintain pumping equipment.
- C. Protect site from puddling or running water. Provide water barriers as required to protect site from soil erosion.
- D. Perform dewatering activities, as required, for the duration of the project.
- E. Ventilate enclosed areas to assist cure of materials, to dissipate humidity, and to prevent accumulation of dust, fumes, vapors, or gases.
- F. Dust Control: Execute work by methods to minimize raising dust from construction operations. Provide positive means to prevent air-borne dust from dispersing into atmosphere and over adjacent property.
 - 1. Provide dust-proof enclosures to prevent entry of dust generated outdoors.
 - 2. Provide dust-proof barriers between construction areas and areas continuing to be occupied by Owner.
- G. Erosion and Sediment Control: Plan and execute work by methods to control surface drainage from cuts and fills, from borrow and waste disposal areas. Prevent erosion and sedimentation.
 - 1. Minimize amount of bare soil exposed at one time.
 - 2. Provide temporary measures such as berms, dikes, and drains, to prevent water flow.
 - Construct fill and waste areas by selective placement to avoid erosive surface silts or clays.
 - 4. Periodically inspect earthwork to detect evidence of erosion and sedimentation; promptly apply corrective measures.
- H. Noise Control: Provide methods, means, and facilities to minimize noise produced by construction operations.

1.06 COORDINATION

- A. Coordinate scheduling, submittals, and work of the various sections of the Project Manual to ensure efficient and orderly sequence of installation of interdependent construction elements, with provisions for accommodating items installed later.
- B. Notify affected utility companies and comply with their requirements.
- C. Verify that utility requirements and characteristics of new operating equipment are compatible with building utilities. Coordinate work of various sections having interdependent

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

responsibilities for installing, connecting to, and placing in service, such equipment.

- D. Coordinate space requirements, supports, and installation of mechanical and electrical work that are indicated diagrammatically on drawings. Follow routing indicated for pipes, ducts, and conduit, as closely as practicable; place runs parallel with lines of building. Utilize spaces efficiently to maximize accessibility for other installations, for maintenance, and for repairs.
- E. In finished areas except as otherwise indicated, conceal pipes, ducts, and wiring within the construction. Coordinate locations of fixtures and outlets with finish elements.
- F. Coordinate completion and clean-up of work of separate sections.
- G. After Owner occupancy of premises, coordinate access to site for correction of defective work and work not in accordance with Contract Documents, to minimize disruption of Owner's activities.

PART 2 PRODUCTS

2.01 PATCHING MATERIALS

- A. New Materials: As specified in product sections; match existing products and work for patching and extending work.
- B. Type and Quality of Existing Products: Determine by inspecting and testing products where necessary, referring to existing work as a standard.
- C. Product Substitution: For any proposed change in materials, submit request for substitution described in Section 016000 Product Requirements.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that existing site conditions and substrate surfaces are acceptable for subsequent work. Start of work means acceptance of existing conditions.
- B. Verify that existing substrate is capable of structural support or attachment of new work being applied or attached.
- C. Examine and verify specific conditions described in individual specification sections.
- D. Take field measurements before confirming product orders or beginning fabrication, to minimize waste due to over-ordering or misfabrication.
- E. Verify that utility services are available, of the correct characteristics, and in the correct locations.
- F. Prior to Cutting: Examine existing conditions prior to commencing work, including elements subject to damage or movement during cutting and patching. After uncovering existing work, assess conditions affecting performance of work. Beginning of cutting or patching means acceptance of existing conditions.

3.02 PREPARATION

- A. Clean substrate surfaces prior to applying next material or substance.
- B. Seal cracks or openings of substrate prior to applying next material or substance.
- C. Apply manufacturer required or recommended substrate primer, sealer, or conditioner prior to applying any new material or substance in contact or bond.

3.03 PREINSTALLATION MEETINGS

- A. When required in individual specification sections, convene a preinstallation meeting at the site prior to commencing work of the section.
- B. Require attendance of parties directly affecting, or affected by, work of the specific section.
- C. Notify Architect four days in advance of meeting date.
- D. Prepare agenda and preside at meeting:

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- 1. Review conditions of examination, preparation and installation procedures.
- 2. Review coordination with related work.
- E. Record minutes and distribute copies within two days after meeting to participants, with two copies to Architect, Owner, participants, and those affected by decisions made.

3.04 LAYING OUT THE WORK

- A. Verify locations of survey control points prior to starting work.
- B. Promptly notify Architect of any discrepancies discovered.
- C. Protect survey control points prior to starting site work; preserve permanent reference points during construction.
- D. Promptly report to Architect the loss or destruction of any reference point or relocation required because of changes in grades or other reasons.
- E. Replace dislocated survey control points based on original survey control. Make no changes without prior written notice to Architect.
- F. Utilize recognized engineering survey practices.
- G. Establish elevations, lines and levels. Locate and lay out by instrumentation and similar appropriate means:
 - 1. Site improvements including pavements; stakes for grading, fill and topsoil placement; utility locations, slopes, and invert elevations.
 - 2. Grid or axis for structures.
 - 3. Building foundation, column locations, ground floor elevations.
- H. Periodically verify layouts by same means.
- I. Maintain a complete and accurate log of control and survey work as it progresses.

3.05 GENERAL INSTALLATION REQUIREMENTS

- A. Install products as specified in individual sections, in accordance with manufacturer's instructions and recommendations, and so as to avoid waste due to necessity for replacement.
- B. Make vertical elements plumb and horizontal elements level, unless otherwise indicated.
- C. Install equipment and fittings plumb and level, neatly aligned with adjacent vertical and horizontal lines, unless otherwise indicated.
- D. Make consistent texture on surfaces, with seamless transitions, unless otherwise indicated.
- E. Make neat transitions between different surfaces, maintaining texture and appearance.

3.06 ALTERATIONS

- A. Drawings showing existing construction and utilities are based on casual field observation and existing record documents only.
 - 1. Verify that construction and utility arrangements are as indicated.
 - 2. Report discrepancies to Architect before disturbing existing installation.
 - 3. Beginning of alterations work constitutes acceptance of existing conditions.
- B. Keep areas in which alterations are being conducted separated from other areas that are still occupied.
 - 1. Provide, erect, and maintain temporary dustproof partitions of construction specified in Section 015000 in locations indicated on drawings.
- C. Maintain weatherproof exterior building enclosure except for interruptions required for replacement or modifications; take care to prevent water and humidity damage.
 - 1. Where openings in exterior enclosure exist, provide construction to make exterior enclosure weatherproof.
 - 2. Insulate existing ducts or pipes that are exposed to outdoor ambient temperatures by alterations work.

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- D. Remove existing work as indicated and as required to accomplish new work.
 - 1. Remove items indicated on drawings.
 - 2. Relocate items indicated on drawings.
 - 3. Where new surface finishes are to be applied to existing work, perform removals, patch, and prepare existing surfaces as required to receive new finish; remove existing finish if necessary for successful application of new finish.
 - 4. Where new surface finishes are not specified or indicated, patch holes and damaged surfaces to match adjacent finished surfaces as closely as possible.
- E. Protect existing work to remain.
 - 1. Prevent movement of structure; provide shoring and bracing if necessary.
 - 2. Perform cutting to accomplish removals neatly and as specified for cutting new work.
 - 3. Repair adjacent construction and finishes damaged during removal work.
- F. Adapt existing work to fit new work: Make as neat and smooth transition as possible.
 - 1. When existing finished surfaces are cut so that a smooth transition with new work is not possible, terminate existing surface along a straight line at a natural line of division and make recommendation to Architect.
 - 2. Where removal of partitions or walls results in adjacent spaces becoming one, rework floors, walls, and ceilings to a smooth plane without breaks, steps, or bulkheads.
 - 3. Where a change of plane of 1/4 inch (6 mm) or more occurs in existing work, submit recommendation for providing a smooth transition for Architect review and request instructions.
- G. Patching: Where the existing surface is not indicated to be refinished, patch to match the surface finish that existed prior to cutting. Where the surface is indicated to be refinished, patch so that the substrate is ready for the new finish.
- H. Refinish existing surfaces as indicated:
 - 1. Where rooms or spaces are indicated to be refinished, refinish all visible existing surfaces to remain to the specified condition for each material, with a neat transition to adjacent finishes.
 - 2. If mechanical or electrical work is exposed accidentally during the work, re-cover and refinish to match.
- I. Clean existing systems and equipment.
- J. Remove demolition debris and abandoned items from alterations areas and dispose of off-site; do not burn or bury.
- K. Do not begin new construction in alterations areas before demolition is complete.
- L. Comply with all other applicable requirements of this section.

3.07 CUTTING AND PATCHING

- A. Whenever possible, execute the work by methods that avoid cutting or patching.
- B. See Alterations article above for additional requirements.
- C. Perform whatever cutting and patching is necessary to:
 - 1. Complete the work.
 - 2. Fit products together to integrate with other work.
 - 3. Provide openings for penetration of mechanical, electrical, and other services.
 - 4. Match work that has been cut to adjacent work.
 - 5. Repair areas adjacent to cuts to required condition.
 - 6. Repair new work damaged by subsequent work.
 - 7. Remove samples of installed work for testing when requested.
 - 8. Remove and replace defective and non-complying work.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- D. Execute work by methods that avoid damage to other work and that will provide appropriate surfaces to receive patching and finishing. In existing work, minimize damage and restore to original condition.
- E. Employ original installer to perform cutting for weather exposed and moisture resistant elements, and sight exposed surfaces.
- F. Cut rigid materials using masonry saw or core drill. Pneumatic tools not allowed without prior approval.
- G. Restore work with new products in accordance with requirements of Contract Documents.
- H. Fit work air tight to pipes, sleeves, ducts, conduit, and other penetrations through surfaces.
- I. At penetrations of fire rated walls, partitions, ceiling, or floor construction, completely seal voids with fire rated material in accordance with Section 078400, to full thickness of the penetrated element.
- J. Patching:
 - 1. Finish patched surfaces to match finish that existed prior to patching. On continuous surfaces, refinish to nearest intersection or natural break. For an assembly, refinish entire unit.
 - 2. Match color, texture, and appearance.
 - 3. Repair patched surfaces that are damaged, lifted, discolored, or showing other imperfections due to patching work. If defects are due to condition of substrate, repair substrate prior to repairing finish.

3.08 PROGRESS CLEANING

- A. Maintain areas free of waste materials, debris, and rubbish. Maintain site in a clean and orderly condition.
- B. Remove debris and rubbish from pipe chases, plenums, attics, crawl spaces, and other closed or remote spaces, prior to enclosing the space.
- C. Broom and vacuum clean interior areas prior to start of surface finishing, and continue cleaning to eliminate dust.
- D. Collect and remove waste materials, debris, and trash/rubbish from site periodically and dispose off-site; do not burn or bury.

3.09 PROTECTION OF INSTALLED WORK

- A. Protect installed work from damage by construction operations.
- B. Provide special protection where specified in individual specification sections.
- C. Provide temporary and removable protection for installed products. Control activity in immediate work area to prevent damage.
- D. Provide protective coverings at walls, projections, jambs, sills, and soffits of openings.
- E. Protect finished floors, stairs, and other surfaces from traffic, dirt, wear, damage, or movement of heavy objects, by protecting with durable sheet materials.
- F. Prohibit traffic or storage upon waterproofed or roofed surfaces. If traffic or activity is necessary, obtain recommendations for protection from waterproofing or roofing material manufacturer.
- G. Remove protective coverings when no longer needed; reuse or recycle coverings if possible.

3.10 SYSTEM STARTUP

- A. Coordinate schedule for start-up of various equipment and systems.
- B. Verify that each piece of equipment or system has been checked for proper lubrication, drive rotation, belt tension, control sequence, and for conditions that may cause damage.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- C. Verify tests, meter readings, and specified electrical characteristics agree with those required by the equipment or system manufacturer.
- D. Verify that wiring and support components for equipment are complete and tested.
- E. Execute start-up under supervision of applicable Contractor personnel and manufacturer's representative in accordance with manufacturers' instructions.
- F. When specified in individual specification Sections, require manufacturer to provide authorized representative to be present at site to inspect, check, and approve equipment or system installation prior to start-up, and to supervise placing equipment or system in operation.
- G. Submit a written report that equipment or system has been properly installed and is functioning correctly.

3.11 DEMONSTRATION AND INSTRUCTION

- A. Demonstrate operation and maintenance of products to Owner's personnel two weeks prior to date of Substantial Completion.
- B. Demonstrate start-up, operation, control, adjustment, trouble-shooting, servicing, maintenance, and shutdown of each item of equipment at scheduled time, at equipment location.
- C. For equipment or systems requiring seasonal operation, perform demonstration for other season within six months.
- D. Provide a qualified person who is knowledgeable about the Project to perform demonstration and instruction of Owner's personnel.

3.12 ADJUSTING

A. Adjust operating products and equipment to ensure smooth and unhindered operation.

3.13 FINAL CLEANING

- A. Use cleaning materials that are nonhazardous.
- B. Clean interior and exterior glass, surfaces exposed to view; remove temporary labels, stains and foreign substances, polish transparent and glossy surfaces, vacuum carpeted and soft surfaces.
- C. Remove all labels that are not permanent. Do not paint or otherwise cover fire test labels or nameplates on mechanical and electrical equipment.
- D. Clean equipment and fixtures to a sanitary condition with cleaning materials appropriate to the surface and material being cleaned.
- E. Clean filters of operating equipment.
- F. Clean debris from roofs, gutters, downspouts, scuppers, overflow drains, area drains, and drainage systems.
- G. Clean site; sweep paved areas, rake clean landscaped surfaces.
- H. Remove waste, surplus materials, trash/rubbish, and construction facilities from the site; dispose of in legal manner; do not burn or bury.

3.14 CLOSEOUT PROCEDURES

- A. Make submittals that are required by governing or other authorities.
- B. Accompany Project Coordinator on preliminary inspection to determine items to be listed for completion or correction in the Contractor's Correction Punch List for Contractor's Notice of Substantial Completion.
- C. Notify Architect when work is considered ready for Architect's Substantial Completion inspection.
- D. Submit written certification containing Contractor's Correction Punch List, that Contract Documents have been reviewed, work has been inspected, and that work is complete in

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

accordance with Contract Documents and ready for Architect's Substantial Completion inspection.

- E. Conduct Substantial Completion inspection and create Final Correction Punch List containing Architect's and Contractor's comprehensive list of items identified to be completed or corrected and submit to Architect.
- F. Correct items of work listed in Final Correction Punch List and comply with requirements for access to Owner-occupied areas.
- G. Notify Architect when work is considered finally complete and ready for Architect's Substantial Completion final inspection.
- H. Complete items of work determined by Architect listed in executed Certificate of Substantial Completion.

3.15 MAINTENANCE

- A. Provide service and maintenance of components indicated in specification sections.
- B. Maintenance Period: As indicated in specification sections or, if not indicated, not less than one year from the Date of Substantial Completion or the length of the specified warranty, whichever is longer.
- C. Examine system components at a frequency consistent with reliable operation. Clean, adjust, and lubricate as required.
- D. Include systematic examination, adjustment, and lubrication of components. Repair or replace parts whenever required. Use parts produced by the manufacturer of the original component.
- E. Maintenance service shall not be assigned or transferred to any agent or subcontractor without prior written consent of the Owner.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 017419 CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

PART 1 GENERAL

1.01 WASTE MANAGEMENT REQUIREMENTS

- A. Owner requires that this project generate the least amount of trash and waste possible.
- B. Employ processes that ensure the generation of as little waste as possible due to error, poor planning, breakage, mishandling, contamination, or other factors.
- C. Minimize trash/waste disposal in landfills; reuse, salvage, or recycle as much waste as economically feasible.
- D. Contractor Reporting Responsibilities: Submit periodic Waste Disposal Reports; report landfill disposal, incineration, recycling, salvage, and reuse regardless of to whom the cost or savings accrues; use the same units of measure on required reports.
- E. Methods of trash/waste disposal that are not acceptable are:
 - 1. Burning on the project site.
 - 2. Burying on the project site.
 - 3. Dumping or burying on other property, public or private.
 - 4. Other illegal dumping or burying.
- F. Regulatory Requirements: Contractor is responsible for knowing and complying with regulatory requirements, including but not limited to Federal, state and local requirements, pertaining to legal disposal of all construction and demolition waste materials.

1.02 RELATED REQUIREMENTS

- A. Section 013000 Administrative Requirements: Additional requirements for project meetings, reports, submittal procedures, and project documentation.
- B. Section 015000 Temporary Facilities and Controls: Additional requirements related to trash/waste collection and removal facilities and services.
- C. Section 016000 Product Requirements: Waste prevention requirements related to delivery, storage, and handling.
- D. Section 017000 Execution and Closeout Requirements: Trash/waste prevention procedures related to demolition, cutting and patching, installation, protection, and cleaning.

1.03 DEFINITIONS

- A. Clean: Untreated and unpainted; not contaminated with oils, solvents, caulk, or the like.
- B. Construction and Demolition Waste: Solid wastes typically including building materials, packaging, trash, debris, and rubble resulting from construction, remodeling, repair and demolition operations.
- C. Hazardous: Exhibiting the characteristics of hazardous substances, i.e., ignitibility, corrosivity, toxicity or reactivity.
- D. Nonhazardous: Exhibiting none of the characteristics of hazardous substances, i.e., ignitibility, corrosivity, toxicity, or reactivity.
- E. Nontoxic: Neither immediately poisonous to humans nor poisonous after a long period of exposure.
- F. Recyclable: The ability of a product or material to be recovered at the end of its life cycle and remanufactured into a new product for reuse by others.
- G. Recycle: To remove a waste material from the project site to another site for remanufacture into a new product for reuse by others.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- H. Recycling: The process of sorting, cleansing, treating and reconstituting solid waste and other discarded materials for the purpose of using the altered form. Recycling does not include burning, incinerating, or thermally destroying waste.
- I. Return: To give back reusable items or unused products to vendors for credit.
- J. Reuse: To reuse a construction waste material in some manner on the project site.
- K. Salvage: To remove a waste material from the project site to another site for resale or reuse by others.
- L. Sediment: Soil and other debris that has been eroded and transported by storm or well production run-off water.
- M. Source Separation: The act of keeping different types of waste materials separate beginning from the first time they become waste.
- N. Toxic: Poisonous to humans either immediately or after a long period of exposure.
- O. Trash: Any product or material unable to be reused, returned, recycled, or salvaged.
- P. Waste: Extra material or material that has reached the end of its useful life in its intended use. Waste includes salvageable, returnable, recyclable, and reusable material.

1.04 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Waste Disposal Reports: Submit at specified intervals, with details of quantities of trash and waste, means of disposal or reuse, and costs; show both totals to date and since last report.
 - 1. Submit updated Report with each Application for Progress Payment; failure to submit Report will delay payment.
 - 2. Submit Report on a form acceptable to Owner.
 - 3. Landfill Disposal: Include the following information:
 - a. Identification of material.
 - b. Amount, in tons or cubic yards (cubic meters), of trash/waste material from the project disposed of in landfills.
 - c. State the identity of landfills, total amount of tipping fees paid to landfill, and total disposal cost.
 - d. Include manifests, weight tickets, receipts, and invoices as evidence of quantity and cost.
 - 4. Incinerator Disposal: Include the following information:
 - a. Identification of material.
 - b. Amount, in tons or cubic yards (cubic meters), of trash/waste material from the project delivered to incinerators.
 - c. State the identity of incinerators, total amount of fees paid to incinerator, and total disposal cost.
 - d. Include manifests, weight tickets, receipts, and invoices as evidence of quantity and cost.
 - 5. Recycled and Salvaged Materials: Include the following information for each:
 - a. Identification of material, including those retrieved by installer for use on other projects.
 - b. Amount, in tons or cubic yards (cubic meters), date removed from the project site, and receiving party.
 - c. Transportation cost, amount paid or received for the material, and the net total cost or savings of salvage or recycling each material.
 - d. Include manifests, weight tickets, receipts, and invoices as evidence of quantity and cost.
 - e. Certification by receiving party that materials will not be disposed of in landfills or by incineration.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 6. Material Reused on Project: Include the following information for each:
 - a. Identification of material and how it was used in the project.
 - b. Amount, in tons or cubic yards (cubic meters).
 - c. Include weight tickets as evidence of quantity.
- 7. Other Disposal Methods: Include information similar to that described above, as appropriate to disposal method.

PART 3 EXECUTION

2.01 WASTE MANAGEMENT PROCEDURES

- A. See Section 013000 for additional requirements for project meetings, reports, submittal procedures, and project documentation.
- B. See Section 015000 for additional requirements related to trash/waste collection and removal facilities and services.
- C. See Section 016000 for waste prevention requirements related to delivery, storage, and handling.
- D. See Section 017000 for trash/waste prevention procedures related to demolition, cutting and patching, installation, protection, and cleaning.

2.02 WASTE MANAGEMENT PLAN IMPLEMENTATION

- A. Manager: Designate an on-site person or persons responsible for instructing workers and overseeing and documenting results of the Waste Management Plan.
- B. Communication: Distribute copies of the Waste Management Plan to job site foreman, each subcontractor, Owner, and Architect.
- C. Instruction: Provide on-site instruction of appropriate separation, handling, and recycling, salvage, reuse, and return methods to be used by all parties at the appropriate stages of the project.
- D. Meetings: Discuss trash/waste management goals and issues at project meetings.
 - 1. Prebid meeting.
 - 2. Preconstruction meeting.
 - 3. Regular job-site meetings.
- E. Facilities: Provide specific facilities for separation and storage of materials for recycling, salvage, reuse, return, and trash disposal, for use by all contractors and installers.
 - 1. Provide containers as required.
 - 2. Provide adequate space for pick-up and delivery and convenience to subcontractors.
 - 3. Keep recycling and trash/waste bin areas neat and clean and clearly marked in order to avoid contamination of materials.
- F. Hazardous Wastes: Separate, store, and dispose of hazardous wastes according to applicable regulations.
- G. Recycling: Separate, store, protect, and handle at the site identified recyclable waste products in order to prevent contamination of materials and to maximize recyclability of identified materials. Arrange for timely pickups from the site or deliveries to recycling facility in order to prevent contamination of recyclable materials.
- H. Reuse of Materials On-Site: Set aside, sort, and protect separated products in preparation for reuse.
- I. Salvage: Set aside, sort, and protect products to be salvaged for reuse off-site.

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

Construction Waste Management and Disposal

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 017800 CLOSEOUT SUBMITTALS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Project record documents.
- B. Operation and maintenance data.
- C. Warranties and bonds.

1.02 RELATED REQUIREMENTS

- A. Section 013000 Administrative Requirements: Submittals procedures, shop drawings, product data, and samples.
- B. Section 017000 Execution and Closeout Requirements: Contract closeout procedures.
- C. Individual Product Sections: Specific requirements for operation and maintenance data.
- D. Individual Product Sections: Warranties required for specific products or Work.

1.03 SUBMITTALS

- A. Project Record Documents: Submit documents to Architect with claim for final Application for Payment.
- B. Operation and Maintenance Data:
 - 1. For equipment, or component parts of equipment put into service during construction and operated by Owner, submit completed documents within ten days after acceptance.
 - 2. Submit one copy of completed documents 15 days prior to final inspection. This copy will be reviewed and returned after final inspection, with Architect comments. Revise content of all document sets as required prior to final submission.
 - 3. Submit two sets of revised final documents in final form within 10 days after final inspection.
- C. Warranties and Bonds:
 - 1. For equipment or component parts of equipment put into service during construction with Owner's permission, submit documents within 10 days after acceptance.
 - 2. Make other submittals within 10 days after Date of Substantial Completion, prior to final Application for Payment.
 - 3. For items of Work for which acceptance is delayed beyond Date of Substantial Completion, submit within 10 days after acceptance, listing the date of acceptance as the beginning of the warranty period.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 PROJECT RECORD DOCUMENTS

- A. Maintain on site one set of the following record documents; record actual revisions to the Work:
 1. Drawings.
 - 2. Specifications.
 - 3. Addenda.
 - 4. Change Orders and other modifications to the Contract.
 - 5. Reviewed shop drawings, product data, and samples.
 - 6. Manufacturer's instruction for assembly, installation, and adjusting.
- B. Ensure entries are complete and accurate, enabling future reference by Owner.
- C. Store record documents separate from documents used for construction.
- D. Record information concurrent with construction progress.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- E. Specifications: Legibly mark and record at each product section description of actual products installed, including the following:
 - 1. Changes made by Addenda and modifications.
- F. Record Drawings and Shop Drawings: Legibly mark each item to record actual construction including:
 - 1. Field changes of dimension and detail.
 - 2. Details not on original Contract drawings.

3.02 OPERATION AND MAINTENANCE DATA

- A. Product Data: Mark each sheet to clearly identify specific products and component parts, and data applicable to installation. Delete inapplicable information.
- B. Drawings: Supplement product data to illustrate relations of component parts of equipment and systems, to show control and flow diagrams. Do not use Project Record Documents as maintenance drawings.
- C. Typed Text: As required to supplement product data. Provide logical sequence of instructions for each procedure, incorporating manufacturer's instructions.

3.03 OPERATION AND MAINTENANCE DATA FOR MATERIALS AND FINISHES

A. Where additional instructions are required, beyond the manufacturer's standard printed instructions, have instructions prepared by personnel experienced in the operation and maintenance of the specific products.

3.04 OPERATION AND MAINTENANCE DATA FOR EQUIPMENT AND SYSTEMS

- A. Where additional instructions are required, beyond the manufacturer's standard printed instructions, have instructions prepared by personnel experienced in the operation and maintenance of the specific products.
- B. Panelboard Circuit Directories: Provide electrical service characteristics, controls, and communications; typed.
- C. Include color coded wiring diagrams as installed.
- D. Operating Procedures: Include start-up, break-in, and routine normal operating instructions and sequences. Include regulation, control, stopping, shut-down, and emergency instructions. Include summer, winter, and any special operating instructions.
- E. Maintenance Requirements: Include routine procedures and guide for preventative maintenance and trouble shooting; disassembly, repair, and reassembly instructions; and alignment, adjusting, balancing, and checking instructions.
 - 1. Include HVAC outdoor and exhaust air damper calibration strategy.
 - a. Include provisions which ensure that full closure of dampers can be achieved.
 - 2. Include Carbon Dioxide Monitoring Protocol.
 - 3. Include Carbon Monoxide Monitoring Protocol.
 - 4. Include Frost Mitigation Strategy for ventilation heat-recovery system.

3.05 ASSEMBLY OF OPERATION AND MAINTENANCE MANUALS

- A. Assemble operation and maintenance data into durable manuals for Owner's personnel use, with data arranged in the same sequence as, and identified by, the specification sections.
- B. Where systems involve more than one specification section, provide separate tabbed divider for each system.
- C. Binders: Commercial quality, 8-1/2 by 11 inch (216 by 280 mm) three D side ring binders with durable plastic covers; 2 inch (50 mm) maximum ring size. When multiple binders are used, correlate data into related consistent groupings.
- D. Cover: Identify each binder with typed or printed title OPERATION AND MAINTENANCE INSTRUCTIONS; identify title of Project; identify subject matter of contents.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- E. Project Directory: Title and address of Project; names, addresses, and telephone numbers of Architect, Consultants, Contractor and subcontractors, with names of responsible parties.
- F. Tables of Contents: List every item separated by a divider, using the same identification as on the divider tab; where multiple volumes are required, include all volumes Tables of Contents in each volume, with the current volume clearly identified.
- G. Dividers: Provide tabbed dividers for each separate product and system; identify the contents on the divider tab; immediately following the divider tab include a description of product and major component parts of equipment.
- H. Text: Manufacturer's printed data, or typewritten data on 20 pound paper.
- I. Drawings: Provide with reinforced punched binder tab. Bind in with text; fold larger drawings to size of text pages.
- J. Arrangement of Contents: Organize each volume in parts as follows:
 - 1. Project Directory.
 - 2. Table of Contents, of all volumes, and of this volume.
 - 3. Operation and Maintenance Data: Arranged by system, then by product category.
 - a. Source data.
 - b. Product data, shop drawings, and other submittals.
 - c. Operation and maintenance data.
 - d. Field quality control data.
 - e. Photocopies of warranties and bonds.
 - 4. Design Data: To allow for addition of design data furnished by Architect or others, provide a tab labeled "Design Data" and provide a binder large enough to allow for insertion of at least 20 pages of typed text.

3.06 WARRANTIES AND BONDS

- A. Obtain warranties and bonds, executed in duplicate by responsible Subcontractors, suppliers, and manufacturers, within 10 days after completion of the applicable item of work. Except for items put into use with Owner's permission, leave date of beginning of time of warranty until Date of Substantial completion is determined.
- B. Verify that documents are in proper form, contain full information, and are notarized.
- C. Co-execute submittals when required.
- D. Retain warranties and bonds until time specified for submittal.

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 024100 DEMOLITION

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Selective demolition of building elements for alteration purposes.

1.02 RELATED REQUIREMENTS

- A. Section 015000 Temporary Facilities and Controls: Site fences, security, protective barriers, and waste removal.
- B. Section 017000 Execution and Closeout Requirements: Project conditions; protection of bench marks, survey control points, and existing construction to remain; reinstallation of removed products; temporary bracing and shoring.
- C. Section 312200 Grading: Rough and fine grading.
- D. Section 312323 Fill: Fill material for filling holes, pits, and excavations generated as a result of removal operations.

1.03 DEFINITIONS

- A. Demolition: Dismantle, raze, destroy or wreck any building or structure or any part thereof.
- B. Remove: Detach or dismantle items from existing construction and dispose of them off site, unless items are indicated to be salvaged or reinstalled.
- C. Remove and Salvage: Detach or dismantle items from existing construction in a manner to prevent damage. Clean, package, label and deliver salvaged items to Owner in ready-for-reuse condition.
- D. Remove and Reinstall: Detach or dismantle items from existing construction in a manner to prevent damage. Clean and prepare for reuse and reinstall where indicated.
- E. Existing to Remain: Designation for existing items that are not to be removed and that are not otherwise indicated to be salvaged or reinstalled.

1.04 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Site Plan: Indicate:
 - 1. Areas for temporary construction and field offices.
- C. Demolition Plan: Submit demolition plan as required by OSHA and local AHJs.
 - 1. Indicate extent of demolition, removal sequencing, bracing and shoring, and location and construction of barricades and fences.
 - 2. Demolition firm qualifications.
- D. Project Record Documents: Accurately record actual locations of capped and active utilities and subsurface construction.

1.05 QUALITY ASSURANCE

A. Demolition Firm Qualifications: Company specializing in the type of work required.1. Minimum of five years of documented experience.

PART 2 PRODUCTS

2.01 MATERIALS

A. Fill Material: See Section 312323.

PART 3 EXECUTION

3.01 DEMOLITION

A. Remove the entire buildings designated Two Story Brick Building and Brick Garage.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- B. Remove paving and curbs required to accomplish new work.
- C. Remove concrete slabs on grade as indicated on drawings.
- D. Remove other items indicated, for salvage, relocation, and recycling.
- E. Fill excavations, open pits, and holes in ground areas generated as result of removals, using specified fill; compact fill as specified in Section 312200.

3.02 GENERAL PROCEDURES AND PROJECT CONDITIONS

- A. Comply with requirements in Section 017000.
- B. Comply with applicable codes and regulations for demolition operations and safety of adjacent structures and the public.
 - 1. Obtain required permits.
 - 2. Use of explosives is not permitted.
 - 3. Take precautions to prevent catastrophic or uncontrolled collapse of structures to be removed; do not allow worker or public access within range of potential collapse of unstable structures.
 - 4. Provide, erect, and maintain temporary barriers and security devices.
 - 5. Conduct operations to minimize effects on and interference with adjacent structures and occupants.
 - 6. Do not close or obstruct roadways or sidewalks without permits from authority having jurisdiction.
 - 7. Conduct operations to minimize obstruction of public and private entrances and exits. Do not obstruct required exits at any time. Protect persons using entrances and exits from removal operations.
 - 8. Obtain written permission from owners of adjacent properties when demolition equipment will traverse, infringe upon, or limit access to their property.
- C. Do not begin removal until receipt of notification to proceed from Owner.
- D. Protect existing structures and other elements to remain in place and not removed.
 - 1. Provide bracing and shoring.
 - 2. Prevent movement or settlement of adjacent structures.
 - 3. Stop work immediately if adjacent structures appear to be in danger.
- E. Minimize production of dust due to demolition operations. Do not use water if that will result in ice, flooding, sedimentation of public waterways or storm sewers, or other pollution.
- F. Hazardous Materials:
 - 1. If hazardous materials are discovered during removal operations, stop work and notify Architect and Owner; hazardous materials include regulated asbestos containing materials, lead, PCBs, and mercury.
- G. Partial Removal of Paving and Curbs: Neatly saw cut at right angle to surface.

3.03 EXISTING UTILITIES

- A. Coordinate work with utility companies. Notify utilities before starting work, comply with their requirements, and obtain required permits.
- B. Protect existing utilities to remain from damage.
- C. Do not disrupt public utilities without permit from authority having jurisdiction.
- D. Do not close, shut off, or disrupt existing life safety systems that are in use without at least 7 days prior written notification to Owner.
- E. Do not close, shut off, or disrupt existing utility branches or take-offs that are in use without at least 3 days prior written notification to Owner.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- F. Locate and mark utilities to remain; mark using highly visible tags or flags, with identification of utility type; protect from damage due to subsequent construction, using substantial barricades if necessary.
- G. Remove exposed piping, valves, meters, equipment, supports, and foundations of disconnected and abandoned utilities.
- H. Prepare building demolition areas by disconnecting and capping utilities outside the demolition zone. Identify and mark, in same manner as other utilities to remain, utilities to be reconnected.

3.04 SELECTIVE DEMOLITION FOR ALTERATIONS

- A. Existing construction and utilities indicated on drawings are based on casual field observation and existing record documents only.
 - 1. Verify construction and utility arrangements are as indicated.
 - 2. Report discrepancies to Architect before disturbing existing installation.
 - 3. Beginning of demolition work constitutes acceptance of existing conditions that would be apparent upon examination prior to starting demolition.
- B. Separate areas in which demolition is being conducted from areas that remain occupied.
 - 1. Provide, erect, and maintain temporary dustproof partitions of construction specified in Section 015000 in locations indicated on drawings.
- C. Maintain weatherproof exterior building enclosure, except for interruptions required for replacement or modifications; prevent water and humidity damage.
- D. Remove existing work as indicated and required to accomplish new work.
 - 1. Remove items indicated on drawings.
- E. Services including, but not limited to, HVAC, Plumbing, Fire Protection, Electrical, and Telecommunications: Remove existing systems and equipment as indicated.
 - 1. Maintain existing active systems to remain in operation, and maintain access to equipment and operational components.
 - 2. Where existing active systems serve occupied facilities but are to be replaced with new services, maintain existing systems in service until new systems are complete and ready for service.
 - 3. Verify that abandoned services serve only abandoned facilities before removal.
 - 4. Remove abandoned pipe, ducts, conduits, and equipment, including those above accessible ceilings. Remove back to source of supply where possible, otherwise cap stub and tag with identification.
- F. Protect existing work to remain.
 - 1. Prevent movement of structure. Provide shoring and bracing as required.
 - 2. Perform cutting to accomplish removal work neatly and as specified for cutting new work.
 - 3. Repair adjacent construction and finishes damaged during removal work.
 - 4. Patch to match new work.

3.05 DEBRIS AND WASTE REMOVAL

- A. Remove debris, junk, and trash from site.
- B. Leave site in clean condition, ready for subsequent work.
- C. Clean up spillage and wind-blown debris from public and private lands.

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

Demolition

024100 - 4
50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 033000 CAST-IN-PLACE CONCRETE

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. 40 CFR 59, Subpart D National Volatile Organic Compound Emission Standards for Architectural Coatings; U.S. Environmental Protection Agency; Current Edition.
- B. ASTM A615/A615M Standard Specification for Deformed and Plain Carbon-Steel Bars for Concrete Reinforcement; 2022.
- C. ASTM C31/C31M Standard Practice for Making and Curing Concrete Test Specimens in the Field; 2024.
- D. ASTM C39/C39M Standard Test Method for Compressive Strength of Cylindrical Concrete Specimens; 2023.
- E. ASTM C94/C94M Standard Specification for Ready-Mixed Concrete; 2024.
- F. ASTM C143/C143M Standard Test Method for Slump of Hydraulic-Cement Concrete; 2020.
- G. ASTM C171 Standard Specification for Sheet Materials for Curing Concrete; 2020.
- H. ASTM C309 Standard Specification for Liquid Membrane-Forming Compounds for Curing Concrete; 2019.
- I. ASTM C494/C494M Standard Specification for Chemical Admixtures for Concrete; 2019, with Editorial Revision (2022).
- J. ASTM C618 Standard Specification for Coal Ash and Raw or Calcined Natural Pozzolan for Use in Concrete; 2023, with Editorial Revision.
- K. ASTM C1059/C1059M Standard Specification for Latex Agents for Bonding Fresh to Hardened Concrete; 2021.
- L. ASTM C1116/C1116M Standard Specification for Fiber-Reinforced Concrete; 2023.
- M. ASTM C1240 Standard Specification for Silica Fume Used in Cementitious Mixtures; 2020.
- N. ASTM D1751 Standard Specification for Preformed Expansion Joint Filler for Concrete Paving and Structural Construction (Nonextruding and Resilient Asphalt Types); 2023.
- O. ASTM D1752 Standard Specification for Preformed Sponge Rubber, Cork, and Recycled PVC Expansion Joint Fillers for Concrete Paving and Structural Construction; 2018 (Reapproved 2023).
- P. ASTM D4397 Standard Specification for Polyethylene Sheeting for Construction, Industrial, and Agricultural Applications; 2016 (Reapproved 2023).
- Q. ASTM E1155 Standard Test Method for Determining FF Floor Flatness and FL Floor Levelness Numbers; 2020.
- R. ASTM E1643 Standard Practice for Selection, Design, Installation, and Inspection of Water Vapor Retarders Used in Contact with Earth or Granular Fill Under Concrete Slabs; 2018a.
- S. AWS D1.4/D1.4M Structural Welding Code Steel Reinforcing Bars; 2018, with Amendment (2020).

1.02 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.03 SUMMARY

A. Section includes cast-in-place concrete, including formwork, reinforcement, concrete materials, mixture design, placement procedures, and finishes.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

1.04 ACTION SUBMITTALS

- A. Design Mixtures: Include mix proportions and mix histories demonstrating a consistent record of achieving required strength.
- B. Steel Reinforcement Shop Drawings: Include bar sizes, lengths, material, grade, bar schedules, stirrup spacing, bent bar diagrams, bar arrangement, splices and laps, mechanical connections, tie spacing, hoop spacing, and supports for concrete reinforcement.
- C. Construction Joint Layout: Indicate proposed construction joints required to construct the structure.

1.05 INFORMATIONAL SUBMITTALS

- A. Field quality-control reports.
- B. Material Certificates: For each of the following if included on the scope of the project
 - 1. Cementitious materials
 - 2. Aggregate.
 - 3. Admixtures.
 - 4. Form materials and form-release agents.
 - 5. Steel reinforcement and accessories.
 - 6. Fiber reinforcement.
 - 7. Waterstops.
 - 8. Curing compounds.
 - 9. Floor and slab treatments.
 - 10. Bonding agents.
 - 11. Adhesives.
 - 12. Vapor retarders.
 - 13. Semirigid joint filler.
 - 14. Joint-filler strips.
 - 15. Repair materials.

1.06 QUALITY ASSURANCE

- A. Concrete Testing Service: Engage a qualified independent testing agency to perform material evaluation tests and to design concrete mixtures.
- B. Source Limitations: Obtain each type or class of cementitious material of the same brand from the same manufacturer's plant, obtain aggregate from single source, and obtain admixtures from single source from single manufacturer.

1.07 DELIVERY, STORAGE, AND HANDLING

A. Deliver, store, and handle all materials as needed to prevent damage.

PART 2 PRODUCTS

2.01 FORM-FACING MATERIALS

- A. Smooth-Formed Finished Concrete: Form-facing panels that will provide continuous, true, and smooth concrete surfaces. Furnish in largest practicable sizes to minimize number of joints.
 1. Plywood, metal, or other approved panel materials.
- B. Rough-Formed Finished Concrete: Plywood, lumber, metal, or another approved material. Provide lumber dressed on at least two edges and one side for tight fit.
- C. Forms for Cylindrical Columns, Pedestals, and Supports: Metal, glass-fiber-reinforced plastic, paper, or fiber tubes that will produce surfaces with gradual or abrupt irregularities not exceeding specified formwork surface class. Provide units with sufficient wall thickness to resist plastic concrete loads without detrimental deformation.
- D. Chamfer Strips: Wood, metal, PVC, or rubber strips, 3/4 by 3/4 inch (19.05 mm), minimum.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- E. Form-Release Agent: Commercially formulated form-release agent that will not bond with, stain, or adversely affect concrete surfaces and will not impair subsequent treatments of concrete surfaces.
- F. Form Ties: Factory-fabricated, removable or snap-off metal or glass-fiber-reinforced plastic form ties designed to resist lateral pressure of fresh concrete on forms and to prevent spalling of concrete on removal.
 - 1. Furnish units that will leave no corrodible metal closer than 1 inch (25.4 mm) to the plane of exposed concrete surface.
 - 2. Furnish ties that, when removed, will leave holes no larger than 1 inch (25.4 mm) in diameter in concrete surface.

2.02 STEEL REINFORCEMENT

- A. Recycled Content of Steel Products: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 60 percent.
- B. Reinforcing Bars: ASTM A615/A615M, Grade 60 deformed bars.
- C. Plain-Steel Welded Wire Reinforcement: ASTM A 185/A 185M, plain, fabricated from as-drawn steel wire into flat sheets.
- D. Plain-Steel Wire: ASTM A 82/A 82M

2.03 REINFORCEMENT ACCESSORIES

- A. Joint Dowel Bars: ASTM A 615, Grade 60 plain-steel bars, cut true to length with ends square and free of burrs.
- B. Epoxy Repair Coating: Liquid, two-part, epoxy repair coating; compatible with epoxy coating on reinforcement and complying with ASTM A 775.
- C. Zinc Repair Material: ASTM A 780, zinc-based solder, paint containing zinc dust, or sprayed zinc.
- D. Bar Supports: Bolsters, chairs, spacers, and other devices for spacing, supporting, and fastening reinforcing bars and welded wire reinforcement in place. Manufacture bar supports from steel wire, plastic, or precast concrete according to CRSI's "Manual of Standard Practice," of greater compressive strength than concrete and as follows:
 - 1. For concrete surfaces exposed to view where legs of wire bar supports contact forms, use CRSI Class 1 plastic-protected steel wire or CRSI Class 2 stainless-steel bar supports.

2.04 CONCRETE MATERIALS

- A. Cementitious Material: Use the following cementitious materials, of the same type, brand, and source, throughout Project:
 - 1. Portland Cement: ASTM C 150, Type I. Supplement with the following:
 - a. Fly Ash: ASTM C618, Class F or C.
 - b. Ground Granulated Blast-Furnace Slag: ASTM C 989, Grade 100 or 120.
 - c. Silica Fume: ASTM C1240, amorphous silica.
- B. Normal-Weight Aggregates: ASTM C 33, coarse aggregate from a single source
 - 1. Maximum Coarse-Aggregate Size: 1-1/2 inches (38 mm) nominal.
 - 2. Fine Aggregate: Free of materials with deleterious reactivity to alkali in cement.
- C. Lightweight Aggregate: ASTM C 330, 1-inch nominal maximum aggregate size.
- D. Water: ASTM C 94, potable.

2.05 ADMIXTURES

- A. Air-Entraining Admixture: ASTM C 260.
- B. Chemical Admixtures: Provide admixtures certified by manufacturer to be compatible with other admixtures and that will not contribute water-soluble chloride ions exceeding those permitted in

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

hardened concrete. Do not use calcium chloride or admixtures containing calcium chloride.

- 1. Water-Reducing Admixture: ASTM C 494, Type A.
- 2. Retarding Admixture: ASTM C 494, Type B.
- 3. Water-Reducing and Retarding Admixture: ASTM C 494, Type D.
- 4. High-Range, Water-Reducing Admixture: ASTM C 494, Type F.
- 5. High-Range, Water-Reducing and Retarding Admixture: ASTM C 494, Type G.
- 6. Plasticizing and Retarding Admixture: ASTM C 1017, Type II.
- C. Set-Accelerating Corrosion-Inhibiting Admixture: Commercially formulated, anodic inhibitor or mixed cathodic and anodic inhibitor; capable of forming a protective barrier and minimizing chloride reactions with steel reinforcement in concrete and complying with ASTM C494/C494M, Type C.
- D. Non-Set-Accelerating Corrosion-Inhibiting Admixture: Commercially formulated, non-setaccelerating, anodic inhibitor or mixed cathodic and anodic inhibitor; capable of forming a protective barrier and minimizing chloride reactions with steel reinforcement in concrete.
- E. Color Pigment: ASTM C 979, synthetic mineral-oxide pigments or colored water-reducing admixtures; color stable, free of carbon black, nonfading, and resistant to lime and other alkalis.

2.06 FIBER REINFORCEMENT

- A. Synthetic Micro-Fiber: Monofilament or fibrillated polypropylene micro-fibers engineered and designed for use in concrete, complying with ASTM C1116/C1116M, Type III, 1/2 to 1-1/2 inches (38 mm).
- B. Synthetic Macro-Fiber: Polyolefin macro-fibers engineered and designed for use in concrete, complying with ASTM C1116/C1116M, Type III, 1 to 2-1/4 inches (57 mm).

2.07 WATERSTOPS

- A. Flexible PVC Waterstops: CE CRD-C 572, for embedding in concrete to prevent passage of fluids through joints. Factory fabricate corners, intersections, and directional changes.
- B. Self-Expanding Strip Waterstops: Manufactured rectangular or trapezoidal strip, bentonite-free hydrophilic polymer modified chloroprene rubber, for adhesive bonding to concrete.

2.08 VAPOR RETARDERS

A. Sheet Vapor Retarder: Polyethylene sheet, ASTM D4397, not less than 10 mils (0.254 mm) thick.

2.09 LIQUID FLOOR TREATMENTS

- A. VOC Content: Liquid floor treatments shall have a VOC content of 200 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- B. Penetrating Liquid Floor Treatment: Clear, chemically reactive, waterborne solution of inorganic silicate or siliconate materials and proprietary components; odorless; that penetrates, hardens, and densifies concrete surfaces.
- C. Penetrating Liquid Floor Treatments for Polished Concrete Finish: Clear, waterborne solution of inorganic silicate or siliconate materials and proprietary components; odorless; that penetrates, hardens, and is suitable for polished concrete surfaces.

2.10 CURING MATERIALS

- A. Evaporation Retarder: Waterborne, monomolecular film forming, manufactured for
- B. Absorptive Cover: AASHTO M 182, Class 2, burlap cloth made from jute or kenaf, weighing approximately 9 oz./sq. yd. when dry.
- C. Moisture-Retaining Cover: ASTM C171, polyethylene film or white burlap-polyethylene sheet.
- D. Water: Potable.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

E. Clear, Waterborne, Membrane-Forming Curing Compound: ASTM C309, Type 1, Class B, nondissipating, certified by curing compound manufacturer to not interfere with bonding of floor covering.

2.11 RELATED MATERIALS

- A. Expansion- and Isolation-Joint-Filler Strips: ASTM D1751, asphalt-saturated cellulosic fiber or ASTM D1752, cork or self-expanding cork.
- B. Bonding Agent: ASTM C1059/C1059M, Type II, non-redispersible, acrylic emulsion or styrene butadiene.
- C. Epoxy Bonding Adhesive: ASTM C 881, two-component epoxy resin, capable of humid curing and bonding to damp surfaces, of class suitable for application temperature and of grade to suit requirements, and as follows:
- D. Reglets: Fabricate reglets of not less than 0.022-inch thick, galvanized-steel sheet. Temporarily fill or cover face opening of reglet to prevent intrusion of concrete or debris.
- E. Dovetail Anchor Slots: Hot-dip galvanized-steel sheet, not less than 0.034 inch (0.86 mm) thick, with bent tab anchors. Temporarily fill or cover face opening of slots to prevent intrusion of concrete or debris.

2.12 REPAIR MATERIALS

- A. Slab Repair: Cement-based, polymer-modified, self-leveling product that can be applied in thicknesses from 1/8 inch (3.18 mm) and that can be feathered at edges to match adjacent floor elevations.
 - 1. Cement Binder: ASTM C 150, portland cement or hydraulic or blended hydraulic cement as defined in ASTM C 219.
 - 2. Primer: Product of underlayment manufacturer recommended for substrate, conditions, and application.
 - 3. Aggregate: Well-graded, washed gravel, 1/8 to 1/4 inch (6.35 mm) or coarse sand as recommended by underlayment manufacturer.
 - 4. Compressive Strength: Not less than 4000 psi (27579.04 kPa) at 28 days when tested according to ASTM C 109.

2.13 CONCRETE MIXTURES, GENERAL

- A. Prepare design mixtures for each type and strength of concrete, proportioned on the basis of laboratory trial mixture or field test data, or both, according to ACI 301.
 - 1. Use a qualified independent testing agency for preparing and reporting proposed mixture designs based on laboratory trial mixtures.
- B. Cementitious Materials: Limit percentage, by weight, of cementitious materials other than portland cement in concrete as follows:
 - 1. Fly Ash: 25 percent.
 - 2. Combined Fly Ash and Pozzolan: 25 percent.
 - 3. Ground Granulated Blast-Furnace Slag: 50 percent.
 - 4. Combined Fly Ash or Pozzolan and Ground Granulated Blast-Furnace Slag: 50 percent portland cement minimum, with fly ash or pozzolan not exceeding 25 percent.
 - 5. Silica Fume: 10 percent.
 - 6. Combined Fly Ash, Pozzolans, and Silica Fume: 35 percent with fly ash or pozzolans not exceeding 25 percent and silica fume not exceeding 10 percent.
 - 7. Combined Fly Ash or Pozzolans, Ground Granulated Blast-Furnace Slag, and Silica Fume: 50 percent with fly ash or pozzolans not exceeding 25 percent and silica fume not exceeding 10 percent.
- C. Limit water-soluble, chloride-ion content in hardened concrete to 0.15 percent by weight of cement.

LAHC – WORKFORCE
EDUCATION RESOURCE AND
DEVELOPMENT CENTER

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

D. Admixtures: Use admixtures according to manufacturer's written instructions.

2.14 CONCRETE MIXTURES FOR BUILDING ELEMENTS

A. Proportion concrete mixes as specified on drawings.

2.15 FABRICATING REINFORCEMENT

A. Fabricate steel reinforcement according to CRSI's "Manual of Standard Practice."

2.16 CONCRETE MIXING

- A. Ready-Mixed Concrete: Measure, batch, mix, and deliver concrete according to ASTM C 94 and ASTM C 1116, and furnish batch ticket information.
 - 1. When air temperature is between 85 and 90 degrees Fahrenheit (32.22 degrees Celsius), reduce mixing and delivery time from 1-1/2 hours to 75 minutes; when air temperature is above 90 deg F reduce mixing and delivery time to 60 minutes.
- B. Project-Site Mixing: Measure, batch, and mix concrete materials and concrete according to ASTM C94/C94M. Mix concrete materials in appropriate drum-type batch machine mixer.
 - 1. For mixer capacity of 1 cu. yd or smaller, continue mixing at least 1-1/2 minutes, but not more than 5 minutes after ingredients are in mixer, before any part of batch is released.
 - 2. For mixer capacity larger than 1 cu. yd, increase mixing time by 15 seconds for each additional1 cu. yd.
 - 3. Provide batch ticket for each batch discharged and used in the Work, indicating Project identification name and number, date, mixture type, mixture time, quantity, and amount of water added. Record approximate location of final deposit in structure.

PART 3 EXECUTION

3.01 FORMWORK

- A. Design, erect, shore, brace, and maintain formwork, according to ACI 301, to support vertical, lateral, static, and dynamic loads, and construction loads that might be applied, until structure can support such loads.
- B. Construct formwork so concrete members and structures are of size, shape, alignment, elevation, and position indicated, within tolerance limits of ACI 117.
- C. Limit concrete surface irregularities, designated by ACI 347 as abrupt or gradual, as follows:
 - 1. Class A, 1/8 inch (3.18 mm), for smooth-formed finished surfaces.
 - 2. Class B, 1/4 inch (6.35 mm), Class C, 1/2 inch (12.7 mm), Class D, 1 inch (25.4 mm) for rough-formed finished surfaces.
- D. Construct forms tight enough to prevent loss of concrete mortar.
- E. Fabricate forms for easy removal without hammering or prying against concrete surfaces. Provide crush or wrecking plates where stripping may damage cast concrete surfaces. Provide top forms for inclined surfaces steeper than 1.5 horizontal to 1 vertical.
 - 1. Install keyways, reglets, recesses, and the like, for easy removal.
 - 2. Do not use rust-stained steel form-facing material.
- F. Set edge forms, bulkheads, and intermediate screed strips for slabs to achieve required elevations and slopes in finished concrete surfaces. Provide and secure units to support screed strips; use strike-off templates or compacting-type screeds.
- G. Provide temporary openings for cleanouts and inspection ports where interior area of formwork is inaccessible. Close openings with panels tightly fitted to forms and securely braced to prevent loss of concrete mortar. Locate temporary openings in forms at inconspicuous locations.
- H. Chamfer exterior corners and edges of permanently exposed concrete.
- I. Form openings, chases, offsets, sinkages, keyways, reglets, blocking, screeds, and bulkheads required in the Work. Determine sizes and locations from trades providing such items.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- J. Clean forms and adjacent surfaces to receive concrete. Remove chips, wood, sawdust, dirt, and other debris just before placing concrete.
- K. Retighten forms and bracing before placing concrete, as required, to prevent mortar leaks and maintain proper alignment.
- L. Coat contact surfaces of forms with form-release agent, according to manufacturer's written instructions, before placing reinforcement.

3.02 EMBEDDED ITEMS

- A. Place and secure anchorage devices and other embedded items required for adjoining work that is attached to or supported by cast-in-place concrete. Use setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
 - Install anchor rods, accurately located, to elevations required and complying with tolerances in Section 7.5 of AISC's "Code of Standard Practice for Steel Buildings and Bridges."
 - 2. Install reglets to receive waterproofing and to receive through-wall flashings in outer face of concrete frame at exterior walls, where flashing is shown at lintels, shelf angles, and other conditions.
 - 3. Install dovetail anchor slots in concrete structures as indicated.

3.03 REMOVING AND REUSING FORMS

- A. General: Formwork for sides of beams, walls, columns, and similar parts of the Work that does not support weight of concrete may be removed after cumulatively curing at not less than 50 degrees Fahrenheit (10 degrees Celsius) for 24 hours after placing concrete. Concrete has to be hard enough to not be damaged by form-removal operations and curing and protection operations need to be maintained.
 - 1. Leave formwork for beam soffits, joists, slabs, and other structural elements that supports weight of concrete in place until concrete has achieved at least 70 percent of its 28-day design compressive strength.
 - 2. Remove forms only if shores have been arranged to permit removal of forms without loosening or disturbing shores.
- B. Clean and repair surfaces of forms to be reused in the Work. Split, frayed, delaminated, or otherwise damaged form-facing material will not be acceptable for exposed surfaces. Apply new form-release agent.
- C. When forms are reused, clean surfaces, remove fins and laitance, and tighten to close joints. Align and secure joints to avoid offsets. Do not use patched forms for exposed concrete surfaces unless approved by Architect.

3.04 VAPOR RETARDERS

- A. Sheet Vapor Retarders: Place, protect, and repair sheet vapor retarder according to ASTM E1643 and manufacturer's written instructions.
 - 1. Lap joints 6 inches (152.4 mm) and seal with manufacturer's recommended tape.

4.01 STEEL REINFORCEMENT

- A. General: Comply with CRSI's "Manual of Standard Practice" for placing reinforcement.
 - 1. Do not cut or puncture vapor retarder. Repair damage and reseal vapor retarder before placing concrete.
- B. Clean reinforcement of loose rust and mill scale, earth, ice, and other foreign materials that would reduce bond to concrete.
- C. Accurately position, support, and secure reinforcement against displacement. Locate and support reinforcement with bar supports to maintain minimum concrete cover. Do not tack weld crossing reinforcing bars.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 1. Weld reinforcing bars according to AWS D1.4/D1.4M, where indicated.
- D. Set wire ties with ends directed into concrete, not toward exposed concrete surfaces.
- E. Install welded wire reinforcement in longest practicable lengths on bar supports spaced to minimize sagging. Lap edges and ends of adjoining sheets at least one mesh spacing. Offset laps of adjoining sheet widths to prevent continuous laps in either direction. Lace overlaps with wire.

4.02 JOINTS

- A. General: Construct joints true to line with faces perpendicular to surface plane of concrete.
- B. Construction Joints: Install so strength and appearance of concrete are not impaired, at locations indicated or as approved by Architect.
 - 1. Place joints perpendicular to main reinforcement. Continue reinforcement across construction joints unless otherwise indicated. Do not continue reinforcement through sides of strip placements of floors and slabs.
 - 2. Form keyed joints as indicated. Embed keys at least 1-1/2 inches (38 mm) into concrete.
 - 3. Locate joints for beams, slabs, joists, and girders in the middle third of spans. Offset joints in girders a minimum distance of twice the beam width from a beam-girder intersection.
 - 4. Locate horizontal joints in walls and columns at underside of floors, slabs, beams, and girders and at the top of footings or floor slabs.
 - 5. Space vertical joints in walls as indicated. Locate joints beside piers integral with walls, near corners, and in concealed locations where possible.
 - 6. Use a bonding agent at locations where fresh concrete is placed against hardened or partially hardened concrete surfaces.
 - 7. Use epoxy-bonding adhesive at locations where fresh concrete is placed against hardened or partially hardened concrete surfaces.
- C. Contraction Joints in Slabs-on-Grade: Form weakened-plane contraction joints, sectioning concrete into areas as indicated. Construct contraction joints for a depth equal to at least one-fourth of concrete thickness as follows:
 - 1. Grooved Joints: Form contraction joints after initial floating by grooving and finishing each edge of joint to a radius of 1/8 inch (3.18 mm) (Repeat grooving of contraction joints after applying surface finishes. Eliminate groover tool marks on concrete surfaces.
 - 2. Sawed Joints: Form contraction joints with power saws equipped with shatterproof abrasive or diamond-rimmed blades. Cut 1/8-inch wide joints into concrete when cutting action will not tear, abrade, or otherwise damage surface and before concrete develops random contraction cracks.
- D. Isolation Joints in Slabs-on-Grade: After removing formwork, install joint-filler strips at slab junctions with vertical surfaces, such as column pedestals, foundation walls, grade beams, and other locations, as indicated.
 - 1. Extend joint-filler strips full width and depth of joint, terminating flush with finished concrete surface unless otherwise indicated.
 - Terminate full-width joint-filler strips not less than 1/2 inch (12.7 mm) or more than 1 inch (25.4 mm) below finished concrete surface where joint sealants, specified in Section 079200 "Joint Sealants," are indicated.
 - 3. Install joint-filler strips in lengths as long as practicable. Where more than one length is required, lace or clip sections together.
- E. Doweled Joints: Install dowel bars and support assemblies at joints where indicated. Lubricate or asphalt coat one-half of dowel length to prevent concrete bonding to one side of joint.

4.03 WATERSTOPS

A. Flexible Waterstops: Install in construction joints and at other joints indicated to form a continuous diaphragm. Install in longest lengths practicable. Support and protect exposed waterstops during progress of the Work. Field fabricate joints in waterstops according to

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

manufacturer's written instructions.

B. Self-Expanding Strip Waterstops: Install in construction joints and at other locations indicated, according to manufacturer's written instructions, adhesive bonding, mechanically fastening, and firmly pressing into place. Install in longest lengths practicable.

4.04 CONCRETE PLACEMENT

- A. Before placing concrete, verify that installation of formwork, reinforcement, and embedded items is complete and that required inspections have been performed.
- B. Do not add water to concrete during delivery, at Project site, or during placement unless approved by Architect.
- C. Before test sampling and placing concrete, water may be added at Project site, subject to limitations of ACI 301.
 - 1. Do not add water to concrete after adding high-range water-reducing admixtures to mixture.
- D. Deposit concrete continuously in one layer or in horizontal layers of such thickness that no new concrete will be placed on concrete that has hardened enough to cause seams or planes of weakness. If a section cannot be placed continuously, provide construction joints as indicated. Deposit concrete to avoid segregation.
 - 1. Deposit concrete in horizontal layers of depth to not exceed formwork design pressures and in a manner to avoid inclined construction joints.
 - 2. Consolidate placed concrete with mechanical vibrating equipment according to ACI 301.
 - 3. Do not use vibrators to transport concrete inside forms. Insert and withdraw vibrators vertically at uniformly spaced locations to rapidly penetrate placed layer and at least 6 inches (152.4 mm) into preceding layer. Do not insert vibrators into lower layers of concrete that have begun to lose plasticity. At each insertion, limit duration of vibration to time necessary to consolidate concrete and complete embedment of reinforcement and other embedded items without causing mixture constituents to segregate.
- E. Deposit and consolidate concrete for floors and slabs in a continuous operation, within limits of construction joints, until placement of a panel or section is complete.
 - 1. Consolidate concrete during placement operations so concrete is thoroughly worked around reinforcement and other embedded items and into corners.
 - 2. Maintain reinforcement in position on chairs during concrete placement.
 - 3. Screed slab surfaces with a straightedge and strike off to correct elevations.
 - 4. Slope surfaces uniformly to drains where required.
 - 5. Begin initial floating using bull floats or darbies to form a uniform and open-textured surface plane, before excess bleedwater appears on the surface. Do not further disturb slab surfaces before starting finishing operations.
- F. Cold-Weather Placement: Comply with ACI 306.1 and as follows. Protect concrete work from physical damage or reduced strength that could be caused by frost, freezing actions, or low temperatures.
 - 1. When average high and low temperature is expected to fall below 40 degrees Fahrenheit (4.44 degrees Celsius) for three successive days, maintain delivered concrete mixture temperature within the temperature range required by ACI 301.
 - 2. Do not use frozen materials or materials containing ice or snow. Do not place concrete on frozen subgrade or on subgrade containing frozen materials.
 - 3. Do not use calcium chloride, salt, or other materials containing antifreeze agents or chemical accelerators unless otherwise specified and approved in mixture designs.
- G. Hot-Weather Placement: Comply with ACI 301 and as follows:
 - 1. Maintain concrete temperature below 90 degrees Fahrenheit (32.22 degrees Celsius) at time of placement. Chilled mixing water or chopped ice may be used to control temperature, provided water equivalent of ice is calculated to total amount of mixing water.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

Using liquid nitrogen to cool concrete is Contractor's option.

2. Fog-spray forms, steel reinforcement, and subgrade just before placing concrete. Keep subgrade uniformly moist without standing water, soft spots, or dry areas.

4.05 FINISHING FORMED SURFACES

- A. Rough-Formed Finish: As-cast concrete texture imparted by form-facing material with tie holes and defects repaired and patched. Remove fins and other projections that exceed specified limits on formed-surface irregularities.
 - 1. Apply to concrete surfaces not exposed to public view.
- B. Smooth-Formed Finish: As-cast concrete texture imparted by form-facing material, arranged in an orderly and symmetrical manner with a minimum of seams. Repair and patch tie holes and defects. Remove fins and other projections that exceed specified limits on formed-surface irregularities.
 - 1. Apply to concrete surfaces exposed to public view, to receive a rubbed finish, or to be covered with a coating or covering material applied directly to concrete.
- C. Rubbed Finish: Apply the following to smooth-formed finished as-cast concrete where indicated:
 - 1. Smooth-Rubbed Finish: Not later than one day after form removal, moisten concrete surfaces and rub with carborundum brick or another abrasive until producing a uniform color and texture. Do not apply cement grout other than that created by the rubbing process.
 - 2. Grout-Cleaned Finish: Wet concrete surfaces and apply grout of a consistency of thick paint to coat surfaces and fill small holes. Mix one part portland cement to one and one-half parts fine sand with a 1:1 mixture of bonding admixture and water. Add white portland cement in amounts determined by trial patches so color of dry grout will match adjacent surfaces. Scrub grout into voids and remove excess grout. When grout whitens, rub surface with clean burlap and keep surface damp by fog spray for at least 36 hours.
 - 3. Cork-Floated Finish: Wet concrete surfaces and apply a stiff grout. Mix one part portland cement and one part fine sand with a 1:1 mixture of bonding agent and water. Add white portland cement in amounts determined by trial patches so color of dry grout will match adjacent surfaces. Compress grout into voids by grinding surface. In a swirling motion, finish surface with a cork float.
- D. Related Unformed Surfaces: At tops of walls, horizontal offsets, and similar unformed surfaces adjacent to formed surfaces, strike off smooth and finish with a texture matching adjacent formed surfaces. Continue final surface treatment of formed surfaces uniformly across adjacent unformed surfaces unless otherwise indicated.

4.06 FINISHING FLOORS AND SLABS

- A. General: Comply with ACI 302.1R recommendations for screeding, restraightening, and finishing operations for concrete surfaces. Do not wet concrete surfaces.
- B. Scratch Finish: While still plastic, texture concrete surface that has been screeded and bullfloated or darbied. Use stiff brushes, brooms, or rakes to produce a profile
 - 1. Apply scratch finish to surfaces to receive concrete floor toppings or mortar setting beds for bonded cementitious floor finishes.
- C. Float Finish: Consolidate surface with power-driven floats or by hand floating if area is small or inaccessible to power driven floats. Restraighten, cut down high spots, and fill low spots. Repeat float passes and restraightening until surface is left with a uniform, smooth, granular texture.
 - 1. Apply float finish to surfaces to receive trowel finish or to be covered with fluid-applied or sheet waterproofing, built-up or membrane roofing, or sand-bed terrazzo.
- D. Trowel Finish: After applying float finish, apply first troweling and consolidate concrete by hand or power-driven trowel. Continue troweling passes and restraighten until surface is free of

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

trowel marks and uniform in texture and appearance. Grind smooth any surface defects that would telegraph through applied coatings or floor coverings.

- 1. Apply a trowel finish to surfaces exposed to view, to be covered with resilient flooring, carpet, ceramic or quarry tile set over a cleavage membrane, paint, or another thin-film-finish coating system.
- 2. Unless indicated otherwise, finish and measure surface so gap at any point between concrete surface and an unleveled, freestanding, 10-ft long straightedge resting on two high spots and placed anywhere on the surface does not exceed 1/4 inch (6.35 mm).
- 3. Where indicated finish surfaces to specified flatness and levelness standards according to ASTM E1155.
- E. Broom Finish: Where indicated apply a broom finish to exterior concrete platforms, steps, ramps, and elsewhere as indicated.

4.07 CONCRETE PROTECTING AND CURING

- A. General: Protect freshly placed concrete from premature drying and excessive cold or hot temperatures. Comply with ACI 306.1 for cold-weather protection and ACI 301 for hot-weather protection during curing.
- B. Evaporation Retarder: Apply evaporation retarder to unformed concrete surfaces if hot, dry, or windy conditions cause moisture loss approaching 0.2 lb/sq. ft. x h before and during finishing operations. Apply according to manufacturer's written instructions after placing, screeding, and bull floating or darbying concrete, but before float finishing.
- C. Formed Surfaces: Cure formed concrete surfaces, including underside of beams, supported slabs, and other similar surfaces. If forms remain during curing period, moist cure after loosening forms. If removing forms before end of curing period, continue curing for the remainder of the curing period.
- D. Unformed Surfaces: Begin curing immediately after finishing concrete. Cure unformed surfaces, including floors and slabs, concrete floor toppings, and other surfaces.
- E. Cure concrete according to ACI 308.1, by one or a combination of the following methods:
 - 1. Moisture Curing: Keep surfaces continuously moist for not less than seven days with the following materials:
 - a. Water.
 - b. Continuous water-fog spray.
 - c. Absorptive cover, water saturated, and kept continuously wet. Cover concrete surfaces and edges with 12 inch (304.8 mm) lap over adjacent absorptive covers.
 - 2. Moisture-Retaining-Cover Curing: Cover concrete surfaces with moisture-retaining cover for curing concrete, placed in widest practicable width, with sides and ends lapped at least 12 inches (304.8 mm) and sealed by waterproof tape or adhesive. Cure for not less than seven days. Immediately repair any holes or tears during curing period using cover material and waterproof tape.
 - a. Moisture cure or use moisture-retaining covers to cure concrete surfaces to receive floor coverings.
 - b. Moisture cure or use moisture-retaining covers to cure concrete surfaces to receive penetrating liquid floor treatments.
 - c. Cure concrete surfaces to receive floor coverings with either a moisture-retaining cover or a curing compound that the manufacturer certifies will not interfere with bonding of floor covering used on Project.
 - 3. Curing Compound: Apply uniformly in continuous operation by power spray or roller according to manufacturer's written instructions. Recoat areas subjected to heavy rainfall within three hours after initial application. Maintain continuity of coating and repair damage during curing period.
 - a. Removal: After curing period has elapsed, remove curing compound without damaging concrete surfaces by method recommended by curing compound

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

manufacturer

4. Curing and Sealing Compound: Apply uniformly to floors and slabs indicated in a continuous operation by power spray or roller according to manufacturer's written instructions. Recoat areas subjected to heavy rainfall within three hours after initial application. Repeat process 24 hours later and apply a second coat. Maintain continuity of coating and repair damage during curing period.

4.08 LIQUID FLOOR TREATMENTS

- A. Penetrating Liquid Floor Treatment: Where indicated, prepare, apply, and finish penetrating liquid floor treatment according to manufacturer's written instructions.
- B. Polished Concrete Floor Treatment: Apply polished concrete finish system to cured and prepared slabs to match accepted mockup.
 - 1. Machine grind floor surfaces to receive polished finishes level and smooth.
 - 2. Apply penetrating liquid floor treatment for polished concrete in polishing sequence and according to manufacturer's written instructions, allowing recommended drying time between successive coats.
 - 3. Continue polishing with progressively finer grit diamond polishing pads to gloss level to match approved mockup.
 - 4. Control and dispose of waste products produced by grinding and polishing operations.
 - 5. Neutralize and clean polished floor surfaces.
- C. Sealing Coat: Uniformly apply a continuous sealing coat of curing and sealing compound to hardened concrete by power spray or roller according to manufacturer's written instructions.

4.09 JOINT FILLING

- A. Prepare, clean, and install joint filler according to manufacturer's written instructions.
 - 1. Defer joint filling until concrete has aged at least one month. Do not fill joints until construction traffic has permanently ceased.
- B. Remove dirt, debris, saw cuttings, curing compounds, and sealers from joints; leave contact faces of joint clean and dry.
- C. Install semirigid joint filler full depth in saw-cut joints and at least 2 inches (50.8 mm) deep in formed joints. Overfill joint and trim joint filler flush with top of joint after hardening.

4.10 CONCRETE SURFACE REPAIRS

- A. Defective Concrete: Repair and patch defective areas when approved by Architect. Remove and replace concrete that cannot be repaired and patched to Architect's approval.
- B. Patching Mortar: Mix dry-pack patching mortar, consisting of one part portland cement to two and one-half parts fine aggregate passing a No. 16 sieve, using only enough water for handling and placing.
- C. Repairing Formed Surfaces: Surface defects include color and texture irregularities, cracks, spalls, air bubbles, honeycombs, rock pockets, fins and other projections on the surface, and stains and other discolorations that cannot be removed by cleaning.
 - Immediately after form removal, cut out honeycombs, rock pockets, and voids more than 1/2 inch (12.7 mm) in any dimension to solid concrete. Limit cut depth to 3/4 inch (19.05 mm). Make edges of cuts perpendicular to concrete surface. Clean, dampen with water, and brush-coat holes and voids with bonding agent. Fill and compact with patching mortar before bonding agent has dried. Fill form-tie voids with patching mortar or cone plugs secured in place with bonding agent.
 - 2. Repair defects on surfaces exposed to view by blending white portland cement and standard portland cement so that, when dry, patching mortar will match surrounding color. Patch a test area at inconspicuous locations to verify mixture and color match before proceeding with patching. Compact mortar in place and strike off slightly higher than surrounding surface.

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- 3. Repair defects on concealed formed surfaces that affect concrete's durability and structural performance as determined by Architect.
- D. Repairing Unformed Surfaces: Test unformed surfaces, such as floors and slabs, for finish and verify surface tolerances specified for each surface. Correct low and high areas. Test surfaces sloped to drain for trueness of slope and smoothness; use a sloped template.
 - 1. Repair finished surfaces containing defects. Surface defects include spalls, popouts, honeycombs, rock pockets, crazing and cracks in excess of 0.01 inch (0.25 mm) wide or that penetrate to reinforcement or completely through unreinforced sections regardless of width, and other objectionable conditions.
 - 2. After concrete has cured at least 14 days, correct high areas by grinding.
 - 3. Correct localized low areas during or immediately after completing surface finishing operations by cutting out low areas and replacing with patching mortar. Finish repaired areas to blend into adjacent concrete.
 - 4. Correct other low areas scheduled to receive floor coverings with a repair underlayment. Prepare, mix, and apply repair underlayment and primer according to manufacturer's written instructions to produce a smooth, uniform, plane, and level surface. Feather edges to match adjacent floor elevations.
 - 5. Correct other low areas scheduled to remain exposed with a repair topping. Cut out low areas to ensure a minimum repair topping depth of 1/4 inch (6.35 mm) to match adjacent floor elevations. Prepare, mix, and apply repair topping and primer according to manufacturer's written instructions to produce a smooth, uniform, plane, and level surface.
 - 6. Repair defective areas, except random cracks and single holes 1 inch (25.4 mm) or less in diameter, by cutting out and replacing with fresh concrete. Remove defective areas with clean, square cuts and expose steel reinforcement with at least a 3/4-inch clearance all around. Dampen concrete surfaces in contact with patching concrete and apply bonding agent. Mix patching concrete of same materials and mixture as original concrete except without coarse aggregate. Place, compact, and finish to blend with adjacent finished concrete. Cure in same manner as adjacent concrete.
 - 7. Repair random cracks and single holes 1 inch (25.4 mm) or less in diameter with patching mortar. Groove top of cracks and cut out holes to sound concrete and clean off dust, dirt, and loose particles. Dampen cleaned concrete surfaces and apply bonding agent. Place patching mortar before bonding agent has dried. Compact patching mortar and finish to match adjacent concrete. Keep patched area continuously moist for at least 72 hours.
- E. Perform structural repairs of concrete, subject to Architect's approval, using epoxy adhesive and patching mortar.
- F. Repair materials and installation not specified above may be used, subject to Architect's approval.

4.11 FIELD QUALITY CONTROL

- A. Testing and Inspecting: Owner will engage a qualified testing and inspecting agency to perform field tests and inspections and prepare test reports.
- B. Inspections:
 - 1. Steel reinforcement placement.
 - 2. Steel reinforcement welding.
 - 3. Headed bolts and studs.
 - 4. Verification of use of required design mixture.
 - 5. Concrete placement, including conveying and depositing.
 - 6. Curing procedures and maintenance of curing temperature.
 - 7. Verification of concrete strength before removal of shores and forms from beams and slabs.
- C. Concrete Tests: Testing of composite samples of fresh concrete obtained according to ASTM C 172 shall be performed according to the following requirements:

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 1. Testing Frequency: Obtain one composite sample for each day's pour of each concrete mixture exceeding 5 cu. yd. but less than 25 cu. yd., plus one set for each additional 50 cu. yd. or fraction thereof.
- 2. Testing Frequency: Obtain at least one composite sample for each 100 cu. yd. (76 cu. m) or fraction thereof of each concrete mixture placed each day.
 - a. When frequency of testing will provide fewer than five compressive-strength tests for each concrete mixture, testing shall be conducted from at least five randomly selected batches or from each batch if fewer than five are used.
- 3. Slump: ASTM C143/C143M; one test at point of placement for each composite sample, but not less than one test for each day's pour of each concrete mixture. Perform additional tests when concrete consistency appears to change.
- 4. Air Content: ASTM C 231, pressure method, for normal-weight concrete; ASTM C 173 one test for each composite sample, but not less than one test for each day's pour of each concrete mixture.
- 5. Concrete Temperature: ASTM C 1064/C 1064M; one test hourly when air temperature is 40 degrees Fahrenheit (4.44 degrees Celsius) and below and when 80 degrees Fahrenheit (26.67 degrees Celsius) and above, and one test for each composite sample.
- 6. Unit Weight: ASTM C 567, fresh unit weight of structural lightweight concrete; one test for each composite sample, but not less than one test for each day's pour of each concrete mixture.
- 7. Compression Test Specimens: ASTM C31/C31M.
 - a. Cast and laboratory cure two sets of two standard cylinder specimens for each composite sample.
 - b. Cast and field cure two sets of two standard cylinder specimens for each composite sample.
- 8. Compressive-Strength Tests: ASTM C39/C39M; test one set of two laboratory-cured specimens at 7 days and one set of two specimens at 28 days.
 - a. one set of two specimens at 28 days.
 - b. A compressive-strength test shall be the average compressive strength from a set of two specimens obtained from same composite sample and tested at age indicated.
- 9. When strength of field-cured cylinders is less than 85 percent of companion laboratorycured cylinders, Contractor shall evaluate operations and provide corrective procedures for protecting and curing in-place concrete.
- 10. Strength of each concrete mixture will be satisfactory if every average of any three consecutive compressive-strength tests equals or exceeds specified compressive strength and no compressive-strength test value falls below specified compressive strength by more than 500 psi (3447.38 kPa).
- 11. Test results shall be reported in writing to Architect, concrete manufacturer, and Contractor within 48 hours of testing. Reports of compressive-strength tests shall contain Project identification name and number, date of concrete placement, name of concrete testing and inspecting agency, location of concrete batch in Work, design compressive strength at 28 days, concrete mixture proportions and materials, compressive breaking strength, and type of break for both 7- and 28-day tests.
- 12. Nondestructive Testing: Impact hammer, sonoscope, or other nondestructive device may be permitted by Architect but will not be used as sole basis for approval or rejection of concrete.
- 13. Additional Tests: Testing and inspecting agency shall make additional tests of concrete when test results indicate that slump, air entrainment, compressive strengths, or other requirements have not been met, as directed by Architect. Testing and inspecting agency may conduct tests to determine adequacy of concrete by cored cylinders complying with ASTM C 42/C 42M or by other methods as directed by Architect.
- 14. Additional testing and inspecting, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- 15. Correct deficiencies in the Work that test reports and inspections indicate do not comply with the Contract Documents.
- D. Measure floor and slab flatness and levelness according to ASTM E1155.

END OF SECTION 033000

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 042000 UNIT MASONRY

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Concrete block.
- B. Clay facing brick.
- C. Mortar and grout.
- D. Reinforcement and anchorage.
- E. Flashings.
- F. Accessories.

1.02 RELATED REQUIREMENTS

- A. Section 032000 Concrete Reinforcing: Reinforcing steel for grouted masonry.
- B. Section 055000 Metal Fabrications: Loose steel lintels.
- C. Section 079200 Joint Sealants: Sealing control and expansion joints.

1.03 REFERENCE STANDARDS

- A. ASTM A153/A153M Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware; 2023.
- B. ASTM A240/A240M Standard Specification for Chromium and Chromium-Nickel Stainless Steel Plate, Sheet, and Strip for Pressure Vessels and for General Applications; 2024b.
- C. ASTM A641/A641M Standard Specification for Zinc-Coated (Galvanized) Carbon Steel Wire; 2019.
- D. ASTM A666 Standard Specification for Annealed or Cold-Worked Austenitic Stainless Steel Sheet, Strip, Plate, and Flat Bar; 2023.
- E. ASTM A951/A951M Standard Specification for Steel Wire for Masonry Joint Reinforcement; 2022.
- F. ASTM A1064/A1064M Standard Specification for Carbon-Steel Wire and Welded Wire Reinforcement, Plain and Deformed, for Concrete; 2022.
- G. ASTM C67/C67M Standard Test Methods for Sampling and Testing Brick and Structural Clay Tile; 2023.
- H. ASTM C90 Standard Specification for Loadbearing Concrete Masonry Units; 2023.
- I. ASTM C91/C91M Standard Specification for Masonry Cement; 2023.
- J. ASTM C129 Standard Specification for Nonloadbearing Concrete Masonry Units; 2023.
- K. ASTM C140/C140M Standard Test Methods for Sampling and Testing Concrete Masonry Units and Related Units; 2023a.
- L. ASTM C144 Standard Specification for Aggregate for Masonry Mortar; 2018.
- M. ASTM C150/C150M Standard Specification for Portland Cement; 2022.
- N. ASTM C207 Standard Specification for Hydrated Lime for Masonry Purposes; 2018.
- O. ASTM C216 Standard Specification for Facing Brick (Solid Masonry Units Made from Clay or Shale); 2023.
- P. ASTM C270 Standard Specification for Mortar for Unit Masonry; 2019a, with Editorial Revision.
- Q. ASTM C404 Standard Specification for Aggregates for Masonry Grout; 2024.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- R. ASTM C476 Standard Specification for Grout for Masonry; 2023.
- S. ASTM C780 Standard Test Methods for Preconstruction and Construction Evaluation of Mortars for Plain and Reinforced Unit Masonry; 2023.
- T. ASTM C1714/C1714M Standard Specification for Preblended Dry Mortar Mix for Unit Masonry; 2019a.
- U. BIA Technical Notes No. 7 Water Penetration Resistance Design and Detailing; 2017.
- V. BIA Technical Notes No. 13 Ceramic Glazed Brick Exterior Walls; 2017.
- W. BIA Technical Notes No. 28B Brick Veneer/Steel Stud Walls; 2005.
- X. BIA Technical Notes No. 46 Maintenance of Brick Masonry; 2017.
- Y. TMS 402/602 Building Code Requirements and Specification for Masonry Structures; 2022, with Errata (2024).

1.04 ADMINISTRATIVE REQUIREMENTS

A. Preinstallation Meeting: Convene a preinstallation meeting one week before starting work of this section; require attendance by all relevant installers.

1.05 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Product Data: Provide data for masonry units, fabricated wire reinforcement, mortar, and masonry accessories.
- C. Shop Drawings: Indicate pertinent dimensions, materials, anchorage, size and type of fasteners, and accessories for brickwork support system.
 - 1. Include calculations or selections from the manufacturer's prescriptive design tables that indicate compliance with the applicable building code and project conditions.
 - 2. Include the design engineer's stamp or seal on each sheet of shop drawings.
- D. Samples: Submit four samples of facing brick units to illustrate color, texture, and extremes of color range.

1.06 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the type of products specified in this section with minimum three years of documented experience.
- B. Installer Qualifications: Company specializing in performing work of the type specified and with at least three years of documented experience.

1.07 MOCK-UPS

- A. Construct a masonry wall as a mock-up panel sized 8 feet (2.4 m) long by 6 feet (1.8 m) high; include mortar, accessories, structural backup, and flashings (with lap joint, corner, and end dam) in mock-up.
- B. Locate where directed.
- C. Mock-up may remain as part of work.

1.08 DELIVERY, STORAGE, AND HANDLING

A. Deliver, handle, and store masonry units by means that will prevent mechanical damage and contamination by other materials.

PART 2 PRODUCTS

2.01 CONCRETE MASONRY UNITS (ALSO REF. STR. DWGS.)

- A. Concrete Block: Comply with referenced standards and as follows:
 - 1. Size: Standard units with nominal face dimensions of 16 by 8 inches (400 by 200 mm) and nominal depth of 8 inches (200 mm).

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

2. Special Shapes: Provide nonstandard blocks configured for lintels, headers, and control joint edges.

a. Provide bullnose units for outside corners.

- 3. Load-Bearing Units: ASTM C90, normal weight.
 - a. Hollow block.
 - b. Exposed Faces: Manufacturer's standard color and texture.
- 4. Nonloadbearing Units: ASTM C129.
 - a. Hollow block, as indicated.
 - b. Normal weight.

2.02 BRICK UNITS

- A. Manufacturers:
 - 1. Belden Brick: www.beldenbrick.com/#sle.
 - 2. Endicott Clay Products Co; Face Brick FBX: www.endicott.com/#sle.
 - 3. General Shale Brick: www.generalshale.com/#sle.
 - 4. Meridian Brick LLC; Athens Architectural Series: www.meridianbrick.com/#sle.
 - 5. McAvoy Brick.
 - 6. Substitutions: See section 016000 Product Requirements.
- B. Facing Brick: ASTM C216, Type FBS Smooth, Grade SW.
 - 1. Color and texture:
 - 2. Nominal size: 3.5 x 2.25 x 7.625 inches
 - 3. Special shapes: Molded units as required by conditions indicated, unless standard units can be sawn to produce equivalent effect.

2.03 MORTAR AND GROUT MATERIALS

- A. Masonry Cement: ASTM C91/C91M, N or S above grade. Use Type S or M below grade. (These are the recommendations of the Architect but The Mason Contractor shall be permitted to select the cement type for use in the mortar.)
 - 1. Colored Mortar: Premixed cement as required to match Architect's color sample.
- B. Portland Cement: ASTM C150/C150M, Type I; color as required to produce approved color sample.
 - 1. Not more than 0.60 percent alkali.
- C. Hydrated Lime: ASTM C207, Type S.
- D. Mortar Aggregate: ASTM C144.
- E. Grout Aggregate: ASTM C404.
- F. Water: Clean and potable.
- G. Packaged Dry Material for Mortar for Unit Masonry: Premixed masonry cement and mason's sand; complying with ASTM C1714/C1714M and capable of producing mortar of the specified strength in accordance with ASTM C270 with the addition of water only.
 - 1. Type: Type N.
 - 2. Color: Standard gray.
- H. Packaged Dry Material for Grout for Masonry: Premixed cementitious materials and dried aggregates; capable of producing grout of the specified strength in accordance with ASTM C476 with the addition of water only.
 - 1. Type: Coarse.

2.04 REINFORCEMENT AND ANCHORAGE

- A. Manufacturers:
 - 1. Blok-Lok Limited: www.blok-lok.com/#sle.
 - 2. FERO Corporation: www.ferocorp.com/#sle.
 - 3. Hohmann & Barnard, Inc; X-Seal Anchor: www.h-b.com/#sle.

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 4. TruFast Walls, a division of Altenloh, Brinck & Co. US, Inc; Thermal-Grip MVA: www.trufastwalls.com/#sle.
- 5. WIRE-BOND: www.wirebond.com/#sle.
- 6. Substitutions: See Section 016000 Product Requirements.
- B. Reinforcing Steel: Type specified in Structural Drawings; size as indicated on drawings; galvanized finish.
- C. Single Wythe Joint Reinforcement: ASTM A951/A951M.
- D. Multiple Wythe Joint Reinforcement: ASTM A951/A951M.
 - 1. Type: Truss.
 - Material: ASTM A1064/A1064M steel wire, mill galvanized to ASTM A641/A641M Class
 3.
 - 3. Size: 0.1875 inch (4.8 mm) side rods with 0.1483 inch (3.8 mm) cross rods; width as required to provide not less than 5/8 inch (16 mm) of mortar coverage on each exposure.
- E. Adjustable Multiple Wythe Joint Reinforcement: ASTM A951/A951M.
 - 1. Type: Truss or ladder, with adjustable ties or tabs spaced at 16 in (406 mm) on center.
 - 2. Material: ASTM A1064/A1064M steel wire, hot dip galvanized after fabrication to ASTM A153/A153M Class B.
 - 3. Size: 0.1875 inch (4.8 mm) side rods with 0.1483 inch (3.8 mm) cross rods and adjustable components of 0.1875 inch (4.8 mm)wire, width of components as required to provide not less than 5/8 inch (16 mm) of mortar coverage from each masonry face.
 - 4. Insulation Clips: Provide clips at tabs or ties designed to secure insulation against outer face of inner wythe of masonry.
- F. Strap Anchors: Bent steel shapes, 1-1/2 inch (38 mm) width, 0.105 inch (2.7 mm) thick, 24 inch (610 mm) length, with 1-1/2 inch (38 mm) long, 90 degree bend at each end to form a U or Z shape or with cross pins, hot dip galvanized to ASTM A153/A153M Class B.
- G. Flexible Anchors: 2-piece anchors that permit differential movement between masonry and building frame, sized to provide not less than 5/8 inch (16 mm) of mortar coverage from masonry face.
 - 1. Steel frame: Crimped wire anchors for welding to frame, 0.25 inch (6.3 mm) thick, with trapezoidal wire ties 0.1875 inch (4.75 mm) thick, hot dip galvanized to ASTM A 153/A 153M, Class B.
- H. Two-Piece Wall Ties: Formed steel wire, 0.1875 inch (4.8 mm) thick, adjustable, eye and pintle type, hot dip galvanized to ASTM A 153/A 153M, Class B, sized to provide not less than 5/8 inch (16 mm) of mortar coverage from masonry face and to allow vertical adjustment of up to 1-1/4 in (32 mm).
- I. Masonry Veneer Anchors: 2-piece anchors that permit differential movement between masonry veneer and structural backup, hot dip galvanized to ASTM A 153/A 153M, Class B.
 - 1. Anchor plates: Not less than 0.075 inch (1.91 mm) thick, designed for fastening to structural backup through sheathing by two fasteners; provide design with legs that penetrate sheathing and insulation to provide positive anchorage.
 - 2. Wire ties: Manufacturer's standard shape, 0.1875 inch (4.75 mm) thick.
 - 3. Vertical adjustment: Not less than 3-1/2 inches (89 mm).
- J. Metal-to-Metal Fasteners: Self-drilling, self-tapping screws; corrosion resistant finish or hot dip galvanized to ASTM A153/A153M.
 - 1. Manufacturers:
 - a. ITW Commercial Construction North America; Teks Select Series: www.ITWBuildex.com/#sle.
 - b. Substitutions: See Section 016000 Product Requirements.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

2.05 FLASHINGS

- A. Metal Flashing Materials:
 - 1. Stainless Steel Flashing: ASTM A666, Type 304, soft temper; 26 gauge, 0.0187 inch (0.48 mm) thick; finish 2B to 2D.
 - 2. Prefabricated Metal Flashing: Smooth fabricated 12 oz/sq ft (3.66 kg/sq m) stainless steel (type 304) flashing for surface mounted conditions.
 - a. Manufacturers:
 - 1) Cheney Flashing Company: www.cheneyflashing.com/#sle.
 - 2) Hohmann & Barnard, Inc: www.h-b.com/#sle.
 - 3) York Flashings;
 - 4) Substitutions: See Section 016000 Product Requirements.
- B. Combination Non-Asphaltic Flashing Materials Stainless Steel:
 - Stainless Steel Flashing Self-adhering: ASTM A240/A240M; 2 mil (0.05 mm) type 304 stainless steel sheet with 8 mil (0.20 mm) of butyl adhesive and a removable release liner.
 Manufacturers:
 - 1) STS Coatings, Inc: www.stscoatings.com/#sle.
 - 2) VaproShield, LLC: www.vaproshield.com/#sle.
 - 3) WIRE-BOND: www.wirebond.com/#sle.
 - 4) York Manufacturing, Inc; York 304: www.yorkmfg.com/#sle.
 - 5) Substitutions: See Section 016000 Product Requirements.
 - 2. Stainless Steel/Polymer Fabric Flashing: ASTM A240/A240M; 2 mil (0.05 mm) type 304 stainless steel sheet bonded on one side to one sheet of polymer fabric.
 - a. Manufacturers:
 - 1) Hohmann & Barnard, Inc; Mighty-Flash Stainless Flashing: www.h-b.com/#sle.
 - 2) WIRE-BOND: www.wirebond.com/#sle.
 - 3) York Manufacturing, Inc; Multi-Flash SS: www.yorkmfg.com/#sle.
 - 3. Stainless Steel/Polymer Fabric Flashing Self-adhering: ASTM A240/A240M; 2 mil (0.05 mm) type 304 stainless steel sheet bonded on inward facing side to a sheet of polymer fabric that has a clear adhesive with a removable release liner.
 - a. Manufacturers:
 - 1) Hohmann & Barnard, Inc: www.h-b.com/#sle.
 - 2) York Flashings.
 - 4. Stainless Steel/Polymer Fabric Drainage Plane Flashing: ASTM A240/A240M; 2 mil (0.05 mm) type 304 stainless steel sheet bonded between one sheet of polymer fabric and one sheet of non-woven drainage material.
 - a. Manufacturers:
 - 1) STS Coatings, Inc: www.stscoatings.com/#sle.
 - 2) York Manufacturing, Inc; Flash-Vent SS:
 - 3) Substitutions: See Section 016000 Product Requirements.
 - 5. Stainless Steel/Polymer Fabric Drainage Plane Flashing Self-Adhering: ASTM A240/A240M; 2 mil (0.05 mm) type 304 stainless steel sheet with co-polymer butyl adhesive and a removable release liner on one side and a sheet of nonwoven drainage material bonded to the other side.
 - a. Manufacturers:
 - 1) York Manufacturing, Inc; Flash-Vent SA:
 - 2) Substitutions: See Section 016000 Product Requirements.
- C. Factory-Fabricated Flashing Corners and End Dams: Stainless steel.
 - 1. Manufacturers:
 - a. Hohmann & Barnard, Inc: www.h-b.com/#sle.
 - b. Mortar Net Solutions; CompleteFlash: www.mortarnet.com/#sle.
 - c. York Manufacturing, Inc: www.yorkmfg.com/#sle.

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- d. Substitutions: See Section 016000 Product Requirements.
- D. Flashing Sealant/Adhesives: Silicone, polyurethane, or silyl-terminated polyether/polyurethane or other type required or recommended by flashing manufacturer; type capable of adhering to type of flashing used.
 - 1. Manufacturers, Synthetic Rubber Products:
 - a. Mortar Net Solutions; BTL-1 Butyl Sealant: www.mortarnet.com/#sle.
 - b. Substitutions: See Section 016000 Product Requirements.
 - 2. Manufacturers, Modified Polyether Products:
 - a. Mortar Net Solutions: www.mortarnet.com/#sle.
 - b. York Manufacturing, Inc; UniverSeal US-100 Liquid Tape: www.yorkmfg.com/#sle.
 - c. Substitutions: See Section 016000 Product Requirements.
- E. Termination Bars: Stainless steel; compatible with membrane and adhesives.
 - 1. Manufacturers:
 - a. Hohmann & Barnard, Inc: www.h-b.com/#sle.
 - b. Mortar Net Solutions; Termination Bars: www.mortarnet.com/#sle.
 - c. York Manufacturing, Inc; Termination Bar: www.yorkmfg.com/#sle.
- F. Drip Edge: Stainless steel; angled drip with hemmed edge; compatible with membrane and adhesives.
 - 1. Manufacturers:
 - a. Hohmann & Barnard, Inc: www.h-b.com/#sle.
 - b. Mortar Net Solutions; Metal Drip Edges: www.mortarnet.com/#sle.
 - c. York Manufacturing, Inc: www.yorkmfg.com/#sle.
- G. Lap Sealants and Tapes: As recommended by flashing manufacturer; compatible with membrane and adhesives.

2.06 ACCESSORIES

- A. Preformed Control Joints: Neoprene material. Provide with corner and tee accessories, fused joints.
 - 1. Manufacturers:
 - a. Blok-Lok Limited: www.blok-lok.com/#sle.
 - b. Hohmann & Barnard, Inc: www.h-b.com/#sle.
 - c. WIRE-BOND: www.wirebond.com/#sle.
 - d. Substitutions: See Section 016000 Product Requirements.
- B. Joint Filler: Closed cell polyethylene; oversized 50 percent to joint width; self expanding; in maximum lengths available.
 - 1. Manufacturers:
 - a. Hohmann & Barnard, Inc: www.h-b.com/#sle.
 - b. WIRE-BOND: www.wirebond.com/#sle.
 - c. Nomaco.
- C. Cavity Mortar Control: Semi-rigid polyethylene or polyester mesh panels, sized to thickness of wall cavity, and designed to prevent mortar droppings from clogging weeps and cavity vents and allow proper cavity drainage.
 - 1. Full-Height Airspace Maintenance and Drainage Material: Mesh panels fitted between masonry ties.
 - a. Drainage Material Thickness: 3/8 inch (9.5 mm).
 - b. Manufacturers:
 - 1) Advanced Building Products, Inc; Mortairvent-CW: www.advancedbuildingproducts.com/#sle.
 - CavClear, a Division of Archovations Inc; CavClear Masonry Mat: www.cavclear.com/#sle.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- D. Weeps:
 - 1. Type: Polyester mesh.
 - 2. Color(s): As selected by Architect from manufacturer's full range.
 - 3. Manufacturers:
 - a. Advanced Building Products, Inc: www.advancedbuildingproducts.com/#sle.
 - b. Blok-Lok Limited: www.blok-lok.com/#sle.
 - c. CavClear, a Division of Archovations Inc: www.cavclear.com/#sle.
 - d. Masonry Technology, Inc; Cavity Weep: www.mtidry.com/#sle.
 - e. Mortar Net Solutions; WeepVent: www.mortarnet.com/#sle.
- E. Cavity Vents:
 - 1. Type: Preformed aluminum vents with sloping louvers.
 - 2. Color(s): As selected by Architect from manufacturer's full range.
 - 3. Manufacturers:
 - a. Advanced Building Products, Inc: www.advancedbuildingproducts.com/#sle.
 - b. Blok-Lok Limited: www.blok-lok.com/#sle.
 - c. CavClear, a Division of Archovations Inc: www.cavclear.com/#sle.
 - d. Hohmann & Barnard, Inc: www.h-b.com/#sle.
 - e. Mortar Net Solutions; CellVent: www.mortarnet.com/#sle.
 - f. WIRE-BOND: www.wirebond.com/#sle.
- F. Cleaning Solution: Non-acidic, not harmful to masonry work or adjacent materials.

2.07 MORTAR AND GROUT MIXING

- A. Mortar for Unit Masonry: ASTM C270, using the Proportion Specification.
 - 1. Masonry below grade and in contact with earth: Type S.
- B. Colored Mortar: Proportion selected pigments and other ingredients to match Architect's sample, without exceeding manufacturer's recommended pigment-to-cement ratio.
- C. Grout: ASTM C476; consistency required to fill completely volumes indicated for grouting; fine grout for spaces with smallest horizontal dimension of 2 inches (50 mm) or less; coarse grout for spaces with smallest horizontal dimension greater than 2 inches (50 mm).
- D. Admixtures: Add to mixture at manufacturer's recommended rate and in accordance with manufacturer's instructions; mix uniformly.
- E. Mixing: Use mechanical batch mixer and comply with referenced standards.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that field conditions are acceptable and are ready to receive masonry.
- B. Verify that related items provided under other sections are properly sized and located.
- C. Verify that built-in items are in proper location, and ready for roughing into masonry work.

3.02 PREPARATION

- A. Direct and coordinate placement of metal anchors supplied for installation under other sections.
- B. Provide temporary bracing during installation of masonry work. Maintain in place until building structure provides permanent bracing.

3.03 COLD AND HOT WEATHER REQUIREMENTS

A. Comply with requirements of TMS 402/602 or applicable building code, whichever is more stringent.

3.04 COURSING

A. Establish lines, levels, and coursing indicated. Protect from displacement.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- B. Maintain masonry courses to uniform dimension. Form vertical and horizontal joints of uniform thickness.
- C. Concrete Masonry Units:
 - 1. Bond: Running.
 - 2. Coursing: One unit and one mortar joint to equal 8 inches (200 mm).
 - 3. Mortar Joints: Concave.
- D. Brick Units:
 - 1. Bond: As indicated for different locations.
 - 2. Coursing: Three units and three mortar joints to equal 8 inches (200 mm).
 - 3. Mortar Joints: Concave.

3.05 PLACING AND BONDING

- A. Lay solid masonry units in full bed of mortar, with full head joints, uniformly jointed with other work.
- B. Lay hollow masonry units with face shell bedding on head and bed joints.
- C. Buttering corners of joints or excessive furrowing of mortar joints is not permitted.
- D. Remove excess mortar and mortar smears as work progresses.
- E. Remove excess mortar with water repellent admixture promptly. Do not use acids, sandblasting or high pressure cleaning methods.
- F. Interlock intersections and external corners, except for units laid in stack bond.
- G. Do not shift or tap masonry units after mortar has achieved initial set. Where adjustment must be made, remove mortar and replace.
- H. Perform job site cutting of masonry units with proper tools to provide straight, clean, unchipped edges. Prevent broken masonry unit corners or edges.
- I. Isolate top joint of masonry partitions from horizontal structural framing members and slabs or decks with compressible joint filler.

3.06 WEEPS/CAVITY VENTS

- A. Install weeps in veneer and cavity walls at 32 inches (800 mm) on center horizontally on top of through-wall flashing above shelf angles and lintels and at bottom of walls.
- B. Install cavity vents in veneer and cavity walls at 32 inches (800 mm) on center horizontally below shelf angles and lintels and near top of walls.

3.07 CAVITY MORTAR CONTROL

- A. Do not permit mortar to drop or accumulate into cavity air space or to plug weep/cavity vents.
- B. For cavity walls, build inner wythe ahead of outer wythe to accommodate accessories.
- C. Install cavity mortar diverter at base of cavity and at other flashing locations as recommended by manufacturer to prevent mortar droppings from blocking weep/cavity vents.

3.08 REINFORCEMENT AND ANCHORAGE - GENERAL, SINGLE WYTHE MASONRY, AND CAVITY WALL MASONRY

- A. Unless otherwise indicated on drawings or specified under specific wall type, install horizontal joint reinforcement 16 inches (400 mm) on center.
- B. Place masonry joint reinforcement in first and second horizontal joints above and below openings. Extend minimum 16 inches (400 mm) each side of opening.
- C. Place continuous joint reinforcement in first and second joint below top of walls.
- D. Embed longitudinal wires of joint reinforcement in mortar joint with at least 5/8 inch (16 mm) mortar cover on each side.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- E. Lap joint reinforcement ends minimum 6 inches (150 mm).
- F. Reinforce stack bonded unit joint corners and intersections with strap anchors 16 inches (400 mm) on center.
- G. Fasten anchors to structural framing and embed in masonry joints as masonry is laid. Unless otherwise indicated on drawings or closer spacing is indicated under specific wall type, space anchors at maximum of 36 inches (900 mm) horizontally and 24 inches (600 mm) vertically.

3.09 REINFORCEMENT AND ANCHORAGE - MASONRY VENEER

- A. Masonry Back-Up: Embed anchors in masonry back-up to bond veneer at maximum 1.77 sq ft (0.16 sq m) of wall surface per anchor. Place additional anchors at perimeter of openings and ends of panels, so maximum spacing of anchors is 8 inches (200 mm) on center.
- B. Stud Back-Up: Secure veneer anchors to stud framed back-up and embed into masonry veneer at maximum 1.77 sq ft (0.16 sq m) of wall surface per anchor. Place additional anchors at perimeter of openings and ends of panels, so maximum spacing of anchors is 8 inches (200 mm) on center.

3.10 REINFORCEMENT AND ANCHORAGES - MULTIPLE WYTHE UNIT MASONRY

A. Use individual metal ties installed in horizontal joints to bond wythes together. Provide ties spaced as indicated on drawings.

3.11 MASONRY FLASHINGS

- A. Whether or not specifically indicated, install masonry flashing to divert water to exterior at all locations where downward flow of water will be interrupted.
 - 1. Extend flashings full width at such interruptions and at least 6 inches (152 mm), minimum, into adjacent masonry or turn up flashing ends at least 1 inch (25.4 mm), minimum, to form watertight pan at nonmasonry construction.
 - 2. Remove or cover protrusions or sharp edges that could puncture flashings.
 - 3. Seal lapped ends and penetrations of flashing before covering with mortar.
- B. Terminate flashing up 8 inches (203 mm) minimum on vertical surface of backing:
 - 1. Install vertical leg of flashing behind water-resistive barrier sheet over backing.
 - 2. Anchor vertical leg of flashing into backing with a termination bar and sealant.
 - 3. Apply cap bead of sealant on top edge of self-adhered flashing.
- C. Install flashing in accordance with BIA Technical Notes No. 7.
- D. Extend metal flashings through exterior face of masonry and terminate in an angled drip with hemmed edge. Install joint sealer below drip edge to prevent moisture migration under flashing.
- E. Support flexible flashings across gaps and openings.
- F. Lap end joints of flashings at least 6 inches (152 mm), minimum, and seal watertight with flashing sealant/adhesive.

3.12 LINTELS

- A. Install loose steel lintels over openings.
- B. Install reinforced unit masonry lintels over openings where steel or precast concrete lintels are not scheduled.

3.13 GROUTED COMPONENTS

- A. Lap splices minimum 24 bar diameters.
- B. Support and secure reinforcing bars from displacement. Maintain position within 1/2 inch (13 mm) of dimensioned position.
- C. Place and consolidate grout fill without displacing reinforcing.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

3.14 CONTROL AND EXPANSION JOINTS

- A. Do not continue horizontal joint reinforcement through control or expansion joints.
- B. Install preformed control joint device in continuous lengths. Seal butt and corner joints in accordance with manufacturer's instructions.
- C. Size control joints as indicated on drawings; if not indicated, 3/4 inch (19 mm) wide and deep.
- D. Form expansion joint as detailed on drawings.

3.15 BUILT-IN WORK

- A. As work progresses, install built-in metal door frames and glazed frames and other items to be built into the work and furnished under other sections.
- B. Bed anchors of metal door and glazed frames in adjacent mortar joints. Fill frame voids solid with grout.
- C. Do not build into masonry construction organic materials that are subject to deterioration.

3.16 TOLERANCES

- A. Install masonry within the site tolerances found in TMS 402/602.
- B. Maximum Variation from Alignment of Columns: 1/4 inch (6 mm).
- C. Maximum Variation From Unit to Adjacent Unit: 1/16 inch (1.6 mm).
- D. Maximum Variation from Plane of Wall: 1/4 inch in 10 ft (6 mm/3 m) and 1/2 inch in 20 ft (13 mm/6 m) or more.
- E. Maximum Variation from Plumb: 1/4 inch (6 mm) per story non-cumulative; 1/2 inch (13 mm) in two stories or more.
- F. Maximum Variation from Level Coursing: 1/8 inch in 3 ft (3 mm/m) and 1/4 inch in 10 ft (6 mm/3 m); 1/2 inch in 30 ft (13 mm/9 m).
- G. Maximum Variation of Mortar Joint Thickness: Head joint, minus 1/4 inch, plus 3/8 inch (minus 6.4 mm, plus 9.5 mm).
- H. Maximum Variation from Cross Sectional Thickness of Walls: 1/4 inch (6 mm).

3.17 CUTTING AND FITTING

3.18 PARGING

- A. Dampen masonry walls prior to parging.
- B. Scarify each parging coat to ensure full bond to subsequent coat.
- C. Parge masonry walls in two uniform coats of mortar to a total thickness of 3/4 inch (19 mm).
- D. Steel trowel surface smooth and flat with a maximum surface variation of 1/8 inch per foot (1 mm/m).
- E. Strike top edge of parging at 45 degrees.

3.19 FIELD QUALITY CONTROL

- A. An independent testing agency will perform field quality control tests, as specified in Section 014000 Quality Requirements.
- B. Clay Masonry Unit Tests: Test each variety of clay masonry in accordance with ASTM C67/C67M requirements, sampling 5 randomly chosen units for each 50,000 installed.
- C. Concrete Masonry Unit Tests: Test each variety of concrete unit masonry in accordance with ASTM C140/C140M for compliance with requirements of this specification.
- D. Mortar Tests: Test each type of mortar in accordance with ASTM C780, testing with same frequency as masonry samples.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

3.20 CLEANING

- A. Remove excess mortar and mortar droppings.
- B. Replace defective mortar. Match adjacent work.
- C. Clean soiled surfaces with cleaning solution.
- D. Use non-metallic tools in cleaning operations.

3.21 PROTECTION

A. Without damaging completed work, provide protective boards at exposed external corners that are subject to damage by construction activities.

END OF SECTION 042000

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 047200 CAST STONE MASONRY

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Architectural cast stone.

1.02 RELATED REQUIREMENTS

- A. Section 042000 Unit Masonry: Installation of cast stone in conjunction with masonry.
- B. Section 079200 Joint Sealants: Sealing joints indicated to be left open for sealant.

1.03 REFERENCE STANDARDS

- ACI CODE-318 Building Code Requirements for Structural Concrete and Commentary; 2019 (Reapproved 2022).
- B. ASTM A615/A615M Standard Specification for Deformed and Plain Carbon-Steel Bars for Concrete Reinforcement; 2022.
- C. ASTM A775/A775M Standard Specification for Epoxy-Coated Steel Reinforcing Bars; 2022.
- D. ASTM A884/A884M Standard Specification for Epoxy-Coated Steel Wire and Welded Wire Reinforcement; 2019, with Editorial Revision (2020).
- E. ASTM C33/C33M Standard Specification for Concrete Aggregates; 2023.
- F. ASTM C150/C150M Standard Specification for Portland Cement; 2022.
- G. ASTM C270 Standard Specification for Mortar for Unit Masonry; 2019a, with Editorial Revision.
- H. ASTM C494/C494M Standard Specification for Chemical Admixtures for Concrete; 2019, with Editorial Revision (2022).
- I. ASTM C642 Standard Test Method for Density, Absorption, and Voids in Hardened Concrete; 2021.
- J. ASTM C1364 Standard Specification for Architectural Cast Stone; 2023.

1.04 SUBMITTALS

- A. See Section 013000 Administrative Requirements, for submittal procedures.
- B. Product Data: Test results of cast stone components made previously by the manufacturer.
- C. Shop Drawings: Include elevations, dimensions, layouts, profiles, cross sections, reinforcement, exposed faces, arrangement of joints, anchoring methods, anchors, and piece numbers.
- D. Verification Samples: Pieces of actual cast stone components not less than 6 inches (152 mm) square, illustrating range of color and texture to be anticipated in components furnished for the project.
- E. Source Quality Control Test Reports.
- F. Manufacturer's Qualification Data: Documentation showing compliance with specified requirements.

1.05 QUALITY ASSURANCE

- A. Manufacturer Qualifications:
 - 1. A firm with a minimum of 10 years experience producing cast stone of types required for project.
 - 2. Adequate plant capacity to furnish quality, sizes, and quantity of cast stone required without delaying progress of the work.

LAHC – WORKFORCE
EDUCATION RESOURCE AND
DEVELOPMENT CENTER

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

B. Installer Qualifications: Company specializing in performing work of the type specified and with at least 5 years of documented experience.

1.06 MOCK-UPS

- A. See Section 014000 Quality Requirements for additional requirements.
- B. Approved mock-up will become standard for appearance and workmanship.
- C. Mock-up may remain as part of the completed work.

1.07 DELIVERY, STORAGE, AND HANDLING

- A. Deliver cast stone components secured to shipping pallets and protected from damage and discoloration. Protect corners from damage.
- B. Number each piece individually to match shop drawings and schedule.
- C. Store cast stone components and installation materials in accordance with manufacturer's instructions.
- D. Store cast stone components on pallets with nonstaining, waterproof covers. Ventilate under covers to prevent condensation. Prevent contact with dirt.
- E. Protect cast stone components during handling and installation to prevent chipping, cracking, or other damage.
- F. Store mortar materials where contamination can be avoided.
- G. Schedule and coordinate production and delivery of cast stone components with unit masonry work to optimize on-site inventory and to avoid delaying the work.

PART 2 PRODUCTS

2.01 ARCHITECTURAL CAST STONE

- A. Cast Stone: Architectural concrete product manufactured to simulate appearance of natural limestone, complying with ASTM C1364.
 - 1. Compressive Strength: As specified in ASTM C1364; calculate strength of pieces to be field cut at 80 percent of uncut piece.
 - 2. Freeze-Thaw Resistance: Demonstrated by laboratory testing in accordance with ASTM C1364.
 - 3. Surface Texture: Fine grained texture, with no bugholes, air voids, or other surface blemishes visible from distance of 20 feet (6 meters).
 - 4. Color: Selected by Architect from manufacturer's full range.
 - 5. Remove cement film from exposed surfaces before packaging for shipment.
- B. Shapes: Provide shapes indicated on drawings.
 - 1. Variation from Any Dimension, Including Bow, Camber, and Twist: Maximum of plus/minus 1/8 inch (3 mm) or length divided by 360, whichever is greater, but not more than 1/4 inch (6 mm).
 - 2. Unless otherwise indicated on drawings, provide:
 - a. Wash or slope of 1:12 on exterior horizontal surfaces.
 - b. Drips on projecting components, wherever possible.
 - c. Raised fillets at back of sills and at ends to be built in.
- C. Reinforcement: Provide reinforcement as required to withstand handling and structural stresses; comply with ACI CODE-318.
 - 1. Pieces More than 24 inches (610 mm) in Any Dimension: Provide full length two-way reinforcement of cross-sectional area not less than 0.25 percent of unit cross-sectional area.

2.02 MATERIALS

A. Portland Cement: ASTM C150/C150M.

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 1. For Mortar: Type I or II, except Type III may be used in cold weather.
- B. Coarse Aggregate: ASTM C33/C33M, except for gradation; granite, quartz, or limestone.
- C. Fine Aggregate: ASTM C33/C33M, except for gradation; natural or manufactured sands.
- D. Admixtures: ASTM C494/C494M.
- E. Water: Potable.
- F. Reinforcing Bars: ASTM A615/A615M, Grade 40 (40,000 psi) (280 MPa), deformed bars, galvanized.
 - 1. Epoxy coated in accordance with ASTM A775/A775M.
- G. Steel Welded Wire Reinforcement: ASTM A884/A884M, epoxy coated.
- H. Embedded Anchors, Dowels, and Inserts: Type 304 stainless steel, of type and size as required for conditions.
- I. Mortar: Portland cement-lime, as specified in Section 040511 ; do not use masonry cement.
- J. Cleaner: General-purpose cleaner designed for removing mortar and grout stains, efflorescence, and other construction stains from new masonry surfaces without discoloring or damaging masonry surfaces; approved for intended use by cast stone manufacturer and by cleaner manufacturer for use on cast stone and adjacent masonry materials.

2.03 SOURCE QUALITY CONTROL

- A. Test compressive strength and absorption of specimens selected at random from plant production.
 - 1. Test in accordance with ASTM C642.
 - 2. Select specimens at rate of 3 per 500 cubic feet (3 per 14 cubic m), with a minimum of 3 per production week.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Examine construction to receive cast stone components. Notify Architect if construction is not acceptable.
- B. Do not begin installation until unacceptable conditions have been corrected.

3.02 INSTALLATION

- A. Install cast stone components in conjunction with masonry, complying with requirements of Section 042000.
- B. Mechanically anchor cast stone units indicated; set remainder in mortar.
- C. Setting:
 - 1. Drench cast stone components with clear, running water immediately before installation.
 - 2. Set units in a full bed of mortar unless otherwise indicated.
 - 3. Fill vertical joints with mortar.
 - 4. Fill dowel holes and anchor slots completely with mortar or non-shrink grout.

3.03 TOLERANCES

- A. Joints: Make all joints 3/8 inch (9.5 mm), except as otherwise detailed.
 - 1. Rake mortar joints 3/4 inch (19 mm) for pointing.
 - 2. Remove excess mortar from face of stone before pointing joints.
 - 3. Point joints with mortar in layers 3/8 inch (9.5 mm) thick and tool to a slight concave profile.
 - 4. Leave the following joints open for sealant:
 - a. Head joints in top courses, including copings, parapets, cornices, sills, and steps.
 - b. Joints in projecting units.
 - c. Joints between rigidly anchored units, including soffits, panels, and column covers.

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- d. Joints below lugged sills and stair treads.
- e. Joints below ledge and relieving angles.
- f. Joints labeled "expansion joint".
- B. Installation Tolerances:
 - 1. Variation from Plumb: Not more than 1/8 inch in 10 feet (3 mm in 3 m) or 1/4 inch in 20 feet (6 mm in 6 m) or more.
 - 2. Variation from Level: Not more than 1/8 inch in 10 feet (3 mm in 3 m) or 1/4 inch in 20 feet (6 mm in 6 m), or 3/8 inch (9 mm) maximum.
 - 3. Variation in Joint Width: Not more than 1/8 inch in 36 inches (3 mm in 900 mm) or 1/4 of nominal joint width, whichever is less.
 - 4. Variation in Plane Between Adjacent Surfaces (Lipping): Not more than 1/16 inch (1.5 mm) difference between planes of adjacent units or adjacent surfaces indicated to be flush with units.

3.04 REPAIR

- A. Repair chips and other surface damage noticeable when viewed in direct daylight at 20 feet (6 m).
- B. Repair with matching touch-up material provided by the manufacturer and in accordance with manufacturer's instructions.
- C. Repair methods and results subject to Architect 's approval.

3.05 CLEANING

A. Keep cast stone components clean as work progresses.

3.06 PROTECTION

- A. Protect completed work from damage.
- B. Clean, repair, or restore damaged or mortar-splashed work to condition of new work.

END OF SECTION 047200

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 051200 STRUCTURAL STEEL FRAMING

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. AISC 303 Code of Standard Practice for Steel Buildings and Bridges; 2022, with Errata (2025).
- B. AISC 360 Specification for Structural Steel Buildings; 2022, with Errata (2025).
- C. ASTM A36/A36M Standard Specification for Carbon Structural Steel; 2019.
- D. ASTM A53/A53M Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless; 2022.
- E. ASTM A108 Standard Specification for Steel Bar, Carbon and Alloy, Cold-Finished; 2018.
- F. ASTM E164 Standard Practice for Contact Ultrasonic Testing of Weldments; 2019.
- G. ASTM E709 Standard Guide for Magnetic Particle Testing; 2021.
- H. ASTM F1554 Standard Specification for Anchor Bolts, Steel, 36, 55, and 105-ksi Yield Strength; 2020.
- I. AWS D1.1/D1.1M Structural Welding Code Steel; 2020, with Errata (2023).
- J. SSPC-PA 1 Shop, Field, and Maintenance Coating of Metals; 2024.
- K. SSPC-Paint 20 Zinc-Rich Coating (Type I Inorganic, and Type II Organic); 2019.

1.02 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.03 SUMMARY

A. Section includes structural steel framing from rolled sections and plates as well as their connections

1.04 ACTION SUBMITTALS

- A. Shop Drawings: Show fabrication of structural-steel components.
 - 1. Include erection drawings as needed to fully describe layout and placement, include details as needed to describe complicated assemblies and connections, and include piece drawings describing each unique fabricated member. Shop drawings are to be fully dimensioned.
 - 2. All drawings are to originate with the contractor or contractor's models. Shop drawing production will not be dependent on use of the architect/engineer's electronic files unless arrangements for use are made prior to award of contract.
 - 3. Submit shop drawings as electronic files (PDF).
- B. Connection Calculations: Provide calculations prepared by a professional engineer licensed in the jurisdiction having authority over the project for all connections indicated on the drawings to require calculations. Provide sealed calculations upon request from the architect/engineer.

1.05 INFORMATIONAL SUBMITTALS

- A. Welding certificates.
- B. Paint Compatibility Certificates: From manufacturers of topcoats applied over shop primers, certifying that shop primers are compatible with topcoats.
- C. Mill test reports for structural steel, including chemical and physical properties.
- D. Product Test Reports: For the following:
 - 1. Direct-tension indicators.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 2. Tension-control, high-strength, bolt-nut-washer assemblies.
- 3. Shop Primers.
- 4. Nonshrink grout.
- E. LEED Submittals required for any credits sought by the owner.

1.06 QUALITY ASSURANCE

- A. Fabricator Qualifications: Engage a qualified fabricator/erector with successful completion of multiple projects of comparable scale and scope over the previous five years.
- B. Welding Qualifications: Qualify procedures and personnel according to AWS D1.1, "Structural Welding Code-Steel."

1.07 DELIVERY, STORAGE, AND HANDLING

- A. Store materials to permit easy access for inspection and identification. Keep steel members off ground and spaced by using pallets, dunnage, or other supports and spacers. Protect steel members and packaged materials from corrosion and deterioration.
 - 1. Do not store materials on structure in a manner that might cause distortion, damage, or overload to members or supporting structures. Repair or replace damaged materials or structures as directed.
- B. Store fasteners in a protected place in sealed containers with manufacturer's labels intact.
 - 1. Fasteners may be repackaged provided Owner's testing and inspecting agency observes repackaging and seals containers.
 - 2. Clean and relubricate bolts and nuts that become dry or rusty before use.
 - 3. Comply with manufacturers' written recommendations for cleaning and lubricating ASTM F 1852 fasteners and for retesting fasteners after lubrication.

PART 2 PRODUCTS

2.01 STRUCTURAL-STEEL MATERIALS

- A. Recycled Content of Steel Products: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.
- B. W-Shapes: ASTM A 992, Grade 50.
- C. Channels, Angles, M, S-Shapes: ASTM A 36, Grade 50.
- D. Plate and Bar: ASTM A 36, Grade 50.
- E. Steel Pipe: ASTM A53/A53M, Type E or Type S, Grade B.
- F. Cold-Formed Hollow Structural Sections: ASTM A 500, Grade B structural tubing.

2.02 BOLTS, CONNECTORS, AND ANCHORS

- A. High-Strength Bolts, Nuts, and Washers: ASTM A 325 heavy-hex steel structural bolts; ASTM A 563, Grade C, heavy-hex carbon-steel nuts; and ASTM F 436, hardened carbon-steel washers; all with plain finish.
 - 1. Direct-Tension Indicators: ASTM F 959, Type 325 compressible-washer type with plain finish.
- B. High-Strength Bolts, Nuts, and Washers: ASTM A 490, heavy-hex steel structural bolts: ASTM A 563, heavy-hex carbon-steel nuts; and ASTM F 436, hardened carbon-steel washers with plain finish.
 - 1. Direct-Tension Indicators: ASTM F 959, Type 490 compressible-washer type with plain finish.
- C. Shear Connectors: ASTM A108, Grades 1015 through 1020, headed-stud type, cold-finished carbon steel; AWS D1.1/D1.1M, Type B.
- D. Anchor Rods: ASTM F1554, Grade 36.
- E. Threated Rods: ASTM A 36, Grade 50, unless indicated otherwise.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- F. Nuts: ASTM A 563, heavy-hex carbon steel.
- G. Washers: ASTM F 436, hardened carbon steel.
- H. Plate Washers: ASTM A36/A36M, carbon steel.

2.03 PRIMER

- A. Primer: Fabricator's standard lead- and chromate-free, nonasphaltic, rust-inhibiting primer complying with MPI#79 and compatible with topcoat, or as needed to achieve project LEED requirements.
- B. Galvanizing Repair Paint: MPI#18, MPI#19, or SSPC-Paint 20, ASTM A 780.

2.04 GROUT

A. Nonmetallic, Shrinkage-Resistant Grout: ASTM C 1107, factory packaged, nonmetallic aggregate grout, noncorrosive and nonstaining, mixed with water to consistency suitable for application and a 30-minute working time.

2.05 FABRICATION

- A. Structural Steel: Fabricate and assemble in shop to greatest extent possible. Fabricate according to AISC 303, "Code of Standard Practice for Steel Buildings and Bridges," and to AISC 360.
 - 1. Camber structural-steel members where indicated.
 - 2. Fabricate beams with rolling camber up.
 - 3. Identify high-strength structural steel according to ASTM A 6 and maintain markings until structural steel has been erected.
 - 4. Mark and match-mark materials for field assembly.
 - 5. Complete structural-steel assemblies, including welding of units, before starting shoppriming operations.
- B. Thermal Cutting: Perform thermal cutting by machine to greatest extent possible.
 1. Plane thermally cut edges to be welded to comply with requirements in AWS D1.1.
- C. Bolt Holes: Cut, drill, or punch standard bolt holes perpendicular to metal surfaces.
- D. Finishing: Accurately finish ends of columns and other members transmitting bearing loads.
- E. Shear Connectors: Prepare steel surfaces as recommended by manufacturer of shear connectors. Use automatic end welding of head-stud shear connectors according to AWS D1.1/D.1M and manufacturer's written instructions.

2.06 SHOP CONNECTIONS

A. High-Strength Bolts: Shop install high-strength bolts according to RCSC's "Specification for Structural Joints Using ASTM A 325 or A 490 Bolts" for type of bolt and type of joint specified.

2.07 SHOP PRIMING

- A. Shop prime steel surfaces except the following:
 - 1. Surfaces embedded in concrete or mortar. Extend priming of partially embedded members to a depth of 2 inches (50.8 mm).
 - 2. Surfaces to be field welded.
 - 3. Surfaces of high-strength bolted, slip-critical connections.
 - 4. Surfaces to receive sprayed fire-resistive materials (applied fireproofing).
 - 5. Galvanized surfaces.
 - 6. Surfaces enclosed in interior construction that are to be concealed by architectural finishes other than paint.
- B. Surface Preparation: Clean surfaces to be painted. Remove loose rust and mill scale and spatter, slag, or flux deposits. Prepare surfaces according to the applicable SSPC standards.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

C. Priming: Immediately after surface preparation, apply primer according to manufacturer's written instructions and at rate recommended by SSPC to provide a minimum dry film thickness of 1.5 mils (0.0381 mm). Use priming methods that result in full coverage of joints, corners, edges, and exposed surfaces.

2.08 GALVANIZING

- A. Hot-Dip Galvanized Finish: Apply zinc coating by the hot-dip process to structural steel according to ASTM A 123.
 - 1. Fill vent and drain holes that are exposed in the finished Work unless they function as weep holes, by plugging with zinc solder and filing off smooth.

2.09 SOURCE QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified testing agency to perform shop tests and inspections.
 - 1. Provide testing agency with access to places where structural-steel work is being fabricated or produced to perform tests and inspections.
- B. Bolted Connections: Inspect and test shop-bolted connections according to RCSC's "Specification for Structural Joints Using ASTM A 325 or A 490 Bolts."
- C. Welded Connections: Visually inspect shop-welded connections according to AWS D1.1and the following inspection procedures, at testing agency's option:
 - 1. Liquid Penetrant Inspection: ASTM E 165.
 - 2. Magnetic Particle Inspection: ASTM E709; performed on root pass and on finished weld. Cracks or zones of incomplete fusion or penetration are not accepted.
 - 3. Ultrasonic Inspection: ASTM E164.
 - 4. Radiographic Inspection: ASTM E 94.
- D. In addition to visual inspection, test and inspect shop-welded shear connectors according to requirements in AWS D1.1/D1.1M for stud welding and as follows:
 - 1. Perform bend tests if visual inspections reveal either a less-than-continuous 360-degree flash or welding repairs to any shear connector.
 - 2. Conduct tests according to requirements in AWS D1.1 on additional shear connectors if weld fracture occurs on shear connectors already tested.
- E. Prepare test and inspection reports.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify, with certified steel erector present, elevations of concrete- and masonry-bearing surfaces and locations of anchor rods, bearing plates, and other embedments for compliance with requirements.
 - 1. Prepare a certified survey of existing conditions. Include bearing surfaces, anchor rods, bearing plates, and other embedments showing dimensions, locations, angles, and elevations.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.02 PREPARATION

- A. Provide temporary shores, guys, braces, and other supports during erection to keep structural steel secure, plumb, and in alignment against temporary construction loads and loads equal in intensity to design loads. Remove temporary supports when permanent structural steel, connections, and bracing are in place unless otherwise indicated.
 - 1. Do not remove temporary shoring supporting composite deck construction until cast-inplace concrete has attained its design compressive strength.
50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

3.03 ERECTION

- A. Set structural steel accurately in locations and to elevations indicated and according to AISC 303 and AISC 360.
- B. Baseplates, Bearing Plates, and Leveling Plates: Clean concrete- and masonry-bearing surfaces of bond-reducing materials, and roughen surfaces prior to setting plates. Clean bottom surface of plates.
 - 1. Set plates for structural members on wedges, shims, or setting nuts as required.
 - 2. Weld plate washers to top of baseplate.
 - 3. Tighten anchor rods after supported members have been positioned and plumbed. Do not remove wedges or shims but, if protruding, cut off flush with edge of plate before packing with grout.
 - 4. Promptly pack grout solidly between bearing surfaces and plates so no voids remain. Neatly finish exposed surfaces; protect grout and allow to cure.
- C. Maintain erection tolerances of structural steel within AISC 303, "Code of Standard Practice for Steel Buildings and Bridges."
- D. Align and adjust various members that form part of complete frame or structure before permanently fastening. Before assembly, clean bearing surfaces and other surfaces that are in permanent contact with members. Perform necessary adjustments to compensate for discrepancies in elevations and alignment.
 - 1. Level and plumb individual members of structure.
 - 2. Make allowances for difference between temperature at time of erection and mean temperature when structure is completed and in service.
- E. Splice members only where indicated.
- F. Do not enlarge unfair holes in members by burning or using drift pins. Ream holes that must be enlarged to admit bolts.
- G. Shear Connectors: Prepare steel surfaces as recommended by manufacturer of shear connectors. Use automatic end welding of headed-stud shear connectors according to AWS D1.1/D1.1M and manufacturer's written instructions.

3.04 FIELD CONNECTIONS

- A. High-Strength Bolts: Install high-strength bolts according to RCSC's "Specification for Structural Joints Using ASTM A 325 or A 490 Bolts" for type of bolt and type of joint specified.
- B. Weld Connections: Comply with AWS D1.1 for tolerances, appearances, welding procedure specifications, weld quality, and methods used in correcting welding work.
 - 1. Comply with AISC 303 and AISC 360 for bearing, alignment, adequacy of temporary connections, and removal of paint on surfaces adjacent to field welds.
 - 2. Assemble and weld built-up sections by methods that maintain true alignment of axes without exceeding tolerances in AISC 303, "Code of Standard Practice for Steel Buildings and Bridges," for mill material.

3.05 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.
- B. Bolted Connections: Inspect and test bolted connections according to RCSC's "Specification for Structural Joints Using ASTM A 325 or A 490 Bolts."
- C. Welded Connections: Visually inspect field welds according to AWS D1.1.
 - 1. In addition to visual inspection, test and inspect field welds according to AWS D1.1/D1.1M and the following inspection procedures, at testing agency's option:
 - a. Liquid Penetrant Inspection: ASTM E 165.
 - b. Magnetic Particle Inspection: ASTM E709; performed on root pass and on finished weld. Cracks or zones of incomplete fusion or penetration are not accepted.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- c. Ultrasonic Inspection: ASTM E164.
- d. Radiographic Inspection: ASTM E 94.
- D. In addition to visual inspection, test and inspect field-welded shear connectors according to requirements in AWS D1.1/D1.1M for stud welding and as follows:
 - 1. Perform bend tests if visual inspections reveal either a less-than-continuous 360-degree flash or welding repairs to any shear connector.
 - 2. Conduct tests according to requirements in AWS D1.1on additional shear connectors if weld fracture occurs on shear connectors already tested.

3.06 REPAIRS AND PROTECTION

- A. Galvanized Surfaces: Clean areas where galvanizing is damaged or missing and repair galvanizing to comply with ASTM A 780.
- B. Touchup Painting: Immediately after erection, clean exposed areas where primer is damaged or missing and paint with the same material as used for shop painting to comply with SSPC-PA 1 for touching up shop-painted surfaces.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 052100 STEEL JOIST FRAMING

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. ASTM E164 Standard Practice for Contact Ultrasonic Testing of Weldments; 2019.
- B. ASTM E165/E165M Standard Practice for Liquid Penetrant Testing for General Industry; 2023.
- C. ASTM E709 Standard Guide for Magnetic Particle Testing; 2021.
- D. AWS D1.1/D1.1M Structural Welding Code Steel; 2020, with Errata (2023).
- E. SSPC-SP 2 Hand Tool Cleaning; 2024.
- F. SSPC-SP 3 Power Tool Cleaning; 2024.

1.02 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.03 SUMMARY

A. Section Includes open web steel joists, girders, and accessories as defined by the Steel Joist Institute

1.04 ACTION SUBMITTALS

- A. Shop Drawings:
 - 1. Include layout, designation, number, type, location, and spacing of joists.
 - 2. Include joining and anchorage details; bracing, bridging, and joist accessories; splice and connection locations and details; and attachments to other construction.
 - 3. Indicate locations and details of bearing plates to be embedded in other construction.

1.05 INFORMATIONAL SUBMITTALS

- A. Welding certificates.
- B. Comprehensive engineering analysis and design of special joists, with calculations signed and sealed by the qualified professional engineer responsible for its preparation.

1.06 QUALITY ASSURANCE

- A. Manufacturer Qualifications: A manufacturer certified by SJI to manufacture joists complying with applicable standard specifications and load tables in SJI's "Specifications
 - 1. Manufacturer's responsibilities include providing professional engineering services for designing special joists to comply with performance requirements.
- B. Welding Qualifications: Qualify field-welding procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code Steel."

1.07 DELIVERY, STORAGE, AND HANDLING

- A. Deliver, store, and handle joists as recommended in SJI's "Specifications"
- B. Protect joists from corrosion, deformation, and other damage during delivery, storage, and handling.

PART 2 PRODUCTS

2.01 PERFORMANCE REQUIREMENTS

- A. Structural Performance: Provide special joists and connections capable of withstanding design loads indicated on the drawings.
- B. Design special joists to withstand design loads with live-load deflections no greater than the following:

FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 1. Vertical live load/snow load deflection of 1/360 of the span.
- 2. Vertical total load deflection of 1/240 of the span.
- C. Recycled Content of Steel Products: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.

2.02 JOISTS AND GIRDERS

- A. Manufacture steel joists and girders of type indicated according to "Standard Specification for Open Web Steel Joists, K-Series" in SJI's "Specifications,"
- B. Camber joists according to SJI's "Specifications." Unless specified otherwise on drawings

2.03 JOIST ACCESSORIES

- A. Bridging: Provide bridging anchors and number of rows of bridging of material, size, and type as indicated on drawings and as required by SJI's "Specifications for type of joist, chord size, spacing, and span. Furnish additional erection bridging if required for stability.
- B. Fabricate steel bearing plates from ASTM A36 steel with integral anchorages of sizes and thicknesses indicated. Shop prime paint unless indicated otherwise
- C. Welding Electrodes: Comply with AWS standards.
- D. Furnish miscellaneous accessories including splice plates and bolts required by joist manufacturer to complete joist assembly.

2.04 CLEANING AND SHOP PAINTING

- A. Clean and remove loose scale, heavy rust, and other foreign materials from fabricated joists and accessories by hand-tool cleaning.
- B. Apply one coat of shop primer to joists and joist accessories to be primed to provide a continuous, dry paint film not less than 1 mil (0.0254 mm) thick.
- C. Do not prime paint joists and accessories to receive sprayed fire-resistive materials.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Examine supporting substrates, embedded bearing plates, and abutting structural framing for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.02 INSTALLATION

- A. Do not install joists until supporting construction is in place and secured.
- B. Install joists and accessories plumb, square, and true to line; securely fasten to supporting construction according to SJI's "Specifications", joist manufacturer's written instructions, and requirements in this Section.
 - 1. Before installation, splice joists delivered to Project site in more than one piece.
 - 2. Space, adjust, and align joists accurately in location before permanently fastening.
 - 3. Install temporary bracing and erection bridging, connections, and anchors to ensure that joists are stabilized during construction.
 - 4. Delay rigidly connecting bottom-chord extensions to columns or supports until dead loads are applied.
- C. Field weld joists to supporting steel bearing plates and framework. Coordinate welding sequence and procedure with placement of joists. Comply with AWS requirements and procedures for welding, appearance and quality of welds, and methods used in correcting welding work.
- D. Bolt joists to supporting steel framework using carbon-steel bolts.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- E. Bolt joists to supporting steel framework using high-strength structural bolts. Comply with RCSC's "Specification for Structural Joints Using ASTM A 325 or ASTM A 490 Bolts" for high-strength structural bolt installation and tightening requirements.
- F. Install and connect bridging concurrently with joist erection, before construction loads are applied. Anchor ends of bridging lines at top and bottom chords if terminating at walls or beams.

3.03 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.
- B. Visually inspect field welds according to AWS D1.1/D1.1M.
 - 1. In addition to visual inspection, test field welds according to AWS D1.1/D1.1M and the following procedures, at testing agency's option:
 - 2. Liquid Penetrant Inspection: ASTM E165/E165M.
 - 3. Magnetic Particle Inspection: ASTM E709.
 - 4. Ultrasonic Testing: ASTM E164.
 - 5. Radiographic Testing: ASTM E 94.
- C. Visually inspect bolted connections.
- D. Prepare test and inspection reports.

3.04 PROTECTION

- A. Repair damaged galvanized coatings on galvanized items with galvanized repair paint according to ASTM A 780 and manufacturer's written instructions.
- B. Touchup Painting: After installation, promptly clean, prepare, and prime or reprime field connections, rust spots, and abraded surfaces of prime-painted joists, bearing plates, abutting structural steel, and accessories.
 - 1. Clean and prepare surfaces by hand-tool cleaning according to SSPC-SP 2 or power-tool cleaning according to SSPC-SP 3.
 - 2. Apply a compatible primer of same type as primer used on adjacent surfaces.

FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 053100 STEEL DECK

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. ASTM A1008/A1008M Standard Specification for Steel, Sheet, Cold-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, Required Hardness, Solution Hardened, and Bake Hardenable; 2023, with Editorial Revision.
- B. ASTM E119 Standard Test Methods for Fire Tests of Building Construction and Materials; 2022.
- C. AWS D1.3/D1.3M Structural Welding Code Sheet Steel; 2018, with Errata (2022).
- D. UL 209 Cellular Metal Floor Raceways and Fittings; Current Edition, Including All Revisions.

1.02 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.03 SUMMARY

A. Section includes corrugated steel deck and accessories

1.04 INFORMATIONAL SUBMITTALS

- A. Shop Drawings: Include layout and types of deck panels, anchorage details, reinforcing channels, pans, cut deck openings, special jointing, accessories, and attachments to other construction
- B. Welding certificates.

1.05 QUALITY ASSURANCE

- A. Welding Qualifications: Qualify procedures and personnel according to AWS D1.3/D1.3M, "Structural Welding Code - Sheet Steel."
- B. Electrical Raceway Units: Provide UL-labeled cellular floor-deck units complying with UL 209 and listed in UL's "Electrical Construction Equipment Directory" for use with standard header ducts and outlets for electrical distribution systems.
- C. FM Global Listing: Provide steel roof deck evaluated by FM Global and listed in its "Approval Guide, Building Materials" for Class 1 fire rating and Class 1-90 windstorm ratings.

1.06 DELIVERY, STORAGE, AND HANDLING

- A. Protect steel deck from corrosion, deformation, and other damage during delivery, storage, and handling.
- B. Stack steel deck on platforms or pallets and slope to provide drainage. Protect with a waterproof covering and ventilate to avoid condensation.
 - 1. Protect and ventilate acoustical cellular roof deck with factory-installed insulation to maintain insulation free of moisture.

PART 2 PRODUCTS

2.01 PERFORMANCE REQUIREMENTS

- A. AISI Specifications: Comply with calculated structural characteristics of steel deck according to AISI's "North American Specification for the Design of Cold-Formed Steel Structural Members."
- B. Fire-Resistance Ratings: Comply with ASTM E119; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 - 1. Indicate design designations from UL's "Fire Resistance Directory" or from the listings of another qualified testing agency.

LAHC – WORKFORCE	50% CONSTRUCTION	FRAMEWORK E, LLC
EDUCATION RESOURCE AND	DOCUMENTS	
DEVELOPMENT CENTER	APRIL 11, 2025	PROJ. NO. 2024007

C. Recycled Content of Steel Products: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.

2.02 ROOF DECK

- A. Roof Deck: Fabricate panels to comply with "SDI Specifications and Commentary for Steel Roof Deck," in SDI Publication No. 31, and with the following:
 - 1. Provide deck of profile and gauge indicated on drawing.
 - 2. Provide deck from galvanized-steel sheet: ASTM A 653, Structural Steel (SS), Grade 33, G60 zinc coating unless indicated otherwise
 - 3. When specified as primed provide deck from Prime-Painted Steel Sheet: ASTM A1008/A1008M, Structural Steel (SS), shop primed with manufacturer's standard baked-on, rust-inhibitive primer.
 - 4. Span Condition: As indicated, otherwise triple span when practical and double span or greater when possible.
 - 5. Side Laps: Overlapped or interlocking seam at Contractor's option.
 - 6. When specified as acoustical deck, provide perforations, sound absorbing insulation, and or NRC rating as specified.

2.03 COMPOSITE FLOOR DECK

- A. Composite Floor Deck: Fabricate panels, with integrally embossed or raised pattern ribs and interlocking side laps, to comply with "SDI Specifications and Commentary for Composite Steel Floor Deck," in SDI Publication No. 31, with the minimum section properties indicated, and with the following:
 - 1. Provide deck of profile and gauge indicated on drawing.
 - 2. Provide deck from galvanized-steel sheet: ASTM A 653, Structural Steel (SS), Grade 40, G60 zinc coating unless indicated otherwise
 - 3. When specified as primed provide deck from Prime-Painted Steel Sheet: ASTM A 1008, shop primed with manufacturer's standard baked-on, rust-inhibitive primer.
 - 4. Span Condition: As indicated, otherwise triple span when practical and double span or greater when possible.
 - 5. Side Laps: Overlapped or interlocking seam at Contractor's option.
 - 6. When specified as acoustical deck, provide perforations, sound absorbing insulation, and or NRC rating as specified.

2.04 NON-COMPOSITE FLOOR DECK

- A. Composite Floor Deck: Fabricate panels, with integrally embossed or raised pattern ribs and interlocking side laps, to comply with "SDI Specifications and Commentary for Composite Steel Floor Deck," in SDI Publication No. 31, with the minimum section properties indicated, and with the following:
 - 1. Provide deck of profile and gauge indicated on drawing.
 - 2. Provide deck from galvanized-steel sheet: ASTM A 653, Structural Steel (SS), Grade 60 for deck 1.5" deep or less and Grade 33 2" deep or more, and G60 zinc coating unless indicated otherwise
 - 3. When specified as primed provide deck from Prime-Painted Steel Sheet: ASTM A 1008, shop primed with manufacturer's standard baked-on, rust-inhibitive primer.
 - 4. Span Condition: As indicated, otherwise triple span when practical and double span or greater when possible.
 - 5. Side Laps: Overlapped or interlocking seam at Contractor's option.

2.05 ACCESSORIES

- A. General: Provide manufacturer's standard accessory materials for deck that comply with requirements indicated.
- B. Mechanical Fasteners: Corrosion-resistant, low-velocity, power-actuated or pneumatically driven carbon-steel fasteners; or self-drilling, self-threading screws.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- C. Side-Lap Fasteners: Corrosion-resistant, hexagonal washer head; self-drilling, carbon-steel screws, No. 10 minimum diameter.
- D. Flexible Closure Strips: Vulcanized, closed-cell, synthetic rubber.
- E. Miscellaneous Sheet Metal Deck Accessories: Steel sheet, minimum yield strength of 33 ksi not less than 0.0359-inch design uncoated thickness, of same material and finish as deck; of profile indicated or required for application.
- F. Pour Stops and Girder Fillers: Steel sheet, minimum yield strength of 33 ksi of same material and finish as deck, and of thickness and profile recommended by SDI Publication No. 31 for overhang and slab depth.
- G. Column Closures, End Closures, Z-Closures, and Cover Plates: Steel sheet, of same material, finish, and thickness as deck unless otherwise indicated.
- H. Piercing Hanger Tabs: Piercing steel sheet hanger attachment devices for use with floor deck.
- I. Weld Washers: Uncoated steel sheet, shaped to fit deck rib, 0.0598 inch (1.52 mm) thick, with factory-punched hole of 3/8-inch minimum diameter.
- J. Flat Sump Plates: Single-piece steel sheet, 0.0747 inch (1.9 mm) thick, of same material and finish as deck. For drains, cut holes in the field.
- K. Recessed Sump Pans: Single-piece steel sheet, 0.0747 inch (1.9 mm) thick, of same material and finish as deck, with 3-inch- wide flanges and recessed pans of 1-1/2-inch minimum depth. For drains, cut holes in the field.
- L. Galvanizing Repair Paint: ASTM A 780.
- M. Repair Paint: Manufacturer's standard rust-inhibitive primer of same color as primer.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Examine supporting frame and field conditions for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.02 INSTALLATION, GENERAL

- A. Install deck panels and accessories according to applicable specifications and commentary in SDI Publication No. 31, manufacturer's written instructions, and requirements in this Section.
- B. Install temporary shoring before placing deck panels if required to meet deflection limitations.
- C. Locate deck bundles to prevent overloading of supporting members.
- D. Place deck panels on supporting frame and adjust to final position with ends accurately aligned and bearing on supporting frame before being permanently fastened. Do not stretch or contract side-lap interlocks.
 - 1. Align cellular deck panels over full length of cell runs and align cells at ends of abutting panels.
- E. Place deck panels flat and square and fasten to supporting frame without warp or deflection.
- F. Cut and neatly fit deck panels and accessories around openings and other work projecting through or adjacent to deck.
- G. Provide additional reinforcement and closure pieces at openings as required for strength, continuity of deck, and support of other work.
- H. Comply with AWS requirements and procedures for manual shielded metal arc welding, appearance and quality of welds, and methods used for correcting welding work.
- I. Mechanical fasteners may be used in lieu of welding to fasten deck. Locate mechanical fasteners and install according to deck manufacturer's written instructions.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

3.03 ROOF-DECK INSTALLATION

- A. Fasten roof-deck panels to steel supporting members by arc spot (puddle) welds of the surface diameter indicated or arc seam welds with an equal perimeter that is not less than 1-1/2 inches (38 mm) long, and as follows:
 - 1. Weld Diameter: 5/8 inch (15.88 mm) nominal.
 - Weld Spacing: Weld edge and interior ribs of deck units with a minimum of two welds per deck unit at each support. Space welds 12 inches (304.8 mm) apart in the field of roof and 6 inches (152.4 mm) apart in roof corners and perimeter, based on roof-area definitions in FMG Loss Prevention Data Sheet 1-28
 - 3. Weld Washers: Install weld washers at each weld location.
- B. Side-Lap and Perimeter Edge Fastening: Fasten side laps and perimeter edges of panels between supports, at intervals not exceeding the lesser of one-half of the span or 18 inches (457.2 mm) as follows:
 - 1. Mechanically fasten with self-drilling, No. 12 diameter or larger, carbon-steel screws.
 - 2. Fasten with a minimum of 1-1/2-inch- long welds.
- C. End Bearing: Install deck ends over supporting frame with a minimum end bearing of 1-1/2 inches (38 mm), with end joints as follows:
 - 1. End Joints: Lapped 2 inches (50.8 mm) minimum or butted at Contractor's option.
- D. Roof Sump Pans and Sump Plates: Install over openings provided in roof deck and weld or mechanically fasten not more than 12 inches (304.8 mm) apart with at least one fastener at each corner.
- E. Miscellaneous Roof-Deck Accessories: Install ridge and valley plates, finish strips, end closures, and reinforcing channels according to deck manufacturer's written instructions. Weld or mechanically fasten to substrate to provide a complete deck installation.
 - 1. Weld cover plates at changes in direction of roof-deck panels unless otherwise indicated.
- F. Flexible Closure Strips: Install flexible closure strips over partitions, walls, and where indicated. Install with adhesive according to manufacturer's written instructions to ensure complete closure.

3.04 FLOOR-DECK INSTALLATION

- A. Fasten floor-deck panels to steel supporting members by arc spot (puddle) welds of the surface diameter indicated and as follows:
 - 1. Weld Diameter: 5/8 inch (15.88 mm) nominal.
 - 2. Weld Spacing: Weld every rib of panels to each support.
 - 3. Weld Washers: Install weld washers at each weld location.
- B. Side-Lap and Perimeter Edge Fastening: Fasten side laps and perimeter edges of panels between supports, at intervals not exceeding the lesser of one-half of the span or 36 inches (914.4 mm) and as follows:
 - 1. Mechanically fasten with self-drilling, No. 12 diameter or larger, carbon-steel screws.
 - 2. Fasten with a minimum of 1-1/2-inch- long welds.
- C. End Bearing: Install deck ends over supporting frame with a minimum end bearing of 1-1/2 inches (38 mm) with end joints lapped or butted at contractors option:
- D. Pour Stops and Girder Fillers: Weld steel sheet pour stops and girder fillers to supporting structure according to SDI recommendations unless otherwise indicated.
- E. Floor-Deck Closures: Weld steel sheet column closures, cell closures, and Z-closures to deck, according to SDI recommendations, to provide tight-fitting closures at open ends of ribs and sides of deck.

3.05 FIELD QUALITY CONTROL

A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- B. Field welds will be subject to inspection.
- C. Prepare test and inspection reports.

3.06 PROTECTION

- A. Galvanizing Repairs: Prepare and repair damaged galvanized coatings on both surfaces of deck with galvanized repair paint according to ASTM A 780 and manufacturer's written instructions.
- B. Repair Painting: Wire brush and clean rust spots, welds, and abraded areas of prime-painted deck immediately after installation, and apply repair paint.
 - 1. Apply repair paint, of same color as adjacent shop-primed deck, to bottom surfaces of deck exposed to view.
 - 2. Wire brushing, cleaning, and repair painting of bottom deck surfaces are included in Section 099113 "Exterior Painting" and Section 099123 "Interior Painting."
- C. Repair Painting: Wire brushing, cleaning, and repair painting of rust spots, welds, and abraded areas of both deck surfaces are included in Section 099113 "Exterior Painting" and Section 099123 "Interior Painting."

FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 054000 COLD-FORMED METAL FRAMING

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Formed steel stud exterior wall framing.
- B. Formed steel joist and purlin framing and bridging.

1.02 RELATED REQUIREMENTS

- A. Section 061600: Sheathing.
- B. Section 092116 Gypsum Board Assemblies: Cold-formed steel nonstructural framing.
- C. Section 092216 Non-Structural Metal Framing.

1.03 DEFINITIONS

- A. General: See AISI S240 for definitions of terms used in this section.
- B. Connection: A combination of structural elements and joints used to transmit forces between two or more members.
- C. Connector: A device used to transmit forces between cold-formed steel structural members or between a cold-formed steel structural member and another structural element.

1.04 REFERENCE STANDARDS

- A. AISI S100 North American Specification for the Design of Cold-Formed Steel Structural Members; 2016, with Supplement (2020).
- B. AISI S201 North American Standard for Cold-Formed Steel Framing Product Data; 2017.
- C. AISI S240 North American Standard for Cold-Formed Steel Structural Framing; 2015, with Errata (2020).
- D. ASCE 7 Minimum Design Loads and Associated Criteria for Buildings and Other Structures; Most Recent Edition Cited by Referring Code or Reference Standard.
- E. ASTM A153/A153M Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware; 2023.
- F. ASTM A780/A780M Standard Practice for Repair of Damaged and Uncoated Areas of Hot-Dip Galvanized Coatings; 2020.
- G. ASTM A1003/A1003M Standard Specification for Steel Sheet, Carbon, Metallic- and Nonmetallic-Coated for Cold-Formed Framing Members; 2015.
- H. ASTM C1007 Standard Specification for Installation of Load Bearing (Transverse and Axial) Steel Studs and Related Accessories; 2020.
- I. AWS B2.1/B2.1M Specification for Welding Procedure and Performance Qualification; 2021, with Errata (2023).
- J. AWS D1.3/D1.3M Structural Welding Code Sheet Steel; 2018, with Errata (2022).
- K. ICC (IBC) International Building Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.

1.05 ADMINISTRATIVE REQUIREMENTS

- A. Coordinate with work of other sections that is to be installed in or adjacent to metal framing systems, including but not limited to structural anchors, cladding anchors, utilities, insulation, and firestopping.
- B. Preinstallation Meeting: Conduct a preinstallation meeting one week prior to the start of the work of this section; require attendance by affected installers.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

1.06 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Product Data: Provide data on cold-formed steel structural members; include material descriptions and base steel thickness.
- C. Product Data: Provide manufacturer's data on factory-made connectors and mechanical fasteners, showing compliance with requirements.
- D. Product Data: For lateral-force resisting systems, provide product data sheets on hold-down, showing compliance with requirements.
- E. Shop Drawings: Indicate component details, framed openings, bearing, anchorage, loading, welds, and type and location of fasteners, and accessories or items required of related work.
 - 1. Indicate stud and ceiling joist layout.
 - 2. Describe method for securing studs to tracks and for bolted framing connections.
- F. Steel Framing Industry Association (SFIA) Certification:
 - 1. Submit documentation that metal studs and connectors used on project meet or exceed requirements of International Building Code.
 - 2. Submit current documentation of contractor accreditation and installer certification. Keep copies of each on-site during and after installation, and present upon request.
- G. Design Data:
 - 1. Shop drawings signed and sealed by a professional structural engineer licensed in the state in which The Work is being performed.
 - 2. Design calculations sufficient to demonstrate compliance with design criteria; signed and sealed by a professional structural engineer licensed in the state in which The Work is being performed.
 - 3. Details and calculations for factory-made connectors, signed and sealed by a professional structural engineer licensed in the state in which The Work is being performed.
- H. Inspection Reports: Provide material verification Inspection Reports in accordance with requirements of AISI S240.
- I. Designer's Qualification Statement.
- J. Testing Agency Qualification Statement.
- K. Welders' Qualification Statement: Welders' certificates in accordance with AWS B2.1/B2.1M and dated no more than 12 months before the start of scheduled welding work.

1.07 QUALITY ASSURANCE

- A. See Section 014000 Quality Requirements for additional requirements.
- B. Designer Qualifications: Design framing system under direct supervision of a professional structural engineer experienced in designing this work and licensed in the State in which the Project is located.
- C. SFIA Code Compliance Certification Program: www.CFsteel.org/#sle: Use metal studs and connectors certified for compliance with International Building Code.
- D. Manufacturer Qualifications: Company specializing in manufacturing the types of products specified in this section, and with minimum three years of documented experience.
- E. Manufacturer Qualifications: Member of Steel Stud Manufacturers Association (SSMA): www.ssma.com/#sle.
- F. Manufacturer Qualifications: Member of Supreme Steel Framing System Association (SSFSA): www.ssfsa.com/#sle.
- G. Professional Contractor and Truss Fabricator Qualifications: SFIA-accredited contractor and fabricator: www.CFsteel.org/#sle.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- H. Welder Qualifications: Welding processes and welding operators qualified in accordance with AWS D1.1/D1.1M and AWS D1.3/D1.3M and dated no more than 12 months before start of scheduled welding work.
- I. Installer Qualifications: Company specializing in performing the work of this section with minimum three years documented experience and approved by manufacturer.

1.08 MOCK-UPS

- A. See Section 014000 Quality Requirements for additional requirements.
- B. Provide mock-up of exterior framed wall, including components specified elsewhere, such as insulation, sheathing, window frame, door frame, and exterior wall finish.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Structural Framing:
 - 1. CEMCO: www.cemcosteel.com/#sle.
 - 2. ClarkDietrich: www.clarkdietrich.com/#sle.
 - 3. Jaimes Industries: www.jaimesind.com/#sle.
 - 4. MarinoWARE: www.marinoware.com/#sle.
 - 5. SCAFCO Corporation: www.scafco.com/#sle.
 - 6. Steel Construction Systems: www.steelconsystems.com/#sle.
 - 7. The Steel Network, Inc: www.SteelNetwork.com/#sle.
 - 8. Substitutions: See Section 016000 Product Requirements.

B. Connectors:

- 1. ClarkDietrich: www.clarkdietrich.com/#sle.
- 2. MarinoWARE: www.marinoware.com/#sle.
- 3. Simpson Strong-Tie: www.strongtie.com/#sle.
- 4. Substitutions: See Section 016000 Product Requirements.

2.02 PERFORMANCE REQUIREMENTS

- A. Comply with requirements for Contractor's design-related professional design services indicated in Section 014000 Quality Requirements.
- B. Design Requirements: Design cold-formed framing systems, components and connectors to withstand specified design loads in compliance with ICC (IBC), ASCE 7, AISI S100, and AISI S240.
- C. Design Criteria: As indicated on the drawings.
 - 1. Live load deflection meeting the following, unless otherwise indicated:
 - 2. Able to tolerate movement of components without damage, failure of joint seals, undue stress on fasteners, or other detrimental effects when subject to seasonal or cyclic day/night temperature ranges.
 - 3. Able to accommodate construction tolerances, deflection of building structural members, and clearances of intended openings.
- D. Fabrication:
 - 1. Shop-fabricate cold-formed framing systems and connectors to the greatest extent possible.
 - 2. Deliver to project site in largest practical sections.

2.03 MATERIALS

- A. Material and Product Requirements Criteria: AISI S201.
- B. Steel Sheet: ASTM A1003/A1003M, subject to the ductility limitations indicated in AISI S240.
 - 1. Structural Grade: As required to meet design criteria.
 - 2. Corrosion Protection Coating Designation: CP 60 in accordance with AISI S240.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

2.04 STRUCTURAL FRAMING COMPONENTS

- A. Wall Studs and Track Sections: AISI S240; c-shaped studs and u-shaped track sections in stud-matching nominal width and compatible height.
- B. Headers: AISI S240; manufactured, engineered one-member or two-member assemblies, with wide flanges, designed to replace conventional box or nested header framing at openings.
 - 1. Jamb Mounting Clips: Manufacturer's standard.
 - 2. Cripple Stud Clips: Manufacturer's standard.
- C. Joists: AISI S240; manufactured, engineered open-web steel joists.

2.05 LATERAL FORCE-RESISTING SYSTEMS

- A. Steel Sheet: ASTM A1003/A1003M, subject to the ductility limitations indicated in AISI S240.
 - 1. Structural Grade: As required to meet design criteria.
 - 2. Corrosion Protection Coating Designation: CP 60 in accordance with AISI S240.
- B. Curtain Wall Studs and Girts:

2.06 CONNECTIONS

- A. Performance Requirements: Provide connections in compliance with requirements of AISI S240.
- B. Steel Sheet: ASTM A1003/A1003M, subject to the ductility limitations indicated in AISI S240.
 - 1. Structural Grade: As required to meet design criteria.
 - 2. Corrosion Protection Coating Designation: CP 60 in accordance with AISI S240.
- C. Structural Performance: Maintain load and movement capacity required by applicable building code and specified design criteria.
- D. Movement Connections: Provide mechanical anchorage devices that accommodate movement using slotted holes, shouldered screws or screws and anti-friction or stepped bushings, while maintaining structural performance of framing. Provide movement connections where indicated on drawings.
 - 1. Where continuous studs bypass elevated floor slab, connect stud to slab in manner allowing vertical and horizontal movement of slab without affecting studs; allow for minimum movement of 1/2 inch (13 mm).
 - 2. Where top of stud wall terminates below structural floor or roof, connect studs to structure in manner allowing vertical movement of slab without affecting studs; allow for minimum movement of 1/2 inch (13 mm).
 - 3. Provide top track preassembled with connection devices spaced to fit stud spacing indicated on drawings; minimum track length of 10 feet (3048 mm).
 - 4. Products:
 - a. ClarkDietrich; Drift Rail and Clip (DRC): www.clarkdietrich.com/#sle.
 - b. ClarkDietrich; Drift FastClip Slide Clip D-FCSC: www.clarkdietrich.com/#sle.
 - c. Simpson Strong-Tie; SCB Side-Clip Connector: www.strongtie.com/#sle.
 - d. Super Stud Building Products, Inc; Deflection Clips: www.buysuperstud.com/#sle.

2.07 MISCELLANEOUS CONNECTIONS

- A. Self-Drilling, Self-Tapping Screws, Bolts, Nuts and Washers: Hot-dip galvanized per ASTM A153/A153M.
- B. Anchorage Devices: Powder actuated.
- C. Welding: Comply with AWS D1.1/D1.1M.

2.08 ACCESSORIES

A. Bracing, Furring, Bridging: Formed sheet steel, thickness determined for conditions encountered; finish to match framing components.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

B. Galvanizing Repair: Touch up bare steel with zinc-rich paint in compliance with ASTM A780/A780M.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that substrate surfaces are ready to receive work.

3.02 PREPARATION

A. Structural Wall Foundations: For gaps between wall bottom track and top of foundation 1/4 inch (6.4 mm) or greater, level substrate with loadbearing shims or grout between track and foundation.

3.03 INSTALLATION - GENERAL

A. Install structural members and connections in compliance with ASTM C1007.

3.04 INSTALLATION OF STUDS

- A. Install wall studs plumb and level.
- B. Construct corners using minimum of three studs. Install double studs at wall openings, door and window jambs.
- C. Install load-bearing studs full length in one piece. Splicing of studs is not permitted.
- D. Install load-bearing studs; brace, and reinforce to develop full strength and achieve design requirements.
- E. Install intermediate studs above and below openings to align with wall stud spacing.
- F. Provide deflection allowance in stud track, directly below horizontal building framing at nonloadbearing framing.
- G. Attach cross studs to studs for attachment of fixtures anchored to walls.
- H. Install framing between studs for attachment of mechanical and electrical items, and to prevent stud rotation.

3.05 FIELD QUALITY CONTROL

- A. See Section 014000 Quality Requirements, for additional requirements.
- B. Provide material verification inspections in accordance with requirements of AISI S240.
- C. Provide inspections for welding, mechanical fastening, and cold-formed steel light-frame construction in accordance with requirements of AISI S240.

3.06 TOLERANCES

- A. Studs Vertical Alignment (Plumbness): 1/960 of span or 1/8 inch in 10 ft (3.2 mm in 3000 mm), in accordance with ASTM C1007.
- B. Stud Spacing: 1/8 inch (3.2 mm) from the designated spacing, provided that the cumulative error does not exceed the requirements of the finishing materials in accordance with ASTM C1007.

FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 055000 METAL FABRICATIONS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Shop fabricated steel and aluminum items.

1.02 RELATED REQUIREMENTS

- A. Section 042000 Unit Masonry: Placement of metal fabrications in masonry.
- B. Section 055213 Pipe and Tube Railings.

1.03 REFERENCE STANDARDS

- A. AAMA 611 Specification for Anodized Architectural Aluminum; 2024.
- B. ASTM A276/A276M Standard Specification for Stainless Steel Bars and Shapes; 2024.
- C. ASTM A36/A36M Standard Specification for Carbon Structural Steel; 2019.
- D. ASTM A53/A53M Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless; 2022.
- E. ASTM A283/A283M Standard Specification for Low and Intermediate Tensile Strength Carbon Steel Plates; 2018.
- F. ASTM A307 Standard Specification for Carbon Steel Bolts, Studs, and Threaded Rod 60 000 PSI Tensile Strength; 2021.
- G. ASTM A501/A501M Standard Specification for Hot-Formed Welded and Seamless Carbon Steel Structural Tubing; 2021.
- H. ASTM A554 Standard Specification for Welded Stainless Steel Mechanical Tubing; 2021.
- I. ASTM A666 Standard Specification for Annealed or Cold-Worked Austenitic Stainless Steel Sheet, Strip, Plate, and Flat Bar; 2023.
- J. ASTM B210/B210M Standard Specification for Aluminum and Aluminum-Alloy Drawn Seamless Tubes; 2019a.
- K. ASTM B211/B211M Standard Specification for Aluminum and Aluminum-Alloy Rolled or Cold Finished Bar, Rod, and Wire; 2019.
- L. ASTM B209/B209M Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate; 2021a.
- M. ASTM B221 Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes; 2021.
- N. AWS A2.4 Standard Symbols for Welding, Brazing, and Nondestructive Examination; 2020.
- O. AWS B2.1/B2.1M Specification for Welding Procedure and Performance Qualification; 2021, with Errata (2023).
- P. AWS D1.1/D1.1M Structural Welding Code Steel; 2020, with Errata (2023).
- Q. AWS D1.2/D1.2M Structural Welding Code Aluminum; 2014, with Errata (2020).
- R. SSPC-Paint 15 Steel Joist Shop Primer/Metal Building Primer; 2004.
- S. SSPC-Paint 20 Zinc-Rich Coating (Type I Inorganic, and Type II Organic); 2019.
- T. SSPC-SP 2 Hand Tool Cleaning; 2024.

1.04 SUBMITTALS

- A. See Section 013000 Administrative Requirements, for submittal procedures.
- B. Shop Drawings: Indicate profiles, sizes, connection attachments, reinforcing, anchorage, size and type of fasteners, and accessories. Include erection drawings, elevations, and details

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

where applicable, signed and sealed by a professional structural engineer licensed in the state in which The Work is being performed.

- 1. Indicate welded connections using standard AWS A2.4 welding symbols. Indicate net weld lengths.
- 2. Design data: Submit drawings and supporting calculations, signed and sealed by a qualified professional structural engineer.
 - a. Include the following, as applicable:
 - 1) Design criteria.
 - 2) Engineering analysis depicting stresses and deflections.
 - 3) Member sizes and gauges.
 - 4) Details of connections.
 - 5) Support reactions.
 - 6) Bracing requirements.
- C. Welders' Qualification Statement: Welders' certificates in accordance with AWS B2.1/B2.1M and dated no more than 12 months before start of scheduled welding work.
- D. Designer's Qualification Statement.

1.05 QUALITY ASSURANCE

- A. Design under direct supervision of a Professional Structural Engineer experienced in design of this work and licensed in the State in which the Project is located.
- B. Welder Qualifications: Welding processes and welding operators qualified in accordance with AWS D1.1/D1.1M and AWS D1.2/D1.2M and dated no more than 12 months before start of scheduled welding work.

PART 2 PRODUCTS

2.01 MATERIALS - STEEL

- A. Steel Sections: ASTM A36/A36M.
- B. Steel Tubing: ASTM A501/A501M hot-formed structural tubing.
- C. Plates: ASTM A283/A283M.
- D. Pipe: ASTM A53/A53M, Grade B Schedule 40, black finish.
- E. Stainless Steel, General: ASTM A666, Type 304.
- F. Stainless Steel Tubing: ASTM A554, Type 304, 16 gauge, 0.0625 inch (1.59 mm) minimum metal thickness, 1-1/2 inch (38 mm) diameter.
- G. Stainless Steel Bars, Shapes and Moldings: ASTM A276/A276M, Type 304.
- H. Mechanical Fasteners: Same material as or compatible with materials being fastened; type consistent with design and specified quality level.
- I. Bolts, Nuts, and Washers: ASTM A307, Grade A, plain.
- J. Welding Materials: AWS D1.1/D1.1M; type required for materials being welded.
- K. Shop and Touch-Up Primer: SSPC-Paint 15, complying with VOC limitations of authorities having jurisdiction.
- L. Touch-Up Primer for Galvanized Surfaces: SSPC-Paint 20, Type I Inorganic, complying with VOC limitations of authorities having jurisdiction.

2.02 MATERIALS - ALUMINUM

- A. Extruded Aluminum: ASTM B221 (ASTM B221M), 6063 alloy, T6 temper.
- B. Sheet Aluminum: ASTM B209/B209M, 5052 alloy, H32 or H22 temper.
- C. Aluminum-Alloy Drawn Seamless Tubes: ASTM B210/B210M, 6063 alloy, T6 temper.
- D. Aluminum-Alloy Bars: ASTM B211/B211M, 6061 alloy, T6 temper.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- E. Bolts, Nuts, and Washers: Stainless steel.
- F. Welding Materials: AWS D1.2/D1.2M; type required for materials being welded.

2.03 FABRICATION

- A. Fit and shop assemble items in largest practical sections, for delivery to site.
- B. Fabricate items with joints tightly fitted and secured.
- C. Grind exposed joints flush and smooth with adjacent finish surface. Make exposed joints butt tight, flush, and hairline. Ease exposed edges to small uniform radius.
- D. Furnish components required for anchorage of fabrications. Fabricate anchors and related components of same material and finish as fabrication, except where specifically noted otherwise.

2.04 FABRICATED ITEMS

- A. Bollards: Steel pipe, concrete filled, crowned cap, as detailed; prime paint finish.
- B. Joist Hangers: Strap anchors, fabricated with sheet steel, 18 gauge, 0.0478 inch (1.21 mm) minimum base metal thickness; galvanized finish.
- C. Ledge Angles, Shelf Angles, Channels, and Plates Not Attached to Structural Framing: For support of metal decking; prime paint finish.
- D. Lintels: As detailed; prime paint finish.
- E. Door Frames for Overhead Door Openings: Angle sections; prime paint finish.
- F. Recessed Mat Frames : As detailed; steel, galvanized finish.
- G. Toilet Partition Suspension Members: Steel angle sections; prime paint finish.

2.05 FINISHES - STEEL

- A. Prime paint steel items.
- B. Prepare surfaces to be primed in accordance with SSPC-SP2.
- C. Clean surfaces of rust, scale, grease, and foreign matter prior to finishing.
- D. Prime Painting: One coat.

2.06 FINISHES - ALUMINUM

- A. Exterior Aluminum Surfaces: Class I natural anodized.
- B. Interior Aluminum Surfaces: Class II natural anodized.
- C. Class I Natural Anodized Finish: AAMA 611 AA-M12C22A41 Clear anodic coating not less than 0.7 mils (0.018 mm) thick.
- D. Class II Natural Anodized Finish: AAMA 611 AA-M12C22A31 Clear anodic coating not less than 0.4 mils (0.01 mm) thick.

2.07 FABRICATION TOLERANCES

- A. Squareness: 1/8 inch (3 mm) maximum difference in diagonal measurements.
- B. Maximum Offset Between Faces: 1/16 inch (1.5 mm).
- C. Maximum Misalignment of Adjacent Members: 1/16 inch (1.5 mm).
- D. Maximum Bow: 1/8 inch (3 mm) in 48 inches (1.2 m).
- E. Maximum Deviation From Plane: 1/16 inch (1.5 mm) in 48 inches (1.2 m).

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that field conditions are acceptable and are ready to receive work.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

3.02 PREPARATION

- A. Clean and strip primed steel items to bare metal where site welding is required.
- B. Furnish setting templates to the appropriate entities for steel items required to be cast into concrete or embedded in masonry.

3.03 INSTALLATION

- A. Install items plumb and level, accurately fitted, free from distortion or defects.
- B. Provide for erection loads, and for sufficient temporary bracing to maintain true alignment until completion of erection and installation of permanent attachments.
- C. Obtain approval prior to site cutting or making adjustments not scheduled.

3.04 TOLERANCES

- A. Maximum Variation From Plumb: 1/4 inch (6 mm) per story, non-cumulative.
- B. Maximum Offset From True Alignment: 1/4 inch (6 mm).
- C. Maximum Out-of-Position: 1/4 inch (6 mm).

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 055100 METAL STAIRS

PART 1 GENERAL

1.01 RELATED REQUIREMENTS

A. Section 033000 - Cast-in-Place Concrete: Concrete fill in stair pans; mesh reinforcement for landings.

1.02 REFERENCE STANDARDS

- A. AISC 201 AISC Certification Program for Structural Steel Fabricators, Standard for Steel Building Structures; 2006.
- B. ASTM A36/A36M Standard Specification for Carbon Structural Steel; 2019.
- C. ASTM A153/A153M Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware; 2023.
- D. ASTM A786/A786M Standard Specification for Hot-Rolled Carbon, Low-Alloy, High-Strength Low-Alloy, and Alloy Steel Floor Plates; 2015 (Reapproved 2021).
- E. ASTM F3125/F3125M Standard Specification for High Strength Structural Bolts and Assemblies, Steel and Alloy Steel, Heat Treated, Inch Dimensions 120 ksi and 150 ksi Minimum Tensile Strength, and Metric Dimensions 830 MPa and 1040 MPa Minimum Tensile Strength; 2023.
- F. AWS A2.4 Standard Symbols for Welding, Brazing, and Nondestructive Examination; 2020.
- G. AWS B2.1/B2.1M Specification for Welding Procedure and Performance Qualification; 2021, with Errata (2023).
- H. AWS D1.1/D1.1M Structural Welding Code Steel; 2020, with Errata (2023).
- I. IAS AC172 Accreditation Criteria for Fabricator Inspection Programs for Structural Steel AC172; 2019.
- J. SSPC-Paint 15 Steel Joist Shop Primer/Metal Building Primer; 2004.
- K. SSPC-SP 2 Hand Tool Cleaning; 2024.

1.03 SUBMITTALS

- A. See Section 013000 Administrative Requirements, for submittal procedures.
- B. Shop Drawings: Indicate profiles, sizes, connection attachments, reinforcing, anchorage, size and type of fasteners, and accessories signed and sealed by a Structural Engineer licensed in the state in which The Work is being performed.
 - 1. Indicate welded connections using standard AWS A2.4 welding symbols. Indicate net weld lengths.
- C. Welders' Qualification Statement: Welders' certificates in accordance with AWS B2.1/B2.1M and dated no more than 12 months before start of scheduled welding work.
- D. Designer's Qualification Statement.

1.04 QUALITY ASSURANCE

- A. Structural Designer Qualifications: Professional Structural Engineer experienced in design of this work and licensed in the State in which the Project is located, or personnel under direct supervision of such an engineer.
- B. Fabricator Qualifications:
 - 1. A qualified steel fabricator that is certified by the American Institute for Steel Construction (AISC) under AISC 201.
 - 2. A qualified steel fabricator that is accredited by the International Accreditation Service (IAS) Fabricator Inspection Program for Structural Steel in accordance with IAS AC172.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

PART 2 PRODUCTS

2.01 METAL STAIRS - GENERAL

- A. Metal Stairs: Provide stairs of the design specified, complete with landing platforms, vertical and horizontal supports, railings, and guards, fabricated accurately for anchorage to each other and to building structure.
 - 1. Regulatory Requirements: Provide stairs and railings that comply with most stringent requirements of local, state, and federal regulations; where requirements of Contract Documents exceed those of regulations, comply with Contract Documents.
 - 2. Dimensions: As indicated on drawings.
 - 3. Shop assemble components; disassemble into largest practical sections suitable for transport and access to site.
 - 4. No sharp or rough areas on exposed travel surfaces and surfaces accessible to touch.
 - 5. Separate dissimilar metals using paint or permanent tape.
- B. Metal Jointing and Finish Quality Levels:
 - 1. Service: Exposed joints tight with face surfaces aligned; underside of stair not covered by soffit is not considered exposed to view.
 - a. Welded Joints: Welded on back side wherever possible.
 - b. Welds Exposed to View: Ground smooth; not required to be flush.
 - c. Bolts Exposed to View: Countersunk flat or oval head bolts; no exposed nuts or screw threads.
 - d. Metal Surfaces to be Painted: Sanded smooth, suitable for satin or matte finish.
- C. Fasteners: Same material or compatible with materials being fastened; type consistent with design and specified quality level.
- D. Anchors and Related Components: Same material and finish as item to be anchored, except where specifically indicated otherwise; provide all anchors and fasteners required.

2.02 METAL STAIRS WITH METAL TREADS

- A. Jointing and Finish Quality Level: Service, as defined above.
- B. Risers: Closed.
- C. Treads: Checkered steel plate.
 - 1. Tread Thickness: 1/4 inch (6 mm), minimum.
 - 2. Anchorage to Stringers: Welded or bolted to carrier angles welded or bolted to stringers.
- D. Risers: Steel sheet.
 - 1. Riser Thickness: As required by design; 14 gauge, 0.075 inch (1.9 mm) minimum.
 - 2. Riser/Nosing Profile: Sloped riser with rounded nosing of minimum radius.
- E. Stringers: Rolled steel channels.
 - 1. Stringer Depth: 10 inches (250 mm).
 - 2. End Closure: Sheet steel of same thickness as risers welded across ends.
- F. Railings: Steel pipe railings.
- G. Finish: Shop- or factory-prime painted.

2.03 HANDRAILS AND GUARDS

A. Wall-Mounted Rails: See Section 055213.

2.04 MATERIALS

- A. Steel Sections: ASTM A36/A36M.
- B. Checkered Plate: ASTM A786/A786M, rolled steel floor plate; manufacturer's standard pattern.
- C. Concrete Fill: See Section 033000. (STRUCTURAL DRAWINGS)

LAHC – WORKFORCE	
EDUCATION RESOURCE AND	
DEVELOPMENT CENTER	

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

D. Concrete Reinforcement: Mesh type as detailed, galvanized.

2.05 ACCESSORIES

- A. Steel Bolts, Nuts, and Washers: ASTM F3125/F3125M, Type 1, and galvanized to ASTM A153/A153M where connecting galvanized components.
- B. Welding Materials: AWS D1.1/D1.1M; type required for materials being welded.
- C. Shop and Touch-Up Primer: SSPC-Paint 15, and comply with VOC limitations of authorities having jurisdiction.

2.06 SHOP FINISHING

- A. Clean surfaces of rust, scale, grease, and foreign matter prior to finishing.
- B. Do not prime surfaces in direct contact with concrete or where field welding is required.
- C. Prime Painting: Use specified shop- and touch-up primer.
 - 1. Preparation of Steel: In accordance with SSPC-SP 2 Hand Tool Cleaning.
 - 2. Number of Coats: One.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that field conditions are acceptable and are ready to receive work.

3.02 PREPARATION

A. When field welding is required, clean and strip primed steel items to bare metal.

3.03 INSTALLATION

- A. Install components plumb and level, accurately fitted, free from distortion or defects.
- B. Allow for erection loads, and for sufficient temporary bracing to maintain true alignment until completion of erection and installation of permanent attachments.
- C. Provide welded field joints where specifically indicated on drawings. Perform field welding in accordance with AWS D1.1/D1.1M.
- D. Other field joints may be either welded or bolted provided the result complies with the limitations specified for jointing quality levels.
- E. Obtain approval prior to site cutting or creating adjustments not scheduled.
- F. After erection, prime welds, abrasions, and surfaces not shop primed or galvanized, except surfaces to be in contact with concrete.

FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 055133 METAL LADDERS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Shop-fabricated metal ladders.
- B. Prefabricated ladders.

1.02 REFERENCE STANDARDS

- A. AAMA 611 Specification for Anodized Architectural Aluminum; 2024.
- B. ANSI A14.3 American National Standard for Ladders -- Fixed -- Safety Requirements; 2008 (Reaffirmed 2018).
- C. ASTM A123/A123M Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products; 2017.
- D. ASTM A36/A36M Standard Specification for Carbon Structural Steel; 2019.
- E. ASTM A53/A53M Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless; 2022.
- F. ASTM A283/A283M Standard Specification for Low and Intermediate Tensile Strength Carbon Steel Plates; 2018.
- G. ASTM A307 Standard Specification for Carbon Steel Bolts, Studs, and Threaded Rod 60 000 PSI Tensile Strength; 2021.
- H. ASTM A501/A501M Standard Specification for Hot-Formed Welded and Seamless Carbon Steel Structural Tubing; 2021.
- I. ASTM B210/B210M Standard Specification for Aluminum and Aluminum-Alloy Drawn Seamless Tubes; 2019a.
- J. ASTM B211/B211M Standard Specification for Aluminum and Aluminum-Alloy Rolled or Cold Finished Bar, Rod, and Wire; 2019.
- K. AWS A2.4 Standard Symbols for Welding, Brazing, and Nondestructive Examination; 2020.
- L. AWS B2.1/B2.1M Specification for Welding Procedure and Performance Qualification; 2021, with Errata (2023).
- M. AWS D1.1/D1.1M Structural Welding Code Steel; 2020, with Errata (2023).
- N. AWS D1.2/D1.2M Structural Welding Code Aluminum; 2014, with Errata (2020).
- O. SSPC-Paint 15 Steel Joist Shop Primer/Metal Building Primer; 2004.
- P. SSPC-Paint 20 Zinc-Rich Coating (Type I Inorganic, and Type II Organic); 2019.
- Q. SSPC-SP 2 Hand Tool Cleaning; 2024.

1.03 SUBMITTALS

- A. See Section 013000 Administrative Requirements, for submittal procedures.
- B. Shop Drawings:
 - 1. Indicate profiles, sizes, connection attachments, reinforcing, anchorage, size and type of fasteners, and accessories. Include erection drawings, elevations, and details where applicable, signed and sealed by a Structural Engineer licensed in the state in which The Work is being performed.
 - 2. Indicate welded connections using standard AWS A2.4 welding symbols. Indicate net weld lengths.
- C. Welders' Qualification Statement: Welders' certificates in accordance with AWS B2.1/B2.1M and dated no more than 12 months before start of scheduled welding work.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

D. Designer's Qualification Statement.

1.04 QUALITY ASSURANCE

- A. Design under direct supervision of a Professional Structural Engineer experienced in design of this work and licensed in the State in which the Project is located.
- B. Welder Qualifications: Welding processes and welding operators qualified in accordance with AWS D1.1/D1.1M and AWS D1.2/D1.2M and dated no more than 12 months before start of scheduled welding work.

PART 2 PRODUCTS

2.01 MATERIALS - STEEL

- A. Steel Sections: ASTM A36/A36M.
- B. Steel Tubing: ASTM A501/A501M hot-formed structural tubing.
- C. Plates: ASTM A283/A283M.
- D. Pipe: ASTM A53/A53M, Grade B Schedule 40, black finish.
- E. Mechanical Fasteners: Same material or compatible with materials being fastened; type consistent with design and specified quality level.
- F. Bolts, Nuts, and Washers: ASTM A307, plain.
- G. Welding Materials: AWS D1.1/D1.1M; type required for materials being welded.
- H. Shop and Touch-Up Primer: SSPC-Paint 15, complying with VOC limitations of authorities having jurisdiction.
- I. Touch-Up Primer for Galvanized Surfaces: SSPC-Paint 20, Type I Inorganic, complying with VOC limitations of authorities having jurisdiction.

2.02 MATERIALS - ALUMINUM

- A. Extruded Aluminum: ASTM B211/B211M, 6063 alloy, T6 temper.
- B. Aluminum-Alloy Drawn Seamless Tubes: ASTM B210/B210M, 6063 alloy, T6 temper.
- C. Aluminum-Alloy Bars: ASTM B211/B211M, 6061 alloy, T6 temper.
- D. Bolts, Nuts, and Washers: Stainless steel.

2.03 FABRICATION

- A. Fit and shop assemble items in largest practical sections, for delivery to site.
- B. Fabricate items with joints tightly fitted and secured.
- C. Grind exposed joints flush and smooth with adjacent finish surface. Make exposed joints butt tight, flush, and hairline. Ease exposed edges to small uniform radius.
- D. Supply components required for anchorage of fabrications. Fabricate anchors and related components of same material and finish as fabrication, except where specifically noted otherwise.

2.04 FABRICATED LADDERS

- A. Ladders: Steel; in compliance with ANSI A14.3; with mounting brackets and attachments; prime paint finish.
 - 1. Side Rails: 3/8 by 2 inches (9 by 50 mm) members spaced at 20 inches (500 mm).
 - 2. Rungs: One inch (25 mm) diameter solid round bar spaced 12 inches (300 mm) on center.
 - 3. Space rungs 7 inches (175 mm) from wall surface.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

2.05 PREFABRICATED LADDERS

- A. Prefabricated Ladder: Welded metal unit complying with ANSI A14.3; factory fabricated to greatest degree practical and in the largest components possible.
 - 1. Components: Manufacturer's standard rails, rungs, treads, handrails. returns, platforms and safety devices complying with the requirements of the MATERIALS article of this section.
 - 2. Materials: Aluminum; ASTM B211/B211M 6063 alloy, T52 temper.
 - 3. Finish: Mill finish aluminum.
 - 4. Manufacturers:
 - a. Industrial Ladder & Scaffolding, Inc.: www.anyladder.com/#sle.
 - b. O'Keeffe's Inc; Model 500: www.okeeffes.com/#sle.
 - c. Precision Ladders, LLC; Fixed Alumnium Wall Ladder:
 - www.precisionladders.com/#sle.
 - d. O'Keeffe's, Inc..
 - e. Substitutions: See Section 016000 Product Requirements.

2.06 FINISHES - STEEL

- A. Prime paint steel items.
- B. Prepare surfaces to be primed in accordance with SSPC-SP2.
- C. Clean surfaces of rust, scale, grease, and foreign matter prior to finishing.
- D. Prime Painting: One coat.
- E. Galvanizing of Structural Steel Members: Galvanize after fabrication to ASTM A123/A123M requirements. Provide minimum 1.7 oz/sq ft galvanized coating. (Provide minimum 530 g/sq m galvanized coating.)

2.07 FINISHES - ALUMINUM

A. Class I Natural Anodized Finish: AAMA 611 AA-M12C22A41 Clear anodic coating not less than 0.7 mils (0.018 mm) thick.

2.08 FABRICATION TOLERANCES

- A. Squareness: 1/8 inch (3 mm) maximum difference in diagonal measurements.
- B. Maximum Offset Between Faces: 1/16 inch (1.5 mm).
- C. Maximum Misalignment of Adjacent Members: 1/16 inch (1.5 mm).
- D. Maximum Bow: 1/8 inch (3 mm) in 48 inches (1.2 m).
- E. Maximum Deviation From Plane: 1/16 inch (1.5 mm) in 48 inches (1.2 m).

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that field conditions are acceptable and are ready to receive work.

3.02 PREPARATION

- A. Clean and strip primed steel items to bare metal where site welding is required.
- B. Supply setting templates to the appropriate entities for steel items required to be cast into concrete or embedded in masonry.

3.03 INSTALLATION

- A. Install items plumb and level, accurately fitted, free from distortion or defects.
- B. Provide for erection loads, and for sufficient temporary bracing to maintain true alignment until completion of erection and installation of permanent attachments.
- C. Obtain approval prior to site cutting or making adjustments not scheduled.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

3.04 TOLERANCES

- A. Maximum Variation From Plumb: 1/4 inch (6 mm) per story, non-cumulative.
- B. Maximum Offset From True Alignment: 1/4 inch (6 mm).
- C. Maximum Out-of-Position: 1/4 inch (6 mm).

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 055213 PIPE AND TUBE RAILINGS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Wall mounted handrails.
- B. Stair railings and guardrails.
- C. Free-standing railings at steps.

1.02 RELATED REQUIREMENTS

- A. Section 033000 Cast-in-Place Concrete: Placement of anchors in concrete.
- B. Section 042000 Unit Masonry: Placement of anchors in masonry.
- C. Section 092116 Gypsum Board Assemblies: Placement of backing plates in stud wall construction.
- D. Section 099113 Exterior Painting: Paint finish.
- E. Section 099123 Interior Painting: Paint finish.

1.03 REFERENCE STANDARDS

- A. AISC 201 AISC Certification Program for Structural Steel Fabricators, Standard for Steel Building Structures; 2006.
- B. ASTM A123/A123M Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products; 2017.
- C. ASTM A500/A500M Standard Specification for Cold-Formed Welded and Seamless Carbon Steel Structural Tubing in Rounds and Shapes; 2023.
- D. ASTM E935 Standard Test Methods for Performance of Permanent Metal Railing Systems and Rails for Buildings; 2021.
- E. AWS D1.1/D1.1M Structural Welding Code Steel; 2020, with Errata (2023).
- F. AWS D1.6/D1.6M Structural Welding Code Stainless Steel; 2017, with Amendment (2021).
- G. AWS C3.4M/C3.4 Specification for Torch Brazing; 2016.
- H. AWS C3.5M/C3.5 Specification for Induction Brazing; 2016, with Amendment (2017).
- I. AWS C3.9M/C3.9 Specification for Resistance Brazing; 2020.
- J. IAS AC172 Accreditation Criteria for Fabricator Inspection Programs for Structural Steel AC172; 2019.
- K. SSPC-Paint 15 Steel Joist Shop Primer/Metal Building Primer; 2004.

1.04 SUBMITTALS

- A. See Section 013000 Administrative Requirements, for submittal procedures.
- B. Shop Drawings: Indicate profiles, sizes, connection attachments, anchorage, size and type of fasteners, and accessories signed and sealed by a Structural Engineer licensed in the state in which The Work is being performed.
- C. Samples: Submit two, 4 inch (____ mm) long samples of handrail. Submit two samples of elbow, wall bracket, and end stop.
- D. Designer's Qualification Statement.
- E. Fabricator's Qualification Statement.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

1.05 QUALITY ASSURANCE

- A. Structural Designer Qualifications: Professional Structural Engineer experienced in design of this work and licensed in the State in which the Project is located, or personnel under direct supervision of such an engineer.
- B. Fabricator Qualifications:
 - 1. A qualified steel fabricator that is certified by the American Institute for Steel Construction (AISC) under AISC 201.
 - 2. A qualified steel fabricator that is accredited by the International Accreditation Service (IAS) Fabricator Inspection Program for Structural Steel in accordance with IAS AC172.

PART 2 PRODUCTS

2.01 RAILINGS - GENERAL REQUIREMENTS

- A. Design, fabricate, and test railing assemblies in accordance with the most stringent requirements of applicable local code.
- B. Distributed Loads: Design railing assembly, wall rails, and attachments to resist distributed force of 75 pounds per linear foot (1095 N/m) applied to the top of the assembly and in any direction, without damage or permanent set. Test in accordance with ASTM E935
- C. Concentrated Loads: Design railing assembly, wall rails, and attachments to resist a concentrated force of 200 pounds (890 N) applied at any point on the top of the assembly and in any direction, without damage or permanent set. Test in accordance with ASTM E935
- D. Allow for expansion and contraction of members and building movement without damage to connections or members.
- E. Dimensions: See drawings for configurations and heights.
- F. Provide anchors and other components as required to attach to structure, made of same materials as railing components unless otherwise indicated; where exposed fasteners are unavoidable provide flush countersunk fasteners.
 - 1. For anchorage to concrete, provide inserts to be cast into concrete, for bolting anchors.
 - 2. For anchorage to masonry, provide brackets to be embedded in masonry, for bolting anchors.
 - 3. For anchorage to stud walls, provide backing plates, for bolting anchors.
- G. Provide slip-on non-weld mechanical fittings to join lengths, seal open ends, and conceal exposed mounting bolts and nuts, including but not limited to elbows, T-shapes, splice connectors, flanges, escutcheons, and wall brackets.
- H. Welded and Brazed Joints: Make visible joints butt tight, flush, and hairline; use methods that avoid discoloration and damage of finish; grind smooth, polish, and restore to required finish.
 - 1. Ease exposed edges to a small uniform radius.
 - 2. Welded Joints:
 - a. Carbon Steel: Perform welding in accordance with AWS D1.1/D1.1M.
 - b. Stainless Steel: Perform welding in accordance with AWS D1.6/D1.6M.
 - 3. Brass/Bronze Brazed Joints:
 - a. Perform torch brazing in accordance with AWS C3.4M/C3.4.
 - b. Perform induction brazing in accordance with AWS C3.5M/C 3.5.
 - c. Perform resistance brazing in accordance with AWS C3.9M/C3.9.

2.02 ALUMINUM MATERIALS

2.03 STEEL RAILING SYSTEM

- A. Steel Tube: ASTM A500/A500M Grade B cold-formed structural tubing.
- B. Non-Weld Mechanical Fittings: Slip-on, galvanized malleable iron castings, for Schedule 40 pipe, with flush setscrews for tightening by standard hex wrench, no bolts or screw fasteners.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- C. Welding Fittings: Factory- or shop-welded from matching pipe or tube; seams continuously welded; joints and seams ground smooth.
- D. Exposed Fasteners: No exposed bolts or screws.
- E. Galvanizing: In accordance with requirements of ASTM A123/A123M.
- F. Shop and Touch-Up Primer: SSPC-Paint 15, complying with VOC limitations of authorities having jurisdiction.

2.04 FABRICATION

- A. Accurately form components to suit specific project conditions and for proper connection to building structure.
- B. Fit and shop assemble components in largest practical sizes for delivery to site.
- C. Fabricate components with joints tightly fitted and secured. Provide spigots and sleeves to accommodate site assembly and installation.
- D. Welded Joints:
 - 1. Exterior Components: Continuously seal joined pieces by intermittent welds and plastic filler. Drill condensate drainage holes at bottom of members at locations that will not encourage water intrusion.
 - 2. Interior Components: Continuously seal joined pieces by intermittent welds and plastic filler.
 - 3. Grind exposed joints flush and smooth with adjacent finish surface. Make exposed joints butt tight, flush, and hairline. Ease exposed edges to small uniform radius.

PART 3 EXECUTION

3.01 INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Install components plumb and level, accurately fitted, free from distortion or defects, with tight joints.
- C. Anchor railings securely to structure.
- D. Conceal anchor bolts and screws whenever possible. Where not concealed, use flush countersunk fastenings.

FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 061000 ROUGH CARPENTRY

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Preservative treated wood materials.
- B. Fire retardant treated wood materials.

1.02 REFERENCE STANDARDS

- A. ASTM A153/A153M Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware; 2023.
- B. ASTM C1002 Standard Specification for Steel Self-Piercing Tapping Screws for Application of Gypsum Panel Products or Metal Plaster Bases to Wood Studs or Steel Studs; 2022.
- C. ASTM D2898 Standard Practice for Accelerated Weathering of Fire-Retardant-Treated Wood for Fire Testing; 2010 (Reapproved 2017).
- D. ASTM E84 Standard Test Method for Surface Burning Characteristics of Building Materials; 2023d.
- E. AWPA U1 Use Category System: User Specification for Treated Wood; 2024.
- F. PS 20 American Softwood Lumber Standard; 2025.

1.03 SUBMITTALS

A. See Section 013000 - Administrative Requirements for submittal procedures.

PART 2 PRODUCTS

2.01 GENERAL REQUIREMENTS

- A. Dimension Lumber: Comply with PS 20 and requirements of specified grading agencies.
 - 1. If no species is specified, provide species graded by the agency specified; if no grading agency is specified, provide lumber graded by grading agency meeting the specified requirements.
 - 2. Grading Agency: Grading agency whose rules are approved by the Board of Review, American Lumber Standard Committee at www.alsc.org, and who provides grading service for the species and grade specified; provide lumber stamped with grade mark unless otherwise indicated.
 - 3. Lumber of other species or grades is acceptable provided structural and appearance characteristics are equivalent to or better than products specified.
- B. Provide wood harvested within a 500 mile (805 km) radius of the project site.

2.02 DIMENSION LUMBER FOR CONCEALED APPLICATIONS

- A. Sizes: Nominal sizes as indicated on drawings, S4S.
- B. Moisture Content: S-dry or MC19.

2.03 ACCESSORIES

- A. Fasteners and Anchors:
 - 1. Metal and Finish: Hot-dipped galvanized steel complying with ASTM A153/A153M for high humidity and preservative-treated wood locations, unfinished steel elsewhere.
 - 2. Gypsum Board Screws: ASTM C1002; Type W, bugle head, self-piercing, tapping screws; length to penetrate wood members 5/8 inch (15.9 mm) minimum.

2.04 FACTORY WOOD TREATMENT

A. Treated Lumber and Plywood: Comply with requirements of AWPA U1 - Use Category System for wood treatments determined by use categories, expected service conditions, and specific applications.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 1. Fire-Retardant Treated Wood: Mark each piece of wood with producer's stamp indicating compliance with specified requirements.
- 2. Preservative-Treated Wood: Provide lumber and plywood marked or stamped by an ALSC-accredited testing agency, certifying level and type of treatment in accordance with AWPA standards.
- B. Fire Retardant Treatment:
 - 1. Products:
 - a. Lonza Group: www.wolmanizedwood.com/#sle.
 - b. Hoover Treated Wood Products, Inc: www.frtw.com/#sle.
 - c. T2EARTH, LLC; OnWood: www.t2earth.com/#sle.
 - d. UFP Industries; ProWood FR Lumber: www.ufpi.com/#sle.
 - e. Substitutions: See Section 016000 Product Requirements.
 - Exterior Type: AWPA U1, Category UCFB, Commodity Specification H, chemically treated and pressure impregnated; capable of providing a maximum flame spread index of 25 when tested in accordance with ASTM E84, with no evidence of significant combustion when test is extended for an additional 20 minutes both before and after accelerated weathering test performed in accordance with ASTM D2898.
 - a. Kiln dry wood after treatment to a maximum moisture content of 19 percent for lumber and 15 percent for plywood.
 - b. Treat exterior rough carpentry items.
 - c. Do not use treated wood in direct contact with the ground.
 - 3. Interior Type A: AWPA U1, Use Category UCFA, Commodity Specification H, low temperature (low hygroscopic) type, chemically treated and pressure impregnated; capable of providing a maximum flame spread index of 25 when tested in accordance with ASTM E84, with no evidence of significant combustion when test is extended for an additional 20 minutes.
 - a. Kiln dry wood after treatment to a maximum moisture content of 19 percent for lumber and 15 percent for plywood.
 - b. Treat rough carpentry items as indicated .
 - c. Do not use treated wood in applications exposed to weather or where the wood may become wet.
- C. Preservative Treatment:
 - 1. Products:
 - a. Lonza Group: www.wolmanizedwood.com/#sle.
 - b. Koppers Performance Chemicals, Inc:
 - www.koppersperformancechemicals.com/#sle.
 - c. Viance, LLC; Preserve ACQ: www.treatedwood.com/#sle.
 - d. Substitutions: See Section 016000 Product Requirements.
 - 2. Preservative Pressure Treatment of Lumber Above Grade: AWPA U1, Use Category UC3B, Commodity Specification A using waterborne preservative.
 - a. Kiln dry lumber after treatment to maximum moisture content of 19 percent.
 - b. Treat lumber in contact with roofing, flashing, or waterproofing.
 - c. Treat lumber in contact with masonry or concrete.
 - d. Treat lumber less than 18 inches (450 mm) above grade.
 - 3. Preservative Pressure Treatment of Plywood Above Grade: AWPA U1, Use Category UC2 and UC3B, Commodity Specification F using waterborne preservative.
 - a. Kiln dry plywood after treatment to maximum moisture content of 19 percent.
 - b. Treat plywood in contact with roofing, flashing, or waterproofing.
 - c. Treat plywood in contact with masonry or concrete.
 - d. Treat plywood less than 18 inches (450 mm) above grade.
50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

PART 3 EXECUTION

3.01 PREPARATION

3.02 INSTALLATION - GENERAL

- A. Select material sizes to minimize waste.
- B. Reuse scrap to the greatest extent possible; clearly separate scrap for use on site as accessory components, including: shims, bracing, and blocking.
- C. Where treated wood is used on interior, provide temporary ventilation during and immediately after installation sufficient to remove indoor air contaminants.

3.03 BLOCKING, NAILERS, AND SUPPORTS

- A. Provide framing and blocking members as indicated or as required to support finishes, fixtures, specialty items, and trim.
- B. In metal stud walls, provide continuous blocking around door and window openings for anchorage of frames, securely attached to stud framing.
- C. In walls, provide blocking attached to studs as backing and support for wall-mounted items, unless item can be securely fastened to two or more studs or other method of support is explicitly indicated.
- D. Where ceiling-mounting is indicated, provide blocking and supplementary supports above ceiling, unless other method of support is explicitly indicated.
- E. Provide the following specific nonstructural framing and blocking:
 - 1. Cabinets and shelf supports.
 - 2. Wall brackets.
 - 3. Handrails.
 - 4. Grab bars.
 - 5. Towel and bath accessories.
 - 6. Wall-mounted door stops.
 - 7. Chalkboards and marker boards.
 - 8. Wall paneling and trim.
 - 9. Joints of rigid wall coverings that occur between studs.

3.04 ROOF-RELATED CARPENTRY

- A. Coordinate installation of roofing carpentry with deck construction, framing of roof openings, and roofing assembly installation.
- B. Provide wood curb at each roof opening except where prefabricated curbs are specified and where specifically indicated otherwise; form corners by alternating lapping side members.

3.05 TOLERANCES

- A. Framing Members: 1/4 inch (6 mm) from true position, maximum.
- B. Variation from Plane, Other than Floors: 1/4 inch in 10 feet (2 mm/m) maximum, and 1/4 inch in 30 feet (7 mm in 10 m) maximum.

3.06 FIELD QUALITY CONTROL

- A. See Section 014000 Quality Requirements for additional requirements.
- B. Coordination of ABAA Tests and Inspections:
 - 1. Provide testing and inspection required by ABAA QAP.
 - 2. Notify in ABAA writing of schedule for air barrier work. Allow adequate time for testing and inspection.
 - 3. Cooperate with ABAA testing agency.
 - 4. Allow access to air barrier work areas and staging.
 - 5. Do not cover air barrier work until tested, inspected, and accepted.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

3.07 CLEANING

- A. Waste Disposal: See Section 017419 Construction Waste Management and Disposal.
 - 1. Comply with applicable regulations.
 - 2. Do not burn scrap on project site.
 - 3. Do not burn scraps that have been pressure treated.
 - 4. Do not send materials treated with pentachlorophenol, CCA, or ACA to co-generation facilities or "waste-to-energy" facilities.
- B. Do not leave wood, shavings, sawdust, etc. on the ground or buried in fill.
- C. Prevent sawdust and wood shavings from entering the storm drainage system.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 061600 SHEATHING

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Sheathing.

1.02 RELATED REQUIREMENTS

A. Section 072700 - Air Barriers.

1.03 REFERENCE STANDARDS

- A. ASTM A153/A153M Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware; 2023.
- B. ASTM C1177/C1177M Standard Specification for Glass Mat Gypsum Substrate for Use as Sheathing; 2017.
- C. ASTM D3273 Standard Test Method for Resistance to Growth of Mold on the Surface of Interior Coatings in an Environmental Chamber; 2021.

1.04 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Product Data: Provide technical data on sheathing and application instructions.
- C. Specimen warranty.

1.05 QUALITY ASSURANCE

- A. Use materials evaluated by Air Barrier Association of America (ABAA).
- B. Manufacturer Qualifications: Company specializing in manufacturing products specified in this section, with minimum three years of documented experience.
- C. Installer Qualifications: Company specializing in performing work of the type specified and with minimum three years of documented experience and approved by manufacturer.

1.06 DELIVERY, STORAGE, AND HANDLING

- A. See Section 017419 Construction Waste Management and Disposal for packaging waste requirements.
- B. Store wood products to protect against moisture. Support stacked products to prevent deformation and to allow air circulation.

1.07 WARRANTY

- A. See Section 017800 Closeout Submittals for additional warranty requirements.
- B. Manufacturer Warranty: Provide 2-year manufacturer warranty for material defects and fabrication. Complete forms in Owner's name and register with manufacturer.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. USG Corporation: www.usg.com/#sle.
- B. Georgia-Pacific Building Products; .
- C. National Gypsum Co.;.
- D. Substitutions: See Section 016000 Product Requirements.

2.02 SHEATHING

- A. Glass-mat-faced gypsum wall sheathing, comply with ASTM C1177/C1177M.
 - 1. Thickness: 5/8 inch (15.9 mm).

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 2. Edges: Square.
- 3. Mold Resistance: Score of 10, when tested in accordance with ASTM D3273.
- 4. Products:
 - a. USG Corporation; Securock Brand Glass-Mat Sheathing Regular.
 - b. Georgia-Pacific Building Products; DensGlass Sheathing.
 - c. National Gypsum Co.; Gold Bond eXP Sheathing. .

2.03 ACCESSORIES

- A. Fasteners and Anchors:
 - 1. Metal and Finish: Hot-dip galvanized steel complying with ASTM A153/A153M for high humidity and preservative-treated wood locations, unfinished steel elsewhere.
 - 2. Anchors: Toggle bolt type for anchorage to hollow masonry.
- B. Air Barrier: See Section 072700.

PART 3 EXECUTION

3.01 PREPARATION

- A. Coordinate installation of roof and floor deck construction, framing of openings, and other assembly installation.
- B. Coordinate installation of rough carpentry members specified in other sections.

3.02 INSTALLATION

- A. Select material sizes to minimize waste.
- B. Reuse and clearly separate scrap for use on-site as accessory components, including shims, bracing, and blocking.
- C. Wall Sheathing: Secure with long dimension perpendicular to wall studs, with ends over firm bearing and staggered, using screws.

3.03 TOLERANCES

- A. Surface Flatness of Floor: 1/8 inch (1 mm) in 10 feet (3 m), maximum, and 1/4 inch (7 mm) in 30 feet (9.1 m), maximum.
- B. Variation from Plane; Surfaces Other Than Floors: 1/4 inch (2 mm) in 10 feet (3 m), maximum, and 1/4 inch (7 mm) in 30 feet (9.1 m), maximum.

3.04 FIELD QUALITY CONTROL

A. See Section 014000 - Quality Requirements for additional requirements.

3.05 CLEANING

- A. Waste Disposal: See Section 017419 Construction Waste Management and Disposal.
 - 1. Comply with applicable regulations.
 - 2. Do not burn scrap on project site.
 - 3. Do not burn pressure treated scraps.
- B. Clean material debris, shavings, and sawdust prior to Substantial Completion of project.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 064100 ARCHITECTURAL WOOD CASEWORK

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Hardware.

1.02 RELATED REQUIREMENTS

A. Section 123600 - Countertops.

1.03 REFERENCE STANDARDS

- A. ANSI A208.1 American National Standard for Particleboard; 2022.
- B. ANSI A208.2 Medium Density Fiberboard (MDF) for Interior Applications; 2022.
- C. AWI (QCP) Quality Certification Program; Current Edition.
- D. AWI/AWMAC/WI (AWS) Architectural Woodwork Standards, 2nd Edition; 2014, with Errata (2016).
- E. AWMAC/WI (NAAWS) North American Architectural Woodwork Standards; 2021, with Errata.
- F. BHMA A156.9 Cabinet Hardware; 2020.
- G. NEMA LD 3 High-Pressure Decorative Laminates; 2005.

1.04 ADMINISTRATIVE REQUIREMENTS

A. Preinstallation Meeting: Convene a preinstallation meeting not less than one week before starting work of this section; require attendance by all affected installers.

1.05 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Shop Drawings: Indicate materials, component profiles, fastening methods, jointing details, and accessories.
 - 1. Provide information as required by AWI/AWMAC/WI (AWS).
- C. Product Data: Provide data for hardware accessories.
- D. Samples: Submit actual samples of architectural cabinet construction, minimum 12 inches (300 mm) square, illustrating proposed cabinet, countertop, and shelf unit substrate and finish.
- E. Samples: Submit actual sample items of proposed pulls, hinges, shelf standards, and locksets, demonstrating hardware design, quality, and finish.
- F. Certificate: Submit labels and certificates required by quality assurance and quality control programs.

1.06 QUALITY ASSURANCE

- A. Fabricator Qualifications: Company specializing in fabricating the products specified in this section with minimum five years of documented experience.
 - 1. Accredited participant in the specified certification program prior to the commencement of fabrication and throughout the duration of the project.
- B. Quality Certification:
 - 1. Comply with AWI (QCP) woodwork association quality certification service/program in accordance with requirements for work specified in this section: www.awiqcp.org/#sle.
 - 2. Provide labels or certificates indicating that the installed work complies with AWI/AWMAC/WI (AWS) requirements for grade or grades specified.
 - 3. Provide designated labels on shop drawings as required by certification program.
 - 4. Provide designated labels on installed products as required by certification program.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- 5. Submit certifications upon completion of installation that verifies this work is in compliance with specified requirements.
- 6. Replace, repair, or rework all work for which certification is refused.

1.07 MOCK-UPS

- A. Provide mock-up of typical base cabinet, wall cabinet, and countertop, including hardware, finishes, and plumbing accessories.
- B. Locate where directed.
- C. Mock-up may remain as part of the work.

1.08 DELIVERY, STORAGE, AND HANDLING

A. Protect units from moisture damage.

1.09 FIELD CONDITIONS

A. During and after installation of custom cabinets, maintain temperature and humidity conditions in building spaces at same levels planned for occupancy.

PART 2 PRODUCTS

2.01 FABRICATORS

- A. Trend Millwork.
- B. Strata Design.
- C. Millwork, Inc. .
- D. Substitutions: See Section 016000 Product Requirements.

2.02 CABINETS

- A. Quality Standard: Custom Grade, in accordance with AWI/AWMAC/WI (AWS), unless noted otherwise.
- B. Plastic Laminate Faced Cabinets: Custom grade.
- C. Cabinets at Kitchen:
 - 1. Finish Exposed Exterior Surfaces: Decorative laminate.
 - 2. Finish Exposed Interior Surfaces: Decorative laminate.
 - 3. Finish Semi-Exposed Surfaces: Decorative laminate
 - 4. Finish Concealed Surfaces: Manufacturer's option.
 - 5. Door and Drawer Front Edge Profiles: square edge with inset band.
 - 6. Casework Construction Type: Manufacturer's option.
 - 7. Cabinet Design Series: As indicated on drawings.
 - 8. Adjustable Shelf Loading: 50 psf (24.4 gm/sq cm).
 - 9. Cabinet Style: Reveal overlay.

2.03 WOOD-BASED COMPONENTS

- A. Wood fabricated from old growth timber is not permitted.
- B. Provide wood harvested within a 500 mile (805 km) radius of the project site.

2.04 PANEL CORE MATERIALS

- A. Particleboard: Composite panel composed of cellulosic particles, additives, and bonding system; comply with ANSI A208.1.
 - 1. Grade: M-2; moisture resistance: MR10.
- B. Medium Density Fiberboard (MDF): Composite panel composed of cellulosic fibers, additives, and bonding system; cured under heat and pressure; comply with ANSI A208.2.

2.05 LAMINATE MATERIALS

A. Manufacturers:

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 1. Arborite: www.arborite.com/#sle.
- 2. Formica Corporation: www.formica.com/#sle.
- 3. Panolam Industries International, Inc: www.panolam.com/#sle.
- 4. Wilsonart LLC: www.wilsonart.com/#sle.
- B. High Pressure Decorative Laminate (HPDL): NEMA LD 3, types as recommended for specific applications.
- C. Provide specific types as indicated.
 - 1. Vertical Surfaces: VGS, 0.028 inch (0.71 mm) nominal thickness, finish as indicated.

2.06 COUNTERTOPS

A. Countertops: See Section 123600.

2.07 ACCESSORIES

- A. Adhesive: Type recommended by fabricator to suit application.
- B. Bolts, Nuts, Washers, Lags, Pins, and Screws: Of size and type to suit application; chromeplated finish in concealed locations and stainless steel or chrome-plated finish in exposed locations.
- C. Grommets: Standard plastic, painted metal, or rubber grommets for cut-outs, in color as indicated.

2.08 HARDWARE

- A. Hardware: BHMA A156.9, types as indicated for quality grade specified.
- B. Metal Z-Shaped Wall Cabinet Support Clips: Paired, cleated, structural anchorage components applied to back of cabinets and walls for wall cabinet mounting.
- C. Adjustable Shelf Supports: Standard side-mounted system using recessed metal shelf standards and coordinated self rests, polished chrome finish, for nominal 1 inch (25 mm) spacing adjustments.
- D. Countertop Support Brackets: Fixed, L-shaped, face-of-stud mounting.
 - 1. Materials: Steel; T-shape cross-section.
 - a. Finish: Manufacturer's standard, factory-applied, powder coat.
 - b. Color: Black.
 - c. Basis of Design Floating Countertop Wall Bracket by Iron Supports
- E. Drawer and Door Pulls: PER FINISH SCHEDULE
- F. Touch-Opening Handleless Drawer Hardware:
 - 1. Manufacturers:
 - a. Titus Cabinet Hardware; Tekform Slimline Tacto: www.titusplus.com/us/en/#sle.
- G. Keyed Cabinet Locks: Keyed cylinder, two keys per lock, master keyed, steel with satin finish.
- H. Drawer Slides:
 - 1. Type: Standard extension.
 - 2. Static Load Capacity: Commercial grade.
 - 3. Mounting: Side mounted.
- I. Soft-Close, Door and Drawer Adjustable Dampers:

2.09 FABRICATION

- A. Assembly: Shop assemble cabinets for delivery to site in units easily handled and to permit passage through building openings.
- B. Fitting: When necessary to cut and fit on site, provide materials with ample allowance for cutting. Provide matching trim for scribing and site cutting.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- C. Plastic Laminate: Apply plastic laminate finish in full uninterrupted sheets consistent with manufactured sizes. Fit corners and joints hairline; secure with concealed fasteners. Slightly bevel arises. Locate counter butt joints minimum 2 feet from sink cut-outs. (Locate counter butt joints minimum 600 mm from sink cut-outs.)
- D. Provide cutouts for plumbing fixtures. Verify locations of cutouts from on-site dimensions. Prime paint cut edges.

2.10 SHOP FINISHING

A. Finish work in accordance with AWI/AWMAC/WI (AWS) or AWMAC/WI (NAAWS), Section 5 - Finishing for grade specified and as follows:

PART 3 EXECUTION

3.01 INSTALLATION

- A. Install work in accordance with AWI/AWMAC/WI (AWS) or AWMAC/WI (NAAWS) requirements for grade indicated.
- B. Set and secure custom cabinets in place, assuring that they are rigid, plumb, and level.
- C. Use fixture attachments in concealed locations for wall mounted components.
- D. Use concealed joint fasteners to align and secure adjoining cabinet units.
- E. Carefully scribe casework abutting other components, with maximum gaps of 1/32 inch (0.79 mm). Do not use additional overlay trim for this purpose.
- F. Secure cabinets to floor using appropriate angles and anchorages.
- G. Countersink anchorage devices at exposed locations. Conceal with solid wood plugs of species to match surrounding wood; finish flush with surrounding surfaces.

3.02 ADJUSTING

A. Adjust moving or operating parts to function smoothly and correctly.

3.03 CLEANING

A. Clean casework, counters, shelves, hardware, fittings, and fixtures.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 072100 THERMAL INSULATION

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Board insulation at cavity wall construction, perimeter foundation wall, and underside of floor slabs.
- B. Batt insulation for filling perimeter window and door shim spaces and crevices in exterior wall and roof.

1.02 DEFINITIONS

- A. Mineral Fiber Material Composition: Insulation referred to as mineral fiber block, board, and blanket insulation is composed of fibers from mineral based substances such as rock, slag, or glass and processed from the molten state into fibrous form.
 - 1. Based on type of insulation substance, the material will be referred to as a mineral fiber when having a rock or slag base, and glass fiber with a glass or silica sand base, also considered a mineral.
 - 2. Insulation blankets are flexible units consisting of felted, bonded, or unbonded fibers formed into rolls or flat cut pieces referred to as batts; rolls are simply longer versions of batts.
 - 3. For additional information about mineral fiber and the various classification types, refer to the following reference standards; ASTM C553, ASTM C612, ASTM C665, and ASTM C726.

1.03 REFERENCE STANDARDS

- A. ASTM C553 Standard Specification for Mineral Fiber Blanket Thermal Insulation for Commercial and Industrial Applications; 2013 (Reapproved 2019).
- B. ASTM C578 Standard Specification for Rigid, Cellular Polystyrene Thermal Insulation; 2023.
- C. ASTM C612 Standard Specification for Mineral Fiber Block and Board Thermal Insulation; 2014 (Reapproved 2019).
- D. ASTM C665 Standard Specification for Mineral-Fiber Blanket Thermal Insulation for Light Frame Construction and Manufactured Housing; 2023.
- E. ASTM C726 Standard Specification for Mineral Wool Roof Insulation Board; 2017.
- F. ASTM C1289 Standard Specification for Faced Rigid Cellular Polyisocyanurate Thermal Insulation Board; 2023a.
- G. ASTM E84 Standard Test Method for Surface Burning Characteristics of Building Materials; 2023d.
- H. ASTM E136 Standard Test Method for Assessing Combustibility of Materials Using a Vertical Tube Furnace at 750 Degrees C; 2024.
- I. NFPA 285 Standard Fire Test Method for Evaluation of Fire Propagation Characteristics of Exterior Wall Assemblies Containing Combustible Components; 2025.

1.04 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Product Data: Provide data on product characteristics, performance criteria, and product limitations.
- C. Shop Drawings: Submit drawings that indicate location of joint or termination detail conditions.
- D. ABAA Field Quality Control Submittals: Submit third-party reports of testing and inspection required by ABAA QAP.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- E. ABAA Manufacturer Qualification: Submit documentation of current evaluation of proposed manufacturer and materials.
- F. ABAA Installer Qualification: Submit documentation of current contractor accreditation and current installer certification. Keep copies of contractor accreditation and installer certification on project site during and after installation. Present on-site documentation upon request.

1.05 QUALITY ASSURANCE

- Air Barrier Association of America (ABAA) Quality Assurance Program (QAP); www.airbarrier.org/#sle:
 - 1. Installer Qualification: Use accredited contractors, certified installers, evaluated materials, and third-party field quality control audit.
 - 2. Manufacturer Qualification: Use evaluated materials from a single manufacturer regularly engaged in air barrier material manufacture. Use secondary materials approved in writing by primary material manufacturer.

1.06 FIELD CONDITIONS

A. Do not install insulation adhesives when temperature or weather conditions are detrimental to successful installation.

PART 2 PRODUCTS

2.01 APPLICATIONS

- A. Insulation Under Concrete Slabs: Extruded Polystyrene board.
- B. Insulation at Perimeter of Foundation: Extruded Polystyrene board.
- C. Insulation Inside Masonry Cavity Walls: Polyisocyanurate (polyiso) board.
- D. Insulation Over Metal Stud Framed Walls, Continuous: Polyisocyanurate (polyiso) board.

2.02 FOAM BOARD INSULATION MATERIALS

- A. Extruded Polystyrene (XPS) Board Insulation: Comply with ASTM C578 with either natural skin or cut cell surfaces.
 - 1. Flame Spread Index (FSI): Class A 0 to 25, when tested in accordance with ASTM E84.
 - 2. Smoke Developed Index (SDI): 450 or less, when tested in accordance with ASTM E84.
 - 3. Type and Thermal Resistance, R-value (RSI-value): Type IV, 5.0 (0.88), minimum, per 1 inch (25.4 mm) thickness at 75 degrees F (24 degrees C) mean temperature.
 - 4. Complies with fire resistance requirements indicated on drawings as part of an exterior non-load-bearing exterior wall assembly when tested in accordance with NFPA 285.
 - 5. Board Edges: Square.
 - 6. Type and Water Absorption: Type XII, 0.3 percent by volume, maximum, by total immersion.
 - 7. Products:
 - a. DuPont de Nemours, Inc: building.dupont.com/#sle.
 - b. Kingspan Insulation LLC; GreenGuard GG25-LG XPS Insulation Board: www.kingspan.com/#sle.
 - c. Owens Corning Corporation; FOAMULAR NGX Type 250 Next Generation Extruded: www.ocbuildingspec.com/#sle.
- B. Polyisocyanurate (ISO) Board Insulation: Rigid cellular foam, comply with ASTM C1289.
 - 1. Classifications:
 - a. Type II: Faced with either cellulosic facers or glass fiber mat facers on both major surfaces of the core foam.
 - 1) Class 1 Faced with glass fiber reinforced cellulosic facers on both major surfaces of core foam.
 - 2) Compressive Strength: Classes 1-2-3, Grade 1 16 psi (110 kPa), minimum.

FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 3) Thermal Resistance, R-value (RSI-value): At 1-1/2 inch (38.1 mm) thick; Class 1, Grades 1-2-3 8.4 (1.48), minimum, at 75 degrees F (24 degrees C).
- 2. Board Size: 48 inch by 96 inch (1220 mm by 2440 mm).
- 3. Board Thickness: Ref. dwgs..
- 4. Board Edges: Square.
- 5. Products:
 - a. Atlas Roofing Corporation; ACFoam Supreme Foil Faced Roof Insulation: www.atlasroofing.com/#sle.
 - b. Carlisle Coatings & Waterproofing, Inc; R2+ Silver: www.carlisleccw.com/#sle.
 - c. DuPont de Nemours, Inc; Thermax Light Duty NH: building.dupont.com/#sle.
 - d. Hunter Panels; Xci Foil (Class A): www.hunterpanels.com/#sle.
 - e. Johns Manville; AP Foil-Faced: www.jm.com/#sle.
 - f. Ox Engineered Products; ISO Red Max (Polyiso Class A): www.oxengineeredproducts.com/#sle.
 - g. Rmax Inc; ECOMAXci FR: www.rmax.com/#sle.
 - h. Substitutions: See Section 016000 Product Requirements.

2.03 MINERAL FIBER BOARD INSULATION MATERIALS

- A. Mineral Wool Block, Board, or Blanket Thermal Insulation: Complying with ASTM C612 or ASTM C553.
 - 1. Smoke Developed Index: 450 or less, when tested in accordance with ASTM E84.
 - 2. Products:
 - a. Johns Manville; MinWool Safing: www.jm.com/#sle.
 - b. Thermafiber, Inc; Safing: www.thermafiber.com/#sle.
 - c. Substitutions: See Section 016000 Product Requirements.

2.04 MINERAL FIBER BLANKET INSULATION MATERIALS

- A. Flexible Glass Fiber Blanket Thermal Insulation: Preformed insulation, complying with ASTM C665; friction fit.
 - 1. Combustibility: Non-combustible, when tested in accordance with ASTM E136, except for facing, if any.
- B. Mineral Wool Blanket Thermal Insulation: Flexible or semi-rigid preformed insulation, complying with ASTM C665.
 - 1. Smoke Developed Index: 450 or less, when tested in accordance with ASTM E84.
- C. Mineral Fiber Enclosure for Recessed Ceiling Fixtures: Insulated box enclosure with foil facing on exterior side for placement over recessed ceiling light fixture; flame spread index of 25 or less, and smoke development index of 450 or less when tested in accordance with ASTM E84.
 - 1. Light Fixture Size: As indicated on drawings.

2.05 ACCESSORIES

- A. Tape: Bright aluminum self-adhering type, mesh reinforced, 2 inch (50 mm) wide.
 - 1. Products:
 - a. Rmax Inc; R-SEAL 3000: www.rmax.com/#sle.
- B. Support for Cladding and Continuous Insulation: See respective cladding section.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that substrate, adjacent materials, and insulation materials are dry and that substrates are ready to receive insulation.
- B. Verify substrate surfaces are flat, free of honeycomb, fins, irregularities, or materials or substances that may impede adhesive bond.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

3.02 BOARD INSTALLATION AT FOUNDATION PERIMETER

- A. Adhere a 6 inches (152 mm) wide strip of polyethylene sheet over construction, control, and expansion joints with double beads of adhesive each side of joint.
 - 1. Tape seal joints.
 - 2. Extend sheet full height of joint.
- B. Apply adhesive to back of boards:
 - 1. Three continuous beads per board length.
 - 2. Full bed 1/8 inch (3.2 mm) thick.
- C. Install boards horizontally on foundation perimeter.
 - 1. Place boards to maximize adhesive contact.
 - 2. Install in running bond pattern.
- D. Cut and fit insulation tightly to protrusions or interruptions to the insulation plane.

3.03 BOARD INSTALLATION AT EXTERIOR WALLS

- A. Install boards horizontally on walls.
- B. Cut and fit insulation tightly to protrusions or interruptions to the insulation plane.

3.04 BOARD INSTALLATION AT CAVITY WALLS

- A. Install boards to fit snugly between wall ties.
- B. Install boards horizontally on walls.
- C. Cut and fit insulation tightly to protrusions or interruptions to the insulation plane.

3.05 BOARD INSTALLATION UNDER CONCRETE SLABS

- A. Place insulation under slabs on grade after base for slab has been compacted.
- B. Cut and fit insulation tightly to protrusions or interruptions to the insulation plane.
- C. Prevent insulation from being displaced or damaged while placing vapor retarder and placing slab.

3.06 BATT INSTALLATION

- A. Install insulation in accordance with manufacturer's instructions.
- B. Trim insulation neatly to fit spaces. Insulate miscellaneous gaps and voids.
- C. Fit insulation tightly in cavities and tightly to exterior side of mechanical and electrical services within the plane of the insulation.

3.07 FIELD QUALITY CONTROL

- A. See Section 014000 Quality Requirements for additional requirements.
- B. Coordination of Air Barrier Association of America (ABAA) Tests and Inspections:
 - 1. Provide testing and inspection required by ABAA Quality Assurance Program (QAP).
 - 2. Notify ABAA in writing of schedule for air barrier work, and allow adequate time for testing and inspection.
 - 3. Cooperate with ABAA testing agency.
 - 4. Allow access to air barrier work areas and staging.
 - 5. Do not cover air barrier work until tested, inspected, and accepted.

3.08 PROTECTION

A. Do not permit installed insulation to be damaged prior to its concealment.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 072700 AIR BARRIERS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Air barriers.

1.02 RELATED REQUIREMENTS

A. Section 061000 - Rough Carpentry: Sheathing with integral air barrier.

1.03 DEFINITIONS

A. Air Barrier: Airtight barrier made of material that is virtually air impermeable but water vapor permeable, both to amount as specified, with sealed seams and sealed joints to adjacent surfaces.

1.04 REFERENCE STANDARDS

- A. ASTM D412 Standard Test Methods for Vulcanized Rubber and Thermoplastic Elastomers--Tension; 2016 (Reapproved 2021).
- B. ASTM D751 Standard Test Methods for Coated Fabrics; 2019.
- C. ASTM D903 Standard Test Method for Peel or Stripping Strength of Adhesive Bonds; 1998 (Reapproved 2017).
- D. ASTM D1970/D1970M Standard Specification for Self-Adhering Polymer Modified Bituminous Sheet Materials Used as Steep Roofing Underlayment for Ice Dam Protection; 2021.
- E. ASTM E84 Standard Test Method for Surface Burning Characteristics of Building Materials; 2023d.
- F. ASTM E96/E96M Standard Test Methods for Gravimetric Determination of Water Vapor Transmission Rate of Materials; 2023.
- G. ASTM E2178 Standard Test Method for Determining Air Leakage Rate and Calculation of Air Permeance of Building Materials; 2021a.
- H. ICC-ES AC148 Acceptance Criteria for Flexible Flashing Materials; 2017, with Editorial Revision (2021).
- I. NFPA 285 Standard Fire Test Method for Evaluation of Fire Propagation Characteristics of Exterior Wall Assemblies Containing Combustible Components; 2025.

1.05 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Product Data: Provide data on material characteristics, performance criteria, and limitations.
- C. Shop Drawings: Provide drawings of special joint conditions.
- D. ABAA Field Quality Control Submittals: Submit third-party reports of testing and inspection required by ABAA QAP.
- E. Manufacturer's Installation Instructions: Indicate preparation, installation methods, and storage and handling criteria.
- F. ABAA Manufacturer Qualification: Submit documentation of current evaluation of proposed manufacturer and materials.
- G. ABAA Installer Qualification: Submit documentation of current contractor accreditation and current installer certification; keep copies of each contractor accreditation and installer certification on site during and after installation, and present on-site documentation upon request.
- H. Manufacturer's qualification statement.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- I. Installer's qualification statement.
- J. Testing agency qualification statement.

1.06 QUALITY ASSURANCE

- A. Air Barrier Association of America (ABAA) Quality Assurance Program (QAP); www.airbarrier.org/#sle:
 - 1. Installer Qualification: Use accredited contractor, certified installers, evaluated materials, and third-party field quality control audit.
- B. Air Barrier Association of America (ABAA) Evaluated Air Barrier Assemblies; www.airbarrier.org/#sle: Use evaluated materials from a single manufacturer regularly engaged in air barrier material manufacture, and use secondary materials approved in writing by primary material manufacturer.
- C. Installer Qualifications: Company specializing in performing the work of this section with minimum three years documented experience.
- D. Manufacturer Qualification: Use evaluated materials from a single manufacturer regularly engaged in air barrier material manufacture, and use secondary materials approved in writing by primary material manufacturer.
- E. Testing Agency Qualifications: Independent firm specializing in performing testing and inspections of the type specified in this section.

1.07 MOCK-UPS

- A. See Section 014000 Quality Requirements for additional requirements.
- B. Construct air barrier mock-up, 8 ft long by 8 ft wide, indicating transitions.
- C. Locate where directed.

1.08 FIELD CONDITIONS

A. Maintain temperature and humidity recommended by materials manufacturers before, during, and after installation.

PART 2 PRODUCTS

2.01 AIR BARRIER MATERIALS (AIR IMPERMEABLE AND WATER VAPOR PERMEABLE)

- A. Air Barrier, Fluid Applied: Vapor semi-permeable, elastomeric waterproofing.
 - 1. Air Barrier Coating:
 - a. Material: Silyl-terminated polyether (STPE).
 - b. Dry Film Thickness (DFT): 20 mil, 0.020 inch (0.508 mm), minimum.
 - c. Air Permeance: 0.004 cfm/sq ft (0.02 L/(s sq m)), maximum, when tested in accordance with ASTM E2178.detroit
 - d. Water Vapor Permeance: 11 perms (629 ng/(Pa s sq m)), minimum, when tested in accordance with ASTM E96/E96M using Procedure B Water Method, at 73.4 degrees F (23 degrees C).
 - e. Ultraviolet (UV) and Weathering Resistance: Approved by manufacturer for up to 90 days of weather exposure.
 - f. Elongation: 300 percent, minimum, when tested in accordance with ASTM D412.
 - g. Surface Burning Characteristics: Flame spread index of 25 or less, smoke developed index of 450 or less, Class A when tested in accordance with ASTM E84.
 - h. Comply with NFPA 285 requirements for wall assembly.
 - i. Nail Sealability: Pass, when tested in accordance with ASTM D1970/D1970M.
 - j. Sealants, Tapes and Accessories: As recommended by coating manufacturer.
 - k. Products:
 - 1) Carlisle Coatings and Waterproofing, Inc: www.carlisleccw.com/#sle.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- 2) Dow Chemical Company: consumer.dow.com/en-us/industry/ind-buildingconstruction.html/#sle.
- 3) DuPont de Nemours, Inc with : building.dupont.com/#sle.
- 4) Henry Company; Air-Bloc All Weather STPE: www.henry.com/#sle.
- 5) Parex USA, Inc: www.parexusa.com/#sle.
- 6) Pecora Corporation; Pecora ProPerm VP Vapor Permeable Air Barrier System with XL-Flash Liquid Flashing and Joint Filler, AVB Silicone Surface Transitions, and XL-Span Transition Membrane: www.pecora.com/#sle.
- 2. Air Barrier Membrane:
 - a. Material: Water-based acrylic.
 - b. Dry Film Thickness (DFT): 30 mil, 0.030 inch (0.762 mm), minimum.
 - c. Air Permeance: 0.004 cfm/sq ft (0.02 L/(s sq m)), maximum, when tested in accordance with ASTM E2178.
 - d. Water Vapor Permeance: 11 perms (629 ng/(Pa s sq m)), minimum, when tested in accordance with ASTM E96/E96M using Procedure B Water Method, at 73.4 degrees F (23 degrees C).

2.02 ACCESSORIES

- A. Sealants, Tapes, and Accessories for Sealing Air Barrier and Adjacent Substrates: As indicated or in compliance with air barrier manufacturer's installation instructions.
- B. Sealant for Cracks and Joints In Substrates: Resilient elastomeric joint sealant compatible with substrate and air barrier materials.
 - 1. Application: Apply at 30 to 40 mil, 0.030 to 0.040 inch (0.76 to 1.02 mm), nominal thickness.
 - 2. Color: Green.
 - 3. Elongation: 1,300 percent, measured in accordance with ASTM D412.
 - 4. Peel Adhesion: 28 lb/inch (5.0 kg/cm), minimum, when tested in accordance with ASTM D903.
 - 5. Hydrostatic Head Pressure: Resists head pressure of 57 feet (17.4 m), maximum, when tested in accordance with ASTM D751.
 - 6. Comply with NFPA 285 requirements for wall assembly.
- C. Primer: Liquid applied polymer.
 - 1. Color: Green.
- D. Flexible Flashing: Self-adhering or mechanically-attached flashing used for wall penetrations in accordance with ICC-ES AC148 requirements.
- E. Sill Plate Sealer: Closed-cell foam tape with rubberized adhesive membrane; bridges gap between foundation structure and sill plate or skirt board.
 - 1. Width: 3-1/2 inches (89 mm).
 - 2. Ultraviolet (UV) and Weathering Resistance: Approved by manufacturer for up to 30 days of weather exposure.
- F. Preformed Transition Membrane: Semirigid silicone or polyester composition, tapered edges, tear resistant.
- G. Stainless Steel Flashing: Flexible flashing with 2 mil, 0.002 inch (0.051 mm) thick Type 304 stainless steel sheet, 8 mil, 0.008 inch (0.203 mm) of butyl adhesive and siliconized release liner.
 - 1. Roll Length: 50 feet (15.2 m) long.
 - 2. Width: 6 inches (152 mm) wide.
- H. Thinners and Cleaners: As recommended by material manufacturer.
- I. Air and Moisture Sealing Insulation Fasteners: Preassembled fastener units consisting of sealing washer, screw, and gasketing tube.

FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- 1. Length as required for thickness of insulation material and penetration of deck substrate.
- 2. Thread and tip types as required for substrate material.
- 3. Products:
 - a. TruFast Walls, a Division of Altenloh, Brinck & Co. US, Inc; Grip-Deck TubeSeal: www.trufastwalls.com/#sle.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that surfaces and conditions are ready for work of this section.
- B. Where existing conditions are responsibility of another installer, notify Architect of unsatisfactory conditions.
- C. Do not proceed with this work until unsatisfactory conditions have been corrected.

3.02 PREPARATION

- A. Remove projections, protruding fasteners, and loose or foreign matter that might interfere with proper installation.
- B. Clean and prime substrate surfaces to receive adhesives and sealants in accordance with manufacturer's installation instructions.

3.03 INSTALLATION

- A. Install materials in accordance with manufacturer's installation instructions.
- B. Air Barriers: Install continuous airtight barrier over surfaces indicated, with sealed seams and with sealed joints to adjacent surfaces.
- C. Apply sealants and adhesives within recommended temperature range in accordance with manufacturer's installation instructions.
- D. Fluid-Applied Coatings or Membranes:
 - 1. Prepare substrate in accordance with manufacturer's installation instructions; treat joints in substrate and between dissimilar materials as indicated.
 - 2. Where exterior masonry veneer is being installed, install masonry anchors before installing air barrier over masonry; provide airtight seal around anchors.
 - 3. Use flashing to seal to adjacent construction and to bridge joints in coating substrate.
- E. Openings and Penetrations in Exterior Air Barriers:
 - 1. Install flashing over sills, covering entire sill frame member, extending at least 5 inches (125 mm) onto air barrier and at least 6 inches (150 mm) up jambs; mechanically fasten stretched edges.
 - 2. At openings with frames having nailing flanges, seal head and jamb flanges using a continuous bead of sealant compressed by flange and cover flanges with sealing tape at least 4 inches (100 mm) wide; do not seal sill flange.
 - 3. At openings with nonflanged frames, seal air barrier to each side of framing at opening using flashing at least 9 inches (230 mm) wide, and covering entire depth of framing.
 - 4. At head of openings, install flashing under air barrier extending at least 2 inches (50 mm) beyond face of jambs; seal air barrier to flashing.
 - 5. At interior face of openings, seal gap between window/door frame and rough framing, using joint sealant over backer rod.
 - 6. Service and Other Penetrations: Form flashing around penetrating item and seal to air barrier surface.

3.04 FIELD QUALITY CONTROL

- A. See Section 014000 Quality Requirements for additional requirements.
- B. Coordination of ABAA Tests and Inspections:
 - 1. Provide testing and inspection required by ABAA QAP.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- 2. Notify ABAA in writing of schedule for air barrier work, and allow adequate time for testing and inspection.
- 3. Cooperate with ABAA testing agency.
- 4. Allow access to air barrier work areas and staging.
- 5. Do not cover air barrier work until tested, inspected, and accepted.
- C. Do not cover installed air barriers until required inspections have been completed.
- D. Obtain approval of installation procedures from air barrier manufacturer based on a mock-up installed in place, prior to proceeding with remainder of installation.

3.05 PROTECTION

A. Do not leave materials exposed to weather longer than recommended by manufacturer.

FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 075300 ELASTOMERIC MEMBRANE ROOFING

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Elastomeric roofing membrane application.
- B. Insulation, flat and tapered.
- C. Vapor retarder.
- D. Cover boards.

1.02 RELATED REQUIREMENTS

A. Section 061000 - Rough Carpentry: Wood cant strips.

1.03 REFERENCE STANDARDS

- A. ASTM C578 Standard Specification for Rigid, Cellular Polystyrene Thermal Insulation; 2023.
- B. ASTM C728 Standard Specification for Perlite Thermal Insulation Board; 2017a (Reapproved 2022).
- C. ASTM C1289 Standard Specification for Faced Rigid Cellular Polyisocyanurate Thermal Insulation Board; 2023a.
- D. ASTM D4637/D4637M Standard Specification for EPDM Sheet Used in Single-Ply Roof Membrane; 2015, with Editorial Revision (2022).
- E. ASTM E96/E96M Standard Test Methods for Gravimetric Determination of Water Vapor Transmission Rate of Materials; 2023.
- F. FM (AG) FM Approval Guide; Current Edition.
- G. FM DS 1-28 Wind Design; 2015, with Editorial Revision (2024).

1.04 ADMINISTRATIVE REQUIREMENTS

- A. Coordinate with installation of associated counterflashings installed under other sections.
- B. Preinstallation Meeting: Convene a preinstallation meeting one week before starting work of this section; require attendance by all affected installers; review preparation and installation procedures and coordination and scheduling necessary for related work.

1.05 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Product Data: Provide data indicating membrane materials, flashing materials, insulation, vapor retarder, surfacing, and fasteners.
- C. Shop Drawings: Indicate joint or termination detail conditions, conditions of interface with other materials, and paver layout.
- D. Samples for Verification: Submit two samples 6 x 6 in size illustrating insulation.
- E. Manufacturer's Installation Instructions: Indicate membrane seaming precautions and perimeter conditions requiring special attention.
- F. Installer's qualification statement.
- G. Warranty: Submit manufacturer warranty and ensure forms have been completed in Owner's name and registered with manufacturer.

1.06 QUALITY ASSURANCE

A. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum three years of documented experience.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

B. Installer Qualifications: Company specializing in performing the work of this section with minimum three years documented experience.

1.07 DELIVERY, STORAGE, AND HANDLING

- A. See Section 017419 Construction Waste Management and Disposal for packaging waste requirements.
- B. Deliver materials in manufacturer's original containers, dry and undamaged, with seals and labels intact.
- C. Store materials in weather protected environment, clear of ground and moisture.
- D. Ensure storage and staging of materials does not exceed static and dynamic load-bearing capacities of roof decking.
- E. Protect foam insulation from direct exposure to sunlight.

1.08 FIELD CONDITIONS

- A. Do not apply roofing membrane during unsuitable weather.
- B. Do not apply roofing membrane when ambient temperature is below 40 degrees F (5 degrees C).
- C. Do not apply roofing membrane to damp or frozen deck surface or when precipitation is expected or occurring.
- D. Do not expose materials vulnerable to water or sun damage in quantities greater than can be weatherproofed the same day.
- E. Schedule applications so that no partially completed sections of roof are left exposed at end of workday.

1.09 WARRANTY

- A. See Section 017800 Closeout Submittals for additional warranty requirements.
- B. Provide five year manufacturer's material and labor warranty to cover failure to prevent penetration of water.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. EPDM Membrane Materials:
 - 1. Carlisle SynTec Systems; Sure-Tough EPDM: www.carlisle-syntec.com/#sle.
 - 2. Elevate; Low Slope Fire Retardant (LSFR) RubberGard EPDM Membrane: www.holcimelevate.com/#sle.
 - 3. GenFlex Roofing Systems, LLC: www.genflex.com/#sle.
 - 4. Johns Manville; JM EPDM: www.jm.com/#sle.
- B. Insulation:
 - 1. Blue Ridge Fiberboard: www.blueridgefiberboard.com/#sle.
 - 2. Dow: www.dow.com/#sle.
 - 3. GAF: www.gaf.com/#sle.
 - 4. Hunter Panels: www.hunterpanels.com/#sle.
 - 5. Owens Corning Corporation: www.owenscorning.com/#sle.
 - 6. ROCKWOOL: www.rockwool.com/#sle.
 - 7. Versico Roofing Systems; SecurShield Insulation: www.versico.com/#sle.
 - 8. Carlisle Syntec Systems. Insul Base POLYISO is basis of design.

2.02 ROOFING - UNBALLASTED APPLICATIONS

- A. Elastomeric Membrane Roofing: One ply membrane, mechanically fastened, over insulation.
- B. Acceptable Insulation Types Constant Thickness Application: Any of types specified.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 1. Minimum 2 layers of polyisocyanurate board.
- C. Acceptable Insulation Types Tapered Application: Any type that meets requirements and is approved by membrane manufacturer for application.
 - 1. Tapered polyisocyanurate, perlite, or extruded polystyrene board.

2.03 ROOFING MEMBRANE AND ASSOCIATED MATERIALS

- A. Membrane: Ethylene-propylene-diene-monomer (EPDM); externally reinforced with fabric; complying with minimum properties of ASTM D4637/D4637M.
 - 1. Thickness: 45 mil, 0.045 inch (1.1 mm), minimum.
 - 2. Sheet Width: 76 inches (1,930 mm), minimum; factory fabricate into widest possible sheets.
- B. Seaming Materials: As recommended by membrane manufacturer.
- C. Membrane Fasteners: As recommended by and approved by membrane manufacturer.
- D. Vapor Retarder: Non-bituminous, foil and fibrous mesh laminate, complying with requirements of fire rating classification; compatible with roofing and insulation materials.
 - 1. Fire-retardant adhesive.
 - 2. Vapor Permeability: 03 perms, measured in accordance with ASTM E96/E96M.
- E. Flexible Flashing Material: Same material as membrane.

2.04 COVER BOARDS

- A. Cover Boards: Faced and with high compressive strength polyisocyanurate (ISO) insulation complying with ASTM C1289.
 - 1. Classifications:
 - a. Type II Faced with either cellulosic facers or glass fiber mat facers on both major surfaces of the core foam.
 - Class 4 Faced with coated or uncoated glass fiber mat facers on both major surfaces of the core foam. This product is used at a maximum thickness of 1/2 inch (12.7 mm).
 - (a) Compressive Strength: Grade 2, 110 psi (Grade 2, 758 kPa), minimum.
 - 2. Board Size: 48 by 96 inches (1220 by 2440 mm).
 - 3. Board Thickness: 1/2 inch (12.7 mm).

2.05 INSULATION

- A. Perlite Board Insulation: Expanded perlite mineral aggregate, complying with ASTM C728.
 - 1. Board Size: 24 by 48 inches (619 by 1220 mm).
 - 2. Board Thickness: 1/2 inch (12.7 mm).
 - 3. Tapered Board: Slope as indicated, fabricate of fewest layers possible.
 - 4. Board Edges: Square.
- B. Polyisocyanurate (ISO) Board Insulation: Rigid cellular foam, complying with ASTM C1289.
 - 1. Classifications:
 - a. Type II: Faced with either cellulosic facers or glass fiber mat facers on both major surfaces of the core foam.
 - 1) Class 1 Faced with glass fiber reinforced cellulosic facers on both major surfaces of the core foam.
 - 2) Compressive Strength: Classes 1-2-3, Grade 2 20 psi (138 kPa), minimum.
 - Thermal Resistance, R-value (RSI-value): At 1-1/2 inches (38 mm) thick; Class 1, Grades 1-2-3 - 8.4 (1.48) at 75 degrees F (24 degrees C).
 - 2. Board Size: 48 by 96 inches (1220 by 2440 mm).
 - 3. Board Thickness: 1.5 inch (37.5 mm).
 - 4. Board Edges: Square.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- C. Extruded Polystyrene (XPS) Board Insulation: Complying with ASTM C578, with natural skin surfaces and drainage channels on one face.
 - 1. Board Size: 48 by 96 inches (1220 by 2440 mm).
 - 2. Board Thickness: 1-1/2 inches (38 mm).
 - 3. Tapered Board: Slope as indicated; minimum thickness 1/2 inch (12.7 mm); fabricate of fewest layers possible.

2.06 ACCESSORIES

- A. Stack Boots: Prefabricated flexible boot and collar for pipe stacks through membrane; same material as membrane.
- B. Cant Strips: Wood, pressure preservative treated; see Section 061000.
- C. Insulation Fasteners: Appropriate for purpose intended.
- D. Membrane Adhesive: As recommended by membrane manufacturer.
- E. Surface Primer Over Roof Substrate for Adhesion of Membrane: Low VOC acrylic primer for application over roofing substrates.
 - 1. Color: White.
 - 2. Roof Membrane Substrate: Includes galvanized metal, plywood, aluminum with Kynar finish, or EPDM as indicated on drawings.
- F. Insulation Adhesive: As recommended by insulation manufacturer.
- G. Roofing Nails: Galvanized, hot-dipped type, size and configuration as required to suit application.
- H. Walkway Pads: Suitable for maintenance traffic, contrasting color or otherwise visually distinctive from roof membrane.
 - 1. Composition: Rubber with mineral granule surface.
 - 2. Surface Color: White or yellow.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that surfaces and site conditions are ready to receive work.
- B. Verify deck is supported and secure.
- C. Verify deck is clean and smooth, flat, free of depressions, waves, or projections, properly sloped and suitable for installation of roof system.
- D. Verify deck surfaces are dry and free of snow or ice.
- E. Verify that roof openings, curbs, and penetrations through roof are solidly set, and cant strips are in place.

3.02 INSTALLATION - INSULATION, UNDER MEMBRANE

- A. Install vapor retarder to deck surface with adhesive in accordance with manufacturer's instructions.
 - 1. Extend vapor retarder under cant strips and blocking to deck edge.
 - 2. Install flexible flashing from vapor retarder to air seal material of wall construction, lap and seal to provide continuity of the air barrier plane.
- B. Ensure vapor retarder is clean and dry, continuous, and ready for application of insulation.
- C. Attachment of Insulation:
 - 1. Mechanically fasten first layer of insulation to deck in accordance with roofing manufacturer's instructions and FM (AG) Factory Mutual requirements.
 - 2. Embed second layer of insulation into full bed of adhesive in accordance with roofing and insulation manufacturers' instructions.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- D. Cover Boards: Mechanically fasten cover boards in accordance with roofing manufacturer's instructions and FM (AG) Factory Mutual requirements.
- E. Lay subsequent layers of insulation with joints staggered minimum 6 inches (152 mm) from joints of preceding layer.
- F. Place tapered insulation to the required slope pattern in accordance with manufacturer's instructions.
- G. Lay boards with edges in moderate contact without forcing. Cut insulation to fit neatly to perimeter blocking and around penetrations through roof.
- H. Do not apply more insulation than can be covered with membrane in same day.

3.03 INSTALLATION - MEMBRANE

- A. Roll out membrane, free from wrinkles or tears. Place sheet into place without stretching.
- B. Shingle joints on sloped substrate in direction of drainage.
- C. Spot Adhered Application: Mechanically fasten adhesion discs to substrate. Apply adhesive to discs and bond membrane. Fully adhere one roll before proceeding to adjacent rolls.
- D. Overlap edges and ends and seal seams by contact adhesive, minimum 3 inches (76 mm). Seal permanently waterproof. Apply uniform bead of sealant to joint edge.
- E. Mechanical Attachment: Install membrane and mechanical attachment devices in accordance with manufacturer's instructions.
- F. At intersections with vertical surfaces:
 - 1. Extend membrane over cant strips and up a minimum of 4 inches (102 mm) onto vertical surfaces.
 - 2. Fully adhere flexible flashing over membrane and up to nailing strips.
- G. Around roof penetrations, seal flanges and flashings with flexible flashing.
- H. Coordinate installation of roof drains and sumps and related flashings.

3.04 FIELD QUALITY CONTROL

- A. See Section 014000 Quality Requirements for additional requirements.
- B. Owner will provide testing services, and Contractor to provide temporary construction and materials for testing in accordance with requirements.
- C. Provide daily on-site attendance of roofing and insulation manufacturer's representative during installation of this work.

3.05 CLEANING

- A. See Section 017000 Execution and Closeout Requirements for additional requirements.
- B. Remove bituminous markings from finished surfaces.
- C. In areas where finished surfaces are soiled by work of this section, consult manufacturer of surfaces for cleaning advice and comply with their documented instructions.
- D. Repair or replace defaced or damaged finishes caused by work of this section.

3.06 PROTECTION

- A. Protect installed roofing and flashings from construction operations.
- B. Where traffic must continue over finished roof membrane, protect surfaces using durable materials.

FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 076200 SHEET METAL FLASHING AND TRIM

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. AAMA 2603 Voluntary Specification, Performance Requirements and Test Procedures for Pigmented Organic Coatings on Aluminum Extrusions and Panels (with Coil Coating Appendix); 2022.
- B. AAMA 2605 Voluntary Specification, Performance Requirements and Test Procedures for Superior Performing Organic Coatings on Aluminum Extrusions and Panels (with Coil Coating Appendix); 2022.
- C. ASTM A653/A653M Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process; 2023.
- D. ASTM A666 Standard Specification for Annealed or Cold-Worked Austenitic Stainless Steel Sheet, Strip, Plate, and Flat Bar; 2023.
- E. ASTM B101 Standard Specification for Lead-Coated Copper Sheet and Strip for Building Construction; 2022.
- F. ASTM B209/B209M Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate; 2021a.
- G. ASTM B370 Standard Specification for Copper Sheet and Strip for Building Construction; 2022.
- H. ASTM C920 Standard Specification for Elastomeric Joint Sealants; 2018.
- I. ASTM D4586/D4586M Standard Specification for Asphalt Roof Cement, Asbestos-Free; 2007 (Reapproved 2018).
- J. CDA A4050 Copper in Architecture Handbook; current edition.
- K. SMACNA (ASMM) Architectural Sheet Metal Manual; 2012.

1.02 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Shop Drawings: Indicate material profile, jointing pattern, jointing details, fastening methods, flashings, terminations, and installation details.

1.03 QUALITY ASSURANCE

A. Perform work in accordance with SMACNA (ASMM) and CDA A4050 requirements and standard details, except as otherwise indicated.

PART 2 PRODUCTS

2.01 SHEET MATERIALS

- A. Galvanized Steel: ASTM A653/A653M, with G90/Z275 zinc coating; minimum 24-gauge, 0.0239-inch (0.61 mm) thick base metal.
- B. Pre-Finished Galvanized Steel: ASTM A653/A653M, with G90/Z275 zinc coating; minimum 24gauge, 0.0239-inch (0.61 mm) thick base metal, shop pre-coated with PVDF coating.
 - 1. Polyvinylidene Fluoride (PVDF) Coating: Superior performing organic powder coating, AAMA 2605; multiple coat, thermally cured fluoropolymer finish system.
- C. Pre-Finished Aluminum: ASTM B209/B209M, 3005 alloy, H12 or H14 temper; 18 gauge, 0.040 inch (1.02 mm) thick; plain finish shop pre-coated with silicone modified polyester coating.
 - 1. Silicone Modified Polyester Coating: Pigmented organic powder coating, AAMA 2603; baked enamel finish system.
 - 2. Color: As selected by Architect from manufacturer's standard colors.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- D. Terne Coated Steel: 28-gauge, 0.0149-inch (0.38 mm) thick copper bearing carbon steel core material with 0.092 lb/sq ft (0.45 kg/sq m) terne alloy coating on both sides of core metal.
- E. Copper: ASTM B370, cold rolled 16 oz/sq ft, 24 gauge, 0.0216 inch (0.55 mm) thick; natural finish.
- F. Lead Coated Copper: ASTM B101, 24 oz/sq ft (7320 g/sq m) weight of bare copper sheet, HOO (cold-rolled) temper.
- G. Terne Coated Stainless Steel: 28-gauge, 0.0156-inch (0.40 mm) ASTM A666 Type 304 alloy core material with 0.092 lb/sq ft (0.45 kg/sq m) terne alloy coating on both sides of core metal.

2.02 FABRICATION

- A. Form sections true to shape, accurate in size, square, and free from distortion or defects.
- B. Form pieces in longest possible lengths.
- C. Hem exposed edges on underside 1/2 inch (13 mm); miter and seam corners.
- D. Form material with flat lock seams, except where otherwise indicated; at moving joints, use sealed lapped, bayonet-type or interlocking hooked seams.
- E. Fabricate corners from one piece with minimum 18-inch (450 mm) long legs; seam for rigidity, seal with sealant.
- F. Fabricate flashings to allow toe to extend 2 inches (50 mm) over roofing gravel. Return and brake edges.

2.03 GUTTERS AND DOWNSPOUTS

- A. Gutters: SMACNA (ASMM) Semi-circular profile.
- B. Downspouts: Profile as indicated.
- C. Gutters and Downspouts: Size for rainfall intensity determined by a storm occurrence of 1 in 10 years in accordance with SMACNA (ASMM).
- D. Accessories: Profiled to suit gutters and downspouts.
 - 1. Anchorage Devices: In accordance with SMACNA (ASMM) requirements.
 - 2. Gutter Supports: Spikes and ferrules.
 - 3. Downspout Supports: Brackets.
- E. Seal metal joints.

2.04 ACCESSORIES

- A. Fasteners: Galvanized steel, with soft neoprene washers.
- B. Primer Type: Zinc chromate.
- C. Concealed Sealants: Non-curing butyl sealant.
- D. Exposed Sealants: ASTM C920; elastomeric sealant, with minimum movement capability as recommended by manufacturer for substrates to be sealed; color to match adjacent material.
- E. Asphalt Roof Cement: ASTM D4586/D4586M, Type I, asbestos-free.

PART 3 EXECUTION

3.01 INSTALLATION

- A. Secure flashings in place using concealed fasteners, and use exposed fasteners only where permitted..
- B. Apply plastic cement compound between metal flashings and felt flashings.
- C. Fit flashings tight in place; make corners square, surfaces true and straight in planes, and lines accurate to profiles.

FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

D. Secure gutters and downspouts in place with concealed fasteners.

FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 077100 ROOF SPECIALTIES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Manufactured roof specialties, including copings.

1.02 RELATED REQUIREMENTS

A. Section 077200 - Roof Accessories: Manufactured curbs, roof hatches, and snow guards.

1.03 REFERENCE STANDARDS

- A. AAMA 2605 Voluntary Specification, Performance Requirements and Test Procedures for Superior Performing Organic Coatings on Aluminum Extrusions and Panels (with Coil Coating Appendix); 2022.
- B. ANSI/SPRI/FM 4435/ES-1 Test Standard for Edge Systems Used with Low Slope Roofing Systems; 2022.
- C. NRCA (RM) The NRCA Roofing Manual; 2025.

1.04 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Product Data: Provide data on shape of components, materials and finishes, anchor types and locations.
- C. Shop Drawings: Indicate configuration and dimension of components, adjacent construction, required clearances and tolerances, and other affected work.
- D. Manufacturer's Installation Instructions: Indicate special procedures, fasteners, supporting members, and perimeter conditions requiring special attention.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Roof Edge Flashings and Copings:
 - 1. Architectural Products Co: www.archprod.com/#sle.
 - 2. ATAS International, Inc; Rapid-Lok Fascia: www.atas.com/#sle.
 - 3. Drexel Metals Inc: www.drexmet.com/#sle.
 - 4. Hickman Edge Systems; Formed Coping Plus: www.hickmanedgesystems.com/#sle.
 - 5. Metal-Era Inc: www.metalera.com/#sle.
 - 6. Metal Roofing Systems, Inc; Rapid Lock Coping: www.metalroofingsystems.biz/#sle.
- B. Pipe and Penetration Flashings:
 - 1. Elmdor: www.elmdor.com/#sle.
- C. Counterflashings:
 - 1. ATAS International, Inc: www.atas.com/#sle.

2.02 COMPONENTS

- A. Roof Edge Flashings: Factory fabricated to sizes required; corners mitered; concealed fasteners.
 - 1. Configuration: Fascia, cant, and edge securement for roof membrane.
 - 2. Pull-Off Resistance: Tested in accordance with ANSI/SPRI/FM 4435/ES-1 using test methods RE-1 and RE-2 to positive and negative design wind pressure as defined by applicable local building code.
 - 3. Exposed Face Height: As indicated on drawings.
 - 4. Material: Formed aluminum sheet, 0.050 inch (1.3 mm) thick, minimum.
 - 5. Finish: 70 percent polyvinylidene fluoride.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 6. Color: As selected by Architect from manufacturer's standard range.
- 7. Products:
- B. Copings: Factory fabricated to sizes required; corners shall be factory mitered/welded; concealed fasteners.
 - 1. Configuration: Concealed continuous hold down cleat at both legs; internal splice piece at joints of same material, thickness, and finish as cap; concealed stainless steel fasteners.
 - Pull-Off Resistance: Tested in accordance with ANSI/SPRI/FM 4435/ES-1 using test method RE-3 to positive and negative design wind pressure as defined by applicable local building code.
 - 3. Wall Width: As indicated on drawings.
 - 4. Outside Face Height: As indicated on drawings.
 - 5. Inside Face Height: As indicated on drawings.
 - 6. Material: Formed aluminum sheet, 0.050 inch (1.3 mm) thick, minimum.
 - 7. Finish: 70 percent polyvinylidene fluoride.
 - 8. Color: As selected by Architect from manufacturer's standard range.
 - 9. Products:
 - a. ATAS International, Inc; Rapid-Lok Coping: www.atas.com/#sle.
 - b. Metal-Era Inc: www.metalera.com/#sle.
 - c. Hickman Edge Systems; Formed Coping Plus: www.hickmanedgesystems.com/#sle.
 - d. Substitutions: See Section 016000 Product Requirements.
- C. Pipe and Penetration Flashing: Base of rounded aluminum, compatible with EPDM roof systems, and capable of accomodating pipes sized between 3/8 inch (9.5 mm) and 12 inches (305 mm).
 - 1. Caps: Clear anodized.
 - 2. Color: selection by Architect from Mfr's. full range.
 - 3. Products:
 - a. Menzies Metal Products; Multi-Flash Insulated Pipe Flashing Spun: www.menziesmetal.com/#sle.
- D. Roof Penetration Sealing Systems: Premanufactured components and accessories as required to preserve integrity of roofing system and maintain roof warranty; suitable for conduits and roofing system to be installed; designed to accommodate existing penetrations where applicable.
- E. Counterflashings: Factory fabricated and finished sheet metal that overlaps top edges of base flashing by at least 4 inches (102 mm), and designed to snap into through-wall flashing or reglets with lapped joints.
 - 1. Material: Stainless steel sheet, 26 gauge, 0.019 inch (0.48 mm) thick, minimum.

2.03 FINISHES

- A. Color Anodized Finish: AAMA 611 AA-M12C22A42/44 Class I integrally or electrolytically colored anodic coating not less than 0.7 mil, 0.0007 inch (0.018 mm) thick.
- B. PVDF (Polyvinylidene Fluoride) Coating: Superior Performance Organic Finish, AAMA 2605; multiple coat, thermally cured fluoropolymer finish system; color as indicated.

2.04 ACCESSORIES

- A. Sealant for Joints in Linear Components: As recommended by component manufacturer.
- B. Adhesive for Anchoring to Roof Membrane: Compatible with roof membrane and approved by roof membrane manufacturer.
- C. Insulation Board Adhesive: Two-component, low-rise polyurethane foam adhesive used for adhering insulation to low slope roof deck materials.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that deck, curbs, roof membrane, base flashing, and other items affecting work of this Section are in place and positioned correctly.

3.02 INSTALLATION

- A. Install components in accordance with manufacturer's instructions and NRCA (RM) applicable requirements.
- B. Seal joints within components when required by component manufacturer.
- C. Anchor components securely.
- D. Coordinate installation of components of this section with installation of roofing membrane and base flashings.
- E. Coordinate installation of sealants and roofing cement with work of this section to ensure water tightness.
- F. Coordinate installation of flashing flanges into reglets.

FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 077200 ROOF ACCESSORIES

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Roof curbs.
- B. Roof hatches.

1.02 REFERENCE STANDARDS

1.03 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Product Data: Manufacturer's data sheets on each product to be used.
 - 1. Preparation instructions and recommendations.
 - 2. Storage and handling requirements and recommendations.
 - 3. Installation methods.
 - 4. Maintenance requirements.
- C. Shop Drawings: Submit detailed layout developed for this project and provide dimensioned location and number for each type of roof accessory.
 - 1. Submit shop drawings sealed and signed by a Professional Engineer experienced in design of this type of work and licensed in the State in which the Project is located.
- D. Warranty Documentation:
 - 1. Submit manufacturer warranty.
 - 2. Ensure that forms have been completed in Owner's name and registered with manufacturer.

1.04 DELIVERY, STORAGE, AND HANDLING

- A. See Section 017419 Construction Waste Management and Disposal for packaging waste requirements.
- B. Store products in manufacturer's unopened packaging until ready for installation.
- C. Store products under cover and elevated above grade.

1.05 WARRANTY

- A. See Section 017800 Closeout Submittals for additional warranty requirements.
- B. Manufacturer Warranty: Provide 2-year manufacturer warranty for installed products. Complete forms in Owner's name and register with manufacturer.

PART 2 PRODUCTS

2.01 ROOF CURBS

- A. Roof Curbs Manufacturers:
 - 1. AES Industries Inc: www.aescurb.com/#sle.
 - 2. The Pate Company: www.patecurbs.com/#sle.
 - 3. LMCurbs; Roof Curbs: www.lmcurbs.com/#sle.
 - 4. MKT Metal Manufacturing: www.mktduct.com/#sle.
- B. Roof Curbs Mounting Assemblies: Factory fabricated hollow sheet metal construction, internally reinforced, and capable of supporting superimposed live and dead loads and designated equipment load with fully mitered and sealed corner joints welded or mechanically fastened, and integral counterflashing with top and edges formed to shed water.
 - 1. Applications: Roof curbs used for HVAC units.
 - 2. Roof Curb Mounting Substrate: Curb substrate consists of flat roof deck sheathing with insulation.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 3. Sheet Metal Material:
 - 1) Finish: Mill finish.
- 4. Provide layouts and configurations indicated on drawings.

2.02 ROOF HATCHES AND VENTS, MANUAL AND AUTOMATIC OPERATION

- A. Roof Hatch Manufacturers:
 - 1. Activar Construction Products Group, Inc. JL Industries: www.activarcpg.com/#sle.
 - 2. Acudor Products Inc; Aluminum Roof Hatch: www.acudor.com/#sle.
 - 3. Babcock-Davis; ThermalMAX: www.babcockdavis.com/#sle.
 - 4. Bilco Company; Type TB (various types and special size): www.bilco.com/#sle.
 - 5. Nystrom, Inc: www.nystrom.com/#sle.
- B. Roof Hatches and Smoke Vents: Factory-assembled aluminum frame and cover, complete with operating and release hardware.
 - 1. Mounting Substrate: Provide frames and curbs suitable for mounting on flat roof with steel framing and decking.
 - 2. Thermally Broken Hatches: Provide insulation within frame and cover.
 - 3. Size: As indicated on drawings; single-leaf style unless otherwise indicated.
 - 4. For Ladder Access: Single leaf; 36 by 36 inches (914 by 914 mm).
- C. Frames and Curbs: One-piece curb and frame with integral cap flashing to receive roof flashings; extended bottom flange to suit mounting.
 - 1. Material: Mill finished aluminum, 11 gauge, 0.0907 inch (2.3 mm) thick.
 - 2. Insulation: Manufacturer's standard; 3 inch (76 mm) rigid polyisocyanurate, located on
 - 3. Curb Height: 8 inches (mm) from finished surface of roof, minimum.
- D. Shadow Box: Straight sections of insulated roof curbs at upper portion of Aluminum Curtain Walls. Ref. Detail 15/A-360.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Do not begin installation until substrates have been properly prepared.
- B. If substrate preparation is the responsibility of another installer, notify Architect of unsatisfactory preparation before proceeding.

3.02 PREPARATION

- A. Clean surfaces thoroughly prior to installation.
- B. Prepare surfaces using methods recommended by manufacturer for achieving acceptable results for applicable substrate under project conditions.

3.03 INSTALLATION

A. Install in accordance with manufacturer's instructions, in manner that maintains roofing system weather-tight integrity.

3.04 CLEANING

A. Clean installed work to like-new condition.

3.05 PROTECTION

- A. Protect installed products until completion of project.
- B. Touch-up, repair or replace damaged products before Date of Substantial Completion.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 079100 PREFORMED JOINT SEALS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Precompressed foam seals.

1.02 RELATED REQUIREMENTS

- A. Section 016116 Volatile Organic Compound (VOC) Content Restrictions: Emissions restrictions for joint seal adhesives and primers.
- B. Section 079200 Joint Sealants: Liquid and mastic joint sealants and their backing materials.

1.03 REFERENCE STANDARDS

1.04 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Product Data: Manufacturer's technical data sheets for each product, including chemical composition, movement capability, color availability, limitations on application, and installation instructions.
- C. Color Cards: For color selection.
- D. Samples for Color Selection: 4 inch (102 mm) long pieces of each color available; at least 2 samples of each color.
- E. Volatile Organic Content (VOC) Documentation: For adhesives and primers, submit VOC content and emissions documentation as specified in Section 016116.
- F. Manufacturer's Qualification Statement.
- G. Installer's Qualification Statement.

1.05 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum three years documented experience.
- B. Installer Qualifications: Company specializing in performing work of the type specified in this section with at least three years of documented experience.

1.06 WARRANTY

- A. See Section 017800 Closeout Submittals for additional warranty requirements.
- B. Correct defective work within a two year period after Date of Substantial Completion.
- C. Warranty: Include coverage for installed sealers that fail to achieve watertight seal or exhibit loss of adhesion or cohesion.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Precompressed Foam Seals:
 - 1. Balco, Inc: www.balcousa.com/#sle.
 - 2. EMSEAL Joint Systems, Ltd: www.emseal.com/#sle.
 - 3. Nystrom, Inc: www.nystrom.com/#sle.
 - 4. Tremco Commercial Sealants & Waterproofing: www.tremcosealants.com/#sle.
 - 5. Watson Bowman Acme Corporation: www.watsonbowmanacme.com/#sle.
 - 6. Substitutions: See Section 016000 Product Requirements.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

2.02 PRECOMPRESSED FOAM SEALS

- A. Precompressed Foam Seal: Comprised of urethane, modified-acrylic impregnated, open-cell polyurethane, or closed-cell neoprene foam impregnated with water-repellent, and with self-adhesive faces protected prior to installation by release paper.
 - 1. Color: As selected by Architect.
 - 2. Size as required to provide weathertight seal when installed.
 - 3. Calculate size according to manufacturer's recommendations.
 - 4. Measure size of existing joints before selecting seal width.
 - 5. Products:
 - a. EMSEAL Joint Systems, Ltd; DSM System: www.emseal.com/#sle. (Sika)
 - b. Willseal LLC; Willseal Color Coreseal SAF-V: www.willseal.com/#sle. (Basis of Design)

2.03 ACCESSORIES

- A. Adhesive: As recommended by seal manufacturer.
- B. Masking Tape: Self-adhesive, nonabsorbent, non-staining, removable without adhesive residue, and compatible with surfaces adjacent to joints and strip seal.
- C. Substrate Cleaner: Non-corrosive, non-staining type recommended by seal manufacturer; compatible with joint forming materials.
- D. Primer: Type recommended by seal manufacturer to suit application; non-staining.
- E. Backing Tape: Self-adhesive polyethylene tape with surface that seal will not adhere to.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that joints are ready to receive this work.
- B. Measure joint dimensions and verify that seal products are of the correct size to properly seal the joints.

3.02 PREPARATION

A. Properly prepare construction components adjacent to the work of this section to prevent damage and disfigurement due to this work.

3.03 INSTALLATION

- A. Install in accordance with manufacturer's written instructions.
- B. Precompressed Foam Seals:
 - 1. Install only when ambient temperature is within recommended application temperature range of adhesive. Consult manufacturer when installing outside this temperature range.
 - 2. Prepare joints and install seals in accordance with manufacturer's written recommendations.
 - 3. Remove loose materials and foreign matter that could impair adhesion of sealant.
 - 4. Do not stretch precompressed seal; avoid joints except at corners, ends, and intersections; install with face 1/8 to 1/4 inch (3 to 6 mm) below adjoining surface.

3.04 CLEANING

A. Clean adjacent soiled surfaces.

3.05 PROTECTION

A. Protect joints from damage until adhesives have properly cured.
50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 079200 JOINT SEALANTS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Nonsag gunnable joint sealants.
- B. Self-leveling pourable joint sealants.
- C. Joint backings and accessories.
- D. Owner-provided field quality control.

1.02 RELATED REQUIREMENTS

- A. Section 016116 Volatile Organic Compound (VOC) Content Restrictions: Additional requirements for sealants and primers.
- B. Section 079100 Preformed Joint Seals: Precompressed foam, gaskets, and strip seals.
- C. Section 092116 Gypsum Board Assemblies: Sealing acoustical and sound-rated walls and ceilings.
- D. Section 093000 Tiling: Sealant between tile and plumbing fixtures and at junctions with other materials and changes in plane.

1.03 REFERENCE STANDARDS

- A. ASTM C661 Standard Test Method for Indentation Hardness of Elastomeric-Type Sealants by Means of a Durometer; 2015 (Reapproved 2022).
- B. ASTM C794 Standard Test Method for Adhesion-in-Peel of Elastomeric Joint Sealants; 2018 (Reapproved 2022).
- C. ASTM C834 Standard Specification for Latex Sealants; 2017 (Reapproved 2023).
- D. ASTM C920 Standard Specification for Elastomeric Joint Sealants; 2018.
- E. ASTM C1087 Standard Test Method for Determining Compatibility of Liquid-Applied Sealants with Accessories Used in Structural Glazing Systems; 2023.
- F. ASTM C1193 Standard Guide for Use of Joint Sealants; 2016 (Reapproved 2023).
- G. ASTM C1248 Standard Test Method for Staining of Porous Substrate by Joint Sealants; 2022.
- H. ASTM C1521 Standard Practice for Evaluating Adhesion of Installed Weatherproofing Sealant Joints; 2019 (Reapproved 2020).
- I. ASTM D2240 Standard Test Method for Rubber Property--Durometer Hardness; 2015 (Reapproved 2021).

1.04 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Product Data: Submit manufacturer's technical datasheets for each product to be used; include the following:
 - 1. Physical characteristics, including movement capability, VOC content, hardness, cure time, and color availability.
 - 2. List of backing materials approved for use with the specific product.
 - 3. Backing material recommended by sealant manufacturer.
 - 4. Substrates that product is known to satisfactorily adhere to and with which it is compatible.
 - 5. Substrates the product should not be used on.
 - 6. Substrates for which use of primer is required.
 - 7. Installation instructions, including precautions, limitations, and recommended backing materials and tools.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 8. Sample product warranty.
- C. Product Data for Accessory Products: Submit manufacturer's technical data sheet for each product to be used, including physical characteristics, installation instructions, and recommended tools.
- D. Color Cards for Selection: Where sealant color is not specified, submit manufacturer's color cards showing standard colors available for selection.
- E. Samples for Verification: Where custom sealant color is specified, obtain directions from Architect and submit at least two physical samples for verification of color of each required sealant.
- F. Preconstruction Laboratory Test Reports: Submit at least four weeks prior to start of installation.
- G. Installation Plan: Submit at least four weeks prior to start of installation.
- H. Preinstallation Field Adhesion Test Plan: Submit at least two weeks prior to start of installation.
- I. Field Quality Control Plan: Submit at least two weeks prior to start of installation.
- J. Preinstallation Field Adhesion Test Reports: Submit filled out Preinstallation Field Adhesion Test Reports log within 10 days after completion of tests; include bagged test samples and photographic records.
- K. Installation Log: Submit filled-out log for each length or instance of sealant installed.
- L. Field Quality Control Log: Submit filled-out log for each length or instance of sealant installed, within 10 days after completion of inspections/tests; include bagged test samples and photographic records, if any.
- M. Manufacturer's qualification statement.
- N. Installer's qualification statement.
- O. Executed warranty.

1.05 QUALITY ASSURANCE

- A. Maintain one copy of each referenced document covering installation requirements on site.
- B. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum three years documented experience.
- C. Installer Qualifications: Company specializing in performing the work of this section and with at least three years of documented experience.
- D. Preconstruction Laboratory Testing: Arrange for sealant manufacturer(s) to test each combination of sealant, substrate, backing, and accessories.
 - 1. Adhesion Testing: In accordance with ASTM C794.
 - 2. Compatibility Testing: In accordance with ASTM C1087.
 - 3. Stain Testing: In accordance with ASTM C1248; required only for stone substrates.
 - 4. Allow sufficient time for testing to avoid delaying the work.
 - 5. Deliver sufficient samples to manufacturer for testing.
 - 6. Report manufacturer's recommended corrective measures, if any, including primers or techniques not indicated in product data submittals.
 - 7. Testing is not required if sealant manufacturer provides data showing previous testing, not older than 24 months, that shows satisfactory adhesion, lack of staining, and compatibility.
- E. Installation Plan: Include schedule of sealed joints, including the following:
 - 1. Joint width indicated in Contract Documents.
 - 2. Method to be used to protect adjacent surfaces from sealant droppings and smears, with acknowledgment that some surfaces cannot be cleaned to like-new condition and therefore prevention is imperative.
 - 3. Installation Log Form: Include the following data fields, with known information filled out.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- a. Unique identification of each length or instance of sealant installed.
- b. Location on project.
- c. Substrates.
- d. Sealant used.
- e. Stated movement capability of sealant.
- f. Primer to be used, or indicate no primer is used.
- g. Size and actual backing material used.
- h. Date of installation.
- i. Name of installer.
- j. Actual joint width; provide space to indicate maximum and minimum width.
- k. Actual joint depth to face of backing material at centerline of joint.
- I. Air temperature.
- F. Preinstallation Field Adhesion Test Plan: Include destructive field adhesion testing of one sample of each combination of sealant type and substrate, except interior acrylic latex sealants, and include the following for each tested sample.
 - 1. Identification of testing agency.
 - 2. Preinstallation Field Adhesion Test Log Form: Include the following data fields, with known information filled out.
 - a. Substrate; if more than one type of substrate is involved in a single joint, provide two entries on form, for testing each sealant substrate side separately.
 - b. Test date.
 - c. Location on project.
 - d. Sealant used.
 - e. Stated movement capability of sealant.
 - f. Test method used.
 - g. Date of installation of field sample to be tested.
 - h. Date of test.
 - i. Copy of test method documents.
 - j. Age of sealant upon date of testing.
 - k. Test results, modeled after the sample form in the test method document.
 - I. Indicate use of photographic record of test.
- G. Owner will employ an independent testing agency to perform the field quality control inspection and testing as referenced in PART 3 of this section and as follows, to prepare and submit the field quality control plan and log, and to provide recommendations of remedies in the case of failure.
 - 1. Contractor shall cooperate with testing agency and repair failures discovered and destructive test location damage.
- H. Field Quality Control Plan:
 - 1. Visual inspection of entire length of sealant joints.
 - 2. Nondestructive field adhesion testing of sealant joints, except interior acrylic latex sealants.
 - a. For each different sealant and substrate combination, allow for one test every 12 inches (305 mm) in the first 10 linear feet (3 linear m) of joint and one test every 24 inches (610 mm) thereafter.
 - b. If any failures occur in the first 10 linear feet (3 linear m), continue testing at 12 inches (305 mm) intervals at no extra cost to Owner.
 - 3. Destructive field adhesion testing of sealant joints, except interior acrylic latex sealant.
 - a. For each different sealant and substrate combination, allow for one test every 100 feet (30 m) in the first 1,000 linear feet (305 linear m), and one test per 1,000 linear feet (305 linear m) thereafter, or once per floor on each elevation.

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- b. If any failures occur in the first 1,000 linear feet (305 linear m), continue testing at frequency of one test per 500 linear feet (152 linear m) at no extra cost to Owner.
- 4. Field Quality Control Log Form: Show same data fields as on Preinstallation Field Adhesion Test Log, with known information filled out and lines for multiple tests per sealant/substrate combinations; include visual inspection and specified field testing; allow for possibility that more tests than minimum specified may be necessary.
- I. Field Adhesion Test Procedures:
 - 1. Allow sealants to fully cure as recommended by manufacturer before testing.
 - 2. Have a copy of the test method document available during tests.
 - 3. Record the type of failure that occurred, other information required by test method, and the information required on the Field Quality Control Log.
 - 4. When performing destructive tests, also inspect the opened joint for proper installation characteristics recommended by manufacturer, and report any deficiencies.
 - 5. Deliver the samples removed during destructive tests in separate sealed plastic bags, identified with project, location, test date, and test results, to Owner.
 - 6. If any combination of sealant type and substrate does not show evidence of minimum adhesion or shows cohesion failure before minimum adhesion, report results to Architect.
- J. Nondestructive Field Adhesion Test: Test for adhesion in accordance with ASTM C1521, using Nondestructive Spot Method.
 - 1. Record results on Field Quality Control Log.
 - 2. Repair failed portions of joints.
- K. Destructive Field Adhesion Test: Test for adhesion in accordance with ASTM C1521, using Destructive Tail Procedure.
 - 1. Sample: At least 18 inches (457 mm) long.
 - 2. Minimum Elongation Without Adhesive Failure: Consider the tail at rest, not under any elongation stress; multiply the stated movement capability of the sealant in percent by two; then multiply 1 inch (25.4 mm) by that percentage; if adhesion failure occurs before the 1-inch mark is that distance from the substrate, the test has failed.
 - 3. If either adhesive or cohesive failure occurs before minimum elongation, take necessary measures to correct conditions and retest; record each modification to products or installation procedures.
- L. Field Adhesion Tests of Joints: Test for adhesion using most appropriate method in accordance with ASTM C1521, or another applicable method as recommended by manufacturer.

1.06 WARRANTY

- A. See Section 017800 Closeout Submittals for additional warranty requirements.
- B. Manufacturer Warranty: Provide 2-year manufacturer warranty for installed sealants and accessories that fail to achieve a watertight seal, exhibit loss of adhesion or cohesion, or do not cure. Complete forms in Owner's name and register with manufacturer.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Nonsag Sealants:
 - 1. Dow: www.dow.com/#sle.
 - 2. Henry Company: www.henry.com/#sle.
 - 3. Hilti, Inc: www.hilti.com/#sle.
 - 4. Pecora Corporation: www.pecora.com/#sle.
 - 5. Sika Corporation: www.usa.sika.com/#sle.
 - 6. Tremco Commercial Sealants & Waterproofing: www.tremcosealants.com/#sle.
 - 7. W.R. Meadows, Inc: www.wrmeadows.com/#sle.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- B. Self-Leveling Sealants:
 - 1. Bostik Inc: www.bostik-us.com/#sle.
 - 2. Dow: www.dow.com/#sle.
 - 3. Pecora Corporation: www.pecora.com/#sle.
 - 4. Sika Corporation: www.usa.sika.com/#sle.
 - 5. Tremco Commercial Sealants & Waterproofing: www.tremcosealants.com/#sle.
 - 6. W.R. Meadows, Inc: www.wrmeadows.com/#sle.

2.02 JOINT SEALANT APPLICATIONS

- A. Scope:
 - 1. Exterior Joints:
 - a. Seal open joints except open joints indicated on drawings as not sealed.
 - 2. Interior Joints:
 - a. Do not seal interior joints indicated on drawings as not sealed.
 - b. Do not seal gaps and openings in suspended ceilings
 - c. Seal open joints except specific open joints indicated on drawings as not sealed.
 - 3. Do Not Seal:
 - a. Intentional weep holes in masonry.
 - b. Joints indicated to be covered with expansion joint cover assemblies.
 - c. Joints where sealant installation is specified in other sections.
- B. Exterior Joints: Use nonsag nonstaining silicone sealant, unless otherwise indicated.
 - 1. Lap Joints in Sheet Metal Fabrications: Butyl rubber, noncuring.
 - 2. Lap Joints between Manufactured Metal Panels: Butyl rubber, noncuring.
 - 3. Control and Expansion Joints in Concrete Paving: Self-leveling polyurethane traffic-grade sealant.
 - 4. Wiring Slots in Concrete Paving: Self-leveling epoxy sealant.
- C. Interior Joints: Use nonsag polyurethane sealant, unless otherwise indicated.
 - 1. Wall and Ceiling Joints in Nonwet Areas: Acrylic emulsion latex sealant.
 - 2. Wall and Ceiling Joints in Wet Areas: Nonsag polyurethane sealant for continuous liquid immersion.
 - 3. Floor Joints in Wet Areas: Self-leveling polyurethane traffic-grade sealant suitable for continuous liquid immersion.
 - 4. Joints between Tile in Wet Areas and Floors, Walls, and Ceilings: Mildew-resistant silicone sealant; .
 - 5. In Sound-Rated Assemblies: Acrylic emulsion latex sealant.
 - 6. Narrow Control Joints in Interior Concrete Slabs: Self-leveling epoxy sealant.
 - 7. Other Floor Joints: Self-leveling polyurethane traffic-grade sealant.
- D. Interior Wet Areas: Bathrooms, restrooms, kitchens, food service areas, and food processing areas; fixtures in wet areas include plumbing fixtures, food service equipment, countertops, cabinets, and other similar items.
- E. Sound-Rated Assemblies: Walls and ceilings identified as STC-rated, sound-rated, or acoustical.
- F. Preformed Joint Seals: See Section 079100 for information.

2.03 JOINT SEALANTS - GENERAL

A. Sealants and Primers: Provide products with acceptable levels of volatile organic compound (VOC) content; see Section 016116.

2.04 NONSAG JOINT SEALANTS

A. Nonstaining Silicone Sealant: ASTM C920, Grade NS, Uses M and A; not expected to withstand continuous water immersion or traffic.

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- 1. Movement Capability: Plus 100 percent and minus 50 percent, minimum.
- 2. Nonstaining to Porous Stone: Nonstaining to light-colored natural stone when tested in accordance with ASTM C1248.
- 3. Dirt Pick-Up: Reduced dirt pick-up compared to other silicone sealants.
- 4. Hardness Range: 15 to 35, Shore A, when tested in accordance with ASTM C661.
- 5. Color: To be selected by Architect from manufacturer's standard range.
- 6. Service Temperature Range: Minus 20 to 180 degrees F (Minus 29 to 82 degrees C).
- 7. Products:
 - a. Dow; DOWSIL 790 Silicone Building Sealant: www.dow.com/#sle.
 - b. Pecora Corporation; Pecora 864 NST (Non-Staining Technology): www.pecora.com/#sle.
 - c. Sika Corporation; Sikasil WS-290: www.usa.sika.com/#sle.
 - d. Tremco Commercial Sealants & Waterproofing; Spectrem 1: www.tremcosealants.com/#sle.
 - e. Substitutions: See Section 016000 Product Requirements.
- B. Mildew-Resistant Silicone Sealant: ASTM C920, Grade NS, Uses M and A; single component, mildew resistant; not expected to withstand continuous water immersion or traffic.
 - 1. Color: selected by Architect from Manufacturer's full range..
 - 2. Products:
 - a. Adfast USA Inc; ADSEAL KB 4800 Series: www.adfastcorp.com/#sle.
 - b. Everkem Diversified Products, Inc; TruSil 100: www.everkemproducts.com/#sle.
 - c. Pecora Corporation; Pecora 898 NST (Non-Staining Technology): www.pecora.com/#sle.
 - d. Sika Corporation; Sikasil GP: www.usa.sika.com/#sle.
 - e. Substitutions: See Section 016000 Product Requirements.
- C. Polyurethane Sealant: ASTM C920, Grade NS, Uses M and A; single or multi-component; not expected to withstand continuous water immersion or traffic.
 - 1. Movement Capability: Plus 100 percent, minus 50 percent, minimum.
 - 2. Hardness Range: 20 to 35, Shore A, when tested in accordance with ASTM C661.
 - 3. Color: To be selected by Architect from manufacturer's standard range.
 - 4. Service Temperature Range: Minus 40 to 180 degrees F (Minus 40 to 82 degrees C).
 - 5. Products:
 - a. Pecora Corporation; DynaTrol II: www.pecora.com/#sle.
 - b. Pecora Corporation; DynaFlex: www.pecora.com/#sle.
 - c. Sika Corporation; Sikaflex-1a: www.usa.sika.com/#sle.
 - d. Tremco Commercial Sealants & Waterproofing; Dymonic 100: www.tremcosealants.com/#sle.
- D. Polyurethane Sealant for Continuous Water Immersion: ASTM C920, Grade NS, Uses M and A; single or multicomponent; explicitly approved by manufacturer for continuous water immersion; suitable for traffic exposure when recessed below traffic surface.
 - 1. Movement Capability: Plus and minus 35 percent, minimum.
 - 2. Color: To be selected by Architect from manufacturer's standard range.
- E. Acrylic Emulsion Latex: Water-based; ASTM C834, single component, nonstaining, nonbleeding, nonsagging; not intended for exterior use.
 - 1. Color: To be selected by Architect from manufacturer's standard range.
- F. Noncuring Butyl Sealant: Solvent-based, single component, nonsag, nonskinning, nonhardening, nonbleeding; nonvapor permeable; intended for fully concealed applications.

2.05 SELF-LEVELING JOINT SEALANTS

A. Self-Leveling Polyurethane Sealant: ASTM C920, Grade P, Uses M and A; single or multicomponent; explicitly approved by manufacturer for traffic exposure; not expected to

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

withstand continuous water immersion .

- B. Self-Leveling Polyurethane Sealant for Continuous Water Immersion: Polyurethane; ASTM C920, Grade P, Uses M and A; single component; explicitly approved by manufacturer for traffic exposure and continuous water immersion.
 - 1. Movement Capability: Plus and minus 25 percent, minimum.
 - 2. Hardness Range: 35 to 55, Shore A, when tested in accordance with ASTM C661.
 - 3. Color: Gray.
 - 4. Color: To be selected by Architect from manufacturer's standard range.
- C. Flexible Polyurethane Foam: Single component, gun grade, and low-expanding.
 - 1. Color: White.
 - 2. Products:
 - a. Adfast USA Inc; Adfoam Flex 1865: www.adfastcorp.com/#sle.
 - b. Tremco Commercial Sealants & Waterproofing; ExoAir Flex Foam: www.tremcosealants.com/#sle.
- D. Semi-Rigid Self-Leveling Epoxy Joint Filler: Epoxy or epoxy/polyurethane copolymer; intended for filling cracks and control joints not subject to significant movement; rigid enough to support concrete edges under traffic.
 - 1. Composition: Multicomponent, 100 percent solids by weight.
 - 2. Durometer Hardness: Minimum of 85 for Type A or 35 for Type D, after seven days when tested in accordance with ASTM D2240.
 - 3. Color: Concrete gray.
 - 4. Joint Width, Minimum: 1/8 inch (3 mm).

2.06 ACCESSORIES

- A. Sealant Backing Materials, General: Materials placed in joint before applying sealants; assists sealant performance and service life by developing optimum sealant profile and preventing three-sided adhesion; type and size recommended by sealant manufacturer for compatibility with sealant, substrate, and application.
- B. Backing Tape: Self-adhesive polyethylene tape with surface that sealant will not adhere to and recommended by tape and sealant manufacturers for specific application.
- C. Masking Tape: Self-adhesive, nonabsorbent, nonstaining, removable without adhesive residue, and compatible with surfaces adjacent to joints and sealants.
- D. Joint Cleaner: Noncorrosive and nonstaining type, type recommended by sealant manufacturer; compatible with joint forming materials.
- E. Primers: Type recommended by sealant manufacturer to suit application; nonstaining.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that joints are ready to receive work.
- B. Verify that backing materials are compatible with sealants.
- C. Preinstallation Adhesion Testing: Install a sample for each test location indicated in the test plan.
 - 1. Test each sample as specified in PART 1 under QUALITY ASSURANCE article.
 - 2. Notify Architect of date and time that tests will be performed, at least seven days in advance.
 - 3. Record each test on Preinstallation Adhesion Test Log as indicated.
 - 4. If any sample fails, review products and installation procedures, consult manufacturer, or take other measures that are necessary to ensure adhesion; retest in a different location; if unable to obtain satisfactory adhesion, report to Architect.

LAHC – WORKFORCE	
EDUCATION RESOURCE AND	
DEVELOPMENT CENTER	

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

5. After completion of tests, remove remaining sample material and prepare joints for new sealant installation.

3.02 PREPARATION

- A. Remove loose materials and foreign matter that could impair adhesion of sealant.
- B. Clean joints, and prime as necessary, in accordance with manufacturer's instructions.
- C. Perform preparation in accordance with manufacturer's instructions and ASTM C1193.
- D. Mask elements and surfaces adjacent to joints from damage and disfigurement due to sealant work; be aware that sealant drips and smears may not be completely removable.
- E. Concrete Floor Joints That Will Be Exposed in Completed Work: Test joint filler in an inconspicuous area to verify that it does not stain or discolor slab.

3.03 INSTALLATION

- A. Install this work in accordance with sealant manufacturer's requirements for preparation of surfaces and material installation instructions.
- B. Provide joint sealant installations complying with ASTM C1193.
- C. Measure joint dimensions and size joint backers to achieve width-to-depth ratio, neck dimension, and surface bond area as recommended by manufacturer, except where specific dimensions are indicated.
- D. Install bond breaker backing tape where backer rod cannot be used.
- E. Install sealant free of air pockets, foreign embedded matter, ridges, and sags, and without getting sealant on adjacent surfaces.
- F. Do not install sealant when ambient temperature is outside manufacturer's recommended temperature range, or will be outside that range during the entire curing period, unless manufacturer's approval is obtained and instructions are followed.
- G. Nonsag Sealants: Tool surface concave, unless otherwise indicated; remove masking tape immediately after tooling sealant surface.
- H. Concrete Floor Joint Filler: After full cure, shave joint filler flush with top of concrete slab.

3.04 FIELD QUALITY CONTROL

- A. See Section 014000 Quality Requirements for additional requirements.
- B. Perform field quality control inspection/testing as specified in PART 1 under QUALITY ASSURANCE article.
- C. Non-Destructive Adhesion Testing: If there are any failures in first 100 linear feet (30 linear m), notify Architect immediately.
- D. Destructive Adhesion Testing: If there are any failures in first 1,000 linear feet (300 linear m), notify Architect immediately.
- E. Remove and replace failed portions of sealants using same materials and procedures as indicated for original installation.
- F. Repair destructive test location damage immediately after evaluation and recording of results.

END OF SECTION 079200

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 079513 EXPANSION JOINT COVER ASSEMBLIES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Expansion joint cover assemblies for Roof to Wall Joint at Connector to Bath House.

1.02 RELATED REQUIREMENTS

- A. Section 061053 Miscellaneous Rough Carpentry
- B. Section 075300 Elastomeric Membrane Roofing
- C. Section 079100 Preformed Joint Seals: Sealing expansion and control joints using preformed joint seals.
- D. Section 079200 Joint Sealants: Sealing expansion and control joints using gunnable and pourable sealants.

1.03 REFERENCE STANDARDS

- A. ASTM B221 Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes; 2021.
- B. ASTM B221M Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes (Metric); 2021.
- C. ASTM B308/B308M Standard Specification for Aluminum-Alloy 6061-T6 Standard Structural Profiles; 2020.

1.04 ADMINISTRATIVE REQUIREMENTS

A. Installation Templates: For frames and anchors to be embedded in concrete or masonry, furnish templates to relevant installers; include installation instructions and tolerances.

1.05 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Product Data: Provide joint assembly profiles, profile dimensions, anchorage devices and available colors and finish.
- C. Shop Drawings: Indicate joint and splice locations, miters, layout of the work, affected adjacent construction and anchorage locations.
- D. Samples: Submit two samples 6 in. long, illustrating profile, dimension, color, and finish selected.
- E. Manufacturer's Installation Instructions: Indicate rough-in sizes and required tolerances for item placement.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Expansion Joint Cover Assemblies:
 - 1. Construction Specialties, Inc: www.c-sgroup.com/#sle.
 - 2. EMSEAL Joint Systems, Ltd: www.emseal.com/#sle.
 - 3. Inpro: www.inprocorp.com/#sle.
 - 4. MM Systems Corp: www.mmsystemscorp.com/#sle.
 - 5. Nystrom, Inc: www.nystrom.com/#sle.
 - 6. Pecora Corporation: www.pecora.com/#sle.
 - 7. Watson Bowman Acme Corporation: www.watsonbowmanacme.com/#sle.
 - 8. Substitutions: See Section 016000 Product Requirements.

1.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

2.02 EXPANSION JOINT COVER ASSEMBLY APPLICATIONS

- A. Exterior Roof Expansion Joint Covers:
 - Manufacturers:
 - a. EMSEAL JOINT SYSTEMS. Basis of design is Roofjoint 0200 EPDM

2.03 EXPANSION JOINT COVER ASSEMBLIES

- A. Expansion Joint Cover Assemblies General: Factory-fabricated and assembled; designed to completely fill joint openings, sealed to prevent passage of air, dust, water, smoke; suitable for traffic expected.
 - 1. Joint Dimensions and Configurations: As indicated on drawings.
 - 2. Joint Cover Sizes: Selected to suit joint width and configuration, based on manufacturer's published recommendations and limitations.
 - 3. Joint Cover Styles: As indicated on drawings.
 - 4. Joint Movement Capability: If not indicated, provide minimum plus/minus 25 percent joint movement capability.
 - 5. Lengths: Provide covers in full lengths required; avoid splicing wherever possible.
 - 6. Anchors, Fasteners, and Fittings: Provided by cover manufacturer.

2.04 MATERIALS

- A. Extruded Aluminum: ASTM B221 (ASTM B221M), 6063 alloy, T6 temper; or ASTM B308/B308M, 6061 alloy, T6 temper.
 - 1. Exposed Finish Outdoors: Natural anodized.
- B. Anchors and Fasteners: As recommended by cover manufacturer.
- C. Backing Paint for Aluminum Components in Contact with Cementitious Materials: Asphaltic type.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that joint preparation and dimensions are acceptable and in accordance with manufacturer's requirements.
- B. Verify that frames and anchors installed by others are in correct locations and suitable for installation of remainder of assembly.

3.02 INSTALLATION

- A. Install components and accessories in accordance with manufacturer's instructions.
- B. Align work plumb and level, flush with adjacent surfaces.
- C. Rigidly anchor to substrate to prevent misalignment.

3.03 PROTECTION

- A. Do not permit traffic over unprotected floor joint surfaces.
- B. Provide strippable coating to protect finish surface.

END OF SECTION 079513

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 080671

DOOR HARDWARE SCHEDULE

PART 1 - GENERAL

1.1 SUMMARY

3.

- A. This Section references specification sections relating to commercial door hardware for the following:
 - 1. Swinging doors.
 - 2. Sliding Doors.
 - Other doors to the extent indicated.
- B. Commercial door hardware includes, but is not necessarily limited to, the following:
 - 1. Mechanical door hardware.
 - 2. Electromechanical and access control door hardware.
 - 3. Electromechanical and access control door hardware power supplies, back-ups and surge protection.
 - 4. Automatic operators.
 - 5. Cylinders specified for doors in other sections.
- C. Related Sections:
 - 1. Division 08 Section "Door Hardware".
 - 2. Division 26 Section "Electrical".
 - 3. Division 28 Section "Access Control".
- D. Codes and References: Comply with the version year adopted by the Authority Having Jurisdiction.
 - 1. ANSI A117.1 Accessible and Usable Buildings and Facilities.
 - 2. ICC/IBC International Building Code.
 - 3. NFPA 70 National Electrical Čode.
 - 4. NFPA 80 Fire Doors and Windows.
 - 5. NFPA 101 Life Safety Code.
 - 6. NFPA 105 Installation of Smoke Door Assemblies.
 - 7. State Building Codes, Local Amendments.
- E. Standards: Reference Related Sections for requirements regarding compliance with applicable industry standards.

1.2 SUBMITTALS

- A. Product Data: Manufacturer's product data sheets including installation details, material descriptions, dimensions of individual components and profiles, operational descriptions and finishes.
- B. Door Hardware Schedule: Prepared by or under the supervision of supplier, detailing fabrication and assembly of door hardware, as well as procedures and diagrams. Coordinate the final Door

Hardware Schedule with doors, frames, and related work to ensure proper size, thickness, hand, function, and finish of door hardware.

- 1. Format: Comply with scheduling sequence and vertical format in DHI's "Sequence and Format for the Hardware Schedule."
- 2. Organization: Organize the Door Hardware Schedule into door hardware sets indicating complete designations of every item required for each door or opening. Organize door hardware sets in same order as in the Door Hardware Sets at the end of Part 3. Submittals that do not follow the same format and order as the Door Hardware Sets will be rejected and subject to resubmission.
- 3. Content: Include the following information:
 - a. Type, style, function, size, label, hand, and finish of each door hardware item.
 - b. Manufacturer of each item.
 - c. Fastenings and other pertinent information.
 - d. Location of door hardware set, cross-referenced to Drawings, both on floor plans and in door and frame schedule.
 - e. Explanation of abbreviations, symbols, and codes contained in schedule.
 - f. Mounting locations for door hardware.
 - g. Door and frame sizes and materials.
- 4. Submittal Sequence: Submit the final Door Hardware Schedule at earliest possible date, particularly where approval of the Door Hardware Schedule must precede fabrication of other work that is critical in the Project construction schedule. Include Product Data, Samples, Shop Drawings of other work affected by door hardware, and other information essential to the coordinated review of the Door Hardware Schedule.
- C. Keying Schedule: Prepared under the supervision of the Owner, separate schedule detailing final keying instructions for locksets and cylinders in writing. Include keying system explanation, door numbers, key set symbols, hardware set numbers and special instructions. Owner to approve submitted keying schedule prior to the ordering of permanent cylinders.
- D. Product Test Reports: Indicating compliance with cycle testing requirements, based on evaluation of comprehensive tests performed by manufacturer and witnessed by a qualified independent testing agency.
- E. Operating and Maintenance Manuals: Provide manufacturers operating and maintenance manuals for each item comprising the complete door hardware installation in quantity as required in Division 01, Closeout Submittals. The manual to include the name, address, and contact information of the manufacturers providing the hardware and their nearest service representatives. The final copies delivered after completion of the installation test to include "as built" modifications made during installation, checkout, and acceptance.
- F. Warranties and Maintenance: Special warranties and maintenance agreements specified in the Related Sections.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

1.3 DELIVERY, STORAGE, AND HANDLING

- A. Inventory door hardware on receipt and provide secure lock-up and shelving for door hardware delivered to Project site. Do not store electronic access control hardware, software or accessories at Project site without prior authorization.
- B. Tag each item or package separately with identification related to the final Door Hardware Schedule, and include basic installation instructions with each item or package.
- C. Deliver, as applicable, permanent keys, cylinders, cores, access control credentials, software and related accessories directly to Owner via registered mail or overnight package service. Instructions for delivery to the Owner shall be established at the "Keying Conference".

1.4 WARRANTY

A. General Warranty: Reference Division 01, General Requirements. Special warranties specified in this Article shall not deprive Owner of other rights Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by Contractor under requirements of the Contract Documents.

1.5 MAINTENANCE SERVICE

A. Maintenance Tools and Instructions: Furnish a complete set of specialized tools and maintenance instructions as needed for Owner's continued adjustment, maintenance, and removal and replacement of door hardware.

PART 2 - PRODUCTS

2.1 SCHEDULED DOOR HARDWARE

A. Refer to "PART 3 – EXECUTION" for required specification sections.

PART 3 - EXECUTION

3.1 DOOR HARDWARE SETS

- A. The door hardware sets represent the design intent and direction of the owner and architect. They are a guideline only and should not be considered a detailed hardware schedule. Discrepancies, conflicting hardware and missing items should be brought to the attention of the architect with corrections made prior to the bidding process. Omitted items not included in a hardware set should be scheduled with the appropriate additional hardware required for proper application and functionality.
 - 1. Quantities listed are for each pair of doors, or for each single door.
 - 2. The supplier is responsible for handing and sizing all products.
 - 3. Where multiple options for a piece of hardware are given in a single line item, the supplier shall provide the appropriate application for the opening.

FRAMEWORK E, LLC PROJ. NO. 2024007

- 4. At existing openings with new hardware the supplier shall field inspect existing conditions prior to the submittal stage to verify the specified hardware will work as required. Provide alternate solutions and proposals as needed.
- B. Products listed in the hardware sets shall be supplied by and in accordance with the requirements described in the specification section as noted for each item.
 - 1. Section 08 71 00 Door Hardware.
- C. Manufacturer's Abbreviations:
 - 1. MK McKinney
 - 2. PE Pemko
 - 3. SU Securitron
 - 4. YA ASSA ABLOY ACCENTRA
 - 5. RO Rockwood
 - 6. NO Norton
 - 7. OT Other

Hardware Sets

Set: 1.0

Doors: 031

T4A3386 [NRP]	US32D	MK	087100
AU 5404LN	626	YA	087100
UNI9500	689	NO	087100
346C TKSP		ΡE	087100
2891AS x 290AS TKSP		ΡE	087100
3452CNB TKSP		ΡE	087100
279x292AFGPK MSES25SS-2		ΡE	087100
	T4A3386 [NRP] AU 5404LN UNI9500 346C TKSP 2891AS x 290AS TKSP 3452CNB TKSP 279x292AFGPK MSES25SS-2	T4A3386 [NRP] US32D AU 5404LN 626 UNI9500 689 346C TKSP 2891AS x 290AS TKSP 3452CNB TKSP 3452CNB TKSP 279x292AFGPK MSES25SS-2	T4A3386 [NRP] US32D MK AU 5404LN 626 YA UNI9500 689 NO 346C TKSP PE 2891AS x 290AS TKSP PE 3452CNB TKSP PE 279x292AFGPK MSES25SS-2 PE

Set: 2.0

Doors: 125

3 Hinge, Full Mortise, Hvy Wt	T4A3386 [NRP]	US32D	MK	087100	
1 Electric Power Transfer	EL-CEPT	630	SU	087100	4
1 Electrified Rim Exit, Fail Secure	6100ED B AU691F Less Dogging	630	YA	087100	4
1 Surface Closer	UNI9500	689	NO	087100	
1 Rain Guard	346C TKSP		ΡE	087100	
1 Gasketing	2891AS x 290AS TKSP		ΡE	087100	
1 Sweep	3452CNB TKSP		ΡE	087100	
1 Threshold	279x292AFGPK MSES25SS-2		ΡE	087100	
1 ElectroLynx Harness	QC-Cxxx LAR		MK	087100	4

Door Hardware Schedule

LAHC-WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER	50% CONSTRUCTION DOCUMENTS APRIL 11, 2025	FRAMEWO PROJ. NO	ORK E, L O. 20240	LC)07
1 ElectroLynx Harness	QC-C2500P	MK 08	37100	4
1 Position Switch (E08)	DPS-M-W	SU 08	37100	4
1 Card Reader	BY SECURITY INTEGRATOR			
1 Power Supply	AQL4-R8E1	SU 08	37100	4
1 Wiring Diagram	- Elevation and Point to Point as Specified	OT		

Notes: •Door normally closed and locked

•Unlocking of door by mechanical key alerts head end system of entry w/ out audit trail.

•Presenting proper credential unlocks outside lever/retracts latch and shunts DPS for authorized entry. •RX tied to inside push pad shunts DPS for set period of time.

•DPS alerts if door is held open longer than programmed time.

•Device is Fail Secure and remains locked upo loss of power.

•Free egress at all times.

Set: 3.0

Doors: 101

1 Continuous Hinge	CFM83SLI-1100 EL-CEPTx32D		ΡE	087100	4
1 Rim Exit Device, Nightlatch	6100ED B MELR 421F Less Dogging	630	YA	087100	4
1 Pull	RM201 Mtg-Type 12XHD	US32D- 316	RO	087100	
1 Surface Closer	PR7500 / R7500	689	NO	087100	
1 Wall Stop	400 / 441CU	US26D	RO	087100	
1 Sweep	315CN TKSP		ΡE	087100	
1 Threshold	172A		ΡE	087100	
1 ElectroLynx Harness	QC-Cxxx LAR		MK	087100	4
1 ElectroLynx Harness	QC-C2500P		MK	087100	4
1 Position Switch (E08)	DPS-M-W		SU	087100	4
1 Card Reader	BY SECURITY INTEGRATOR				
1 Power Supply	AQL4-R8E1		SU	087100	4
1 Wiring Diagram	- Elevation and Point to Point as Specified		ОТ		

Notes: Perimeter / meeting stile gasketing by Alum Door / Frame Manufacturer.

•Door normally closed and locked

•Presenting valid credential shunts DPS and retracts latch permitting pulled entry.

•Deprtessing push rail shunts DPS for authorized exit.

•Entry by manual key alerts head end to entry w/ out audit trail unless power is off.

•FD access by mech key.

•Free egress at all times.

AHC-WORKFORCE	50% CONSTRUCTION DOCUMENTS APRIL 11, 2025	FRAMEWORK E, LLC PROJ. NO. 2024007
JEVELOFIVIENT CENTER	AFRIL 11, 2025	

<u>Set: 4.0</u>

Doors: 027, 102, 108, 110, 111, 112, 113, 114, 114.A, 117

3 Hinge, Full Mortise	TA2714 [NRP]	US26D	MK	087100
1 Classroom Lock	AU 5408LN	626	YA	087100
1 Wall Stop	400 / 441CU	US26D	RO	087100
1 Gasketing	S88		PE	087100

<u>Set: 5.0</u>

Doors: 106, 123, 124

3 Hinge, Full Mortise	TA2714 [NRP]	US26D	MK	087100
1 Privacy	AU YPL02	626	YA	087100
1 Wall Stop	400 / 441CU	US26D	RO	087100
1 Gasketing	S88		ΡE	087100

<u>Set: 6.0</u>

Doors: 125.B

3 Hinge, Full Mortise	TA2714 [NRP]	US26D	MK	087100	
1 Electric Power Transfer	EL-CEPT	630	SU	087100	4
1 Fail Secure Lock	AU 5491LN REX	626	YA	087100	4
1 Surface Closer	PR7500 / R7500	689	NO	087100	
1 Wall Stop	400 / 441CU	US26D	RO	087100	
1 Gasketing	S88		PE	087100	
1 Threshold	2550A		PE	087100	
1 ElectroLynx Harness	QC-Cxxx LAR		MK	087100	4
1 ElectroLynx Harness	QC-C2500P		MK	087100	4
1 Position Switch (E08)	DPS-M-W		SU	087100	4
1 Card Reader	BY SECURITY INTEGRATOR				
1 Power Supply	AQL4-R8E1		SU	087100	4
1 Wiring Diagram	- Elevation and Point to Point as Specified		от		

Notes:

•Door normally closed and locked

•Unlocking of door by mechanical key alerts head end system of entry w/ out audit trail.

•Presenting proper credential unlocks outside lever and shunts DPS for authorized entry.

•RX tied to inside lever shunts DPS for set period of time.

•DPS alerts if door is held open longer than programmed time.

•Lock is Fail Secure.

•Free egress at all times.

EDUCATION RESOURCE AND DOCU	IMENTS FRAMEWORK E, LLC
DEVELOPMENT CENTER APRIL	PROJ. NO. 2024007

Set: 7.0

Doors: 103, 104, 105, 115

3 Hinge, Full Mortise	TA2714 [NRP]	US26D	MK	087100
1 Entry Lock	AU 5404LN	626	YA	087100
1 Wall Stop	400 / 441CU	US26D	RO	087100
1 Gasketing	S88		ΡE	087100

Set: 8.0

Doors: 036, 107, 116, 120, 121, 122

3 Hinge, Full Mortise	TA2714 [NRP]	US26D	MK	087100
1 Entry Lock	AU 5404LN	626	YA	087100
1 Wall Stop	400 / 441CU	US26D	RO	087100
1 Gasketing	S88		PE	087100

<u>Set: 9.0</u>

Doors: 125.A

3 Hinge, Full Mortise	TA2714 [NRP]	US26D	MK	087100	
1 Electric Power Transfer	EL-CEPT	630	SU	087100	4
1 Electrified Rim Exit, Fail Secure	6100ED B AU691F Less Dogging	630	YA	087100	4
1 Surface Closer	PR7500 / R7500	689	NO	087100	
1 Wall Stop	400 / 441CU	US26D	RO	087100	
1 Gasketing	S88		ΡE	087100	
1 Sweep	315CN TKSP		ΡE	087100	
1 ElectroLynx Harness	QC-Cxxx LAR		MK	087100	4
1 ElectroLynx Harness	QC-C2500P		MK	087100	4
1 Position Switch (E08)	DPS-M-W		SU	087100	4
1 Card Reader	BY SECURITY INTEGRATOR				
1 Power Supply	AQL4-R8E1		SU	087100	4
1 Wiring Diagram	- Elevation and Point to Point as Specified		ОТ		

Notes: •Door normally closed and locked

•Unlocking of door by mechanical key alerts head end system of entry w/ out audit trail.

•Presenting proper credential unlocks outside lever/retracts latch and shunts DPS for authorized entry. •RX tied to inside push pad shunts DPS for set period of time.

•DPS alerts if door is held open longer than programmed time.

•Device is Fail Secure and remains locked upo loss of power.

•Free egress at all times.

LAHC-WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

END OF SECTION 080671

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 081113 HOLLOW METAL DOORS AND FRAMES

PART 1 GENERAL

1.01 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.02 SUMMARY

- A. Section Includes:
 - 1. Standard and custom hollow metal doors and frames.
 - 2. Steel sidelight, borrowed lite and transom frames.
 - 3. Louvers installed in hollow metal doors.
 - 4. Light frames and glazing installed in hollow metal doors.
- B. Related Sections:
 - 1. Division 08 Section "Flush Wood Doors".
 - 2. Division 08 Section "Flush Wood Doors" for glass view panels in hollow metal doors and frames.
 - 3. Division 08 Section "Door Hardware".
 - 4. Division 09 Sections "Exterior Painting" and "Interior Painting" for field painting hollow metal doors and frames.
- C. Codes and References: Comply with the version year adopted by the Authority Having Jurisdiction.
 - 1. ANSI/SDI A250.8 Recommended Specifications for Standard Steel Doors and Frames.
 - 2. ANSI/SDI A250.4 Test Procedure and Acceptance Criteria for Physical Endurance for Steel Doors, Frames, Frames Anchors and Hardware Reinforcing.
 - 3. ANSI/SDI A250.6 Recommended Practice for Hardware Reinforcing on Standard Steel Doors and Frames.
 - 4. ANSI/SDI A250.10 Test Procedure and Acceptance Criteria for Prime Painted Steel Surfaces for Steel Doors and Frames.
 - 5. ANSI/SDI A250.11 Recommended Erection Instructions for Steel Frames.
 - 6. ASTM A1008 Standard Specification for Steel Sheet, Cold-Rolled, Carbon, Structural, High-Strength Low-Alloy and High-Strength Low-Alloy with Improved Formability.
 - 7. ASTM A653 Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process.
 - 8. ASTM A924 Standard Specification for General Requirements for Steel Sheet, Metallic-Coated by the Hot-Dip Process.
 - 9. ANSI/BHMA A156.115 Hardware Preparation in Steel Doors and Frames.
 - 10. ANSI/SDI 122 Installation and Troubleshooting Guide for Standard Steel Doors and Frames.
 - 11. ANSI/NFPA 80 Standard for Fire Doors and Fire Windows; National Fire Protection Association.
 - 12. ANSI/NFPA 105: Standard for the Installation of Smoke Door Assemblies.
 - 13. NFPA 252 Standard Methods of Fire Tests of Door Assemblies; National Fire Protection Association.
 - 14. UL 10C Positive Pressure Fire Tests of Door Assemblies.
 - 15. UL 1784 Standard for Air Leakage Tests of Door Assemblies.

1.03 QUALITY ASSURANCE

A. Source Limitations: Obtain hollow metal doors and frames through one source from a single manufacturer wherever possible.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- B. Quality Standard: In addition to requirements specified, furnish SDI-Certified manufacturer products that comply with ANSI/SDI A250.8, latest edition, "Recommended Specifications for Standard Steel Doors and Frames".
- C. Fire-Rated Door Assemblies: Assemblies complying with NFPA 80 that are listed and labeled by a qualified testing agency, for fire-protection ratings indicated, based on testing at positive pressure according to UL10C (neutral pressure at 40" above sill) or UL 10C.
 - 1. Oversize Fire-Rated Door Assemblies Construction: For units exceeding sizes of tested assemblies, attach construction label certifying doors are built to standard construction requirements for tested and labeled fire rated door assemblies except for size.
 - Temperature-Rise Limit: Where indicated and at vertical exit enclosures (stairwell openings) and exit passageways, provide doors that have a maximum transmitted temperature end point of not more than 450 deg F (250 deg C) above ambient after 30 minutes of standard fire-test exposure.
 - 3. Smoke Control Door Assemblies: Comply with NFPA 105.
 - a. Smoke "S" Label: Doors to bear "S" label, and include smoke and draft control gasketing applied to frame and on meeting stiles of pair doors.
- D. Fire-Rated, Borrowed-Light Frame Assemblies: Assemblies complying with NFPA 80 that are listed and labeled, by a testing and inspecting agency acceptable to authorities having jurisdiction, for fire-protection ratings indicated, based on testing according to NFPA 257. Provide labeled glazing material.
- E. Pre-Submittal Conference: Conduct conference in compliance with requirements in Division 01 Section "Project Meetings" with attendance by representatives of Supplier, Installer, and Contractor to review proper methods and procedures for installing hollow metal doors and frames and to verify installation of electrical knockout boxes and conduit at frames with electrified or access control hardware.

1.04 DELIVERY, STORAGE, AND HANDLING

- A. Deliver hollow metal work palletized, wrapped, or crated to provide protection during transit and Project site storage. Do not use non-vented plastic.
- B. Deliver welded frames with two removable spreader bars across bottom of frames, tack welded to jambs and mullions.
- C. Store hollow metal work under cover at Project site. Place in stacks of five units maximum in a vertical position with heads up, spaced by blocking, on minimum 4-inch high wood blocking. Do not store in a manner that traps excess humidity.
 - 1. Provide minimum 1/4-inch space between each stacked door to permit air circulation. Door and frames to be stacked in a vertical upright position.

1.05 PROJECT CONDITIONS

A. Field Measurements: Verify actual dimensions of openings by field measurements before fabrication.

1.06 COORDINATION

A. Coordinate installation of anchorages for hollow metal frames. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors. Deliver such items to Project site in time for installation.

1.07 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace doors that fail in materials or workmanship within specified warranty period.
- B. Warranty includes installation and finishing that may be required due to repair or replacement of defective doors.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide steel doors and frames from a SDI Certified manufacturer:
 - 1. CECO Door Products (C).
 - 2. Curries Company (CU).
 - 3. Steelcraft (S).

2.02 MATERIALS

- A. Cold-Rolled Steel Sheet: ASTM A 1008/A 1008M, Commercial Steel (CS), Type B; suitable for exposed applications.
- B. Metallic-Coated Steel Sheet: ASTM A 653/A 653M, Commercial Steel (CS), Type B; with minimum G60 (Z180) or A60 (ZF180) metallic coating.
- C. Frame Anchors: ASTM A 653/A 653M, Commercial Steel (CS), Commercial Steel (CS), Type B; with minimum G60 (Z180) or A60 (ZF180) metallic coating.

2.03 HOLLOW METAL DOORS

- A. General: Provide 1-3/4 inch doors of design indicated, not less than thickness indicated; fabricated with smooth surfaces, without visible joints or seams on exposed faces unless otherwise indicated. Comply with ANSI/SDI A250.8 and ANSI/NAAMM HMMA 867.
- B. Exterior Doors (Energy Efficient): Face sheets fabricated of commercial quality hot-dipped zinc coated steel that complies with ASTM A924 A60. Provide doors complying with requirements indicated below by referencing ANSI/SDI A250.8 for level and model, ANSI/SDI A250.4 for physical performance level, and HMMA 867 for door construction.
 - 1. Design: Flush panel.
 - 2. Core Construction: Foamed in place polyurethane and steel stiffened laminated core with no stiffener face welds, in compliance with HMMA 867 "Laminated Core".
 - a. Provide 22-gauge steel stiffeners at 6 inches on-center internally welded at 5" oncenter to integral core assembly, foamed in place polyurethane core chemically bonded to all interior surfaces. No stiffener face welding is permitted.
 - b. Thermal properties to rate at a fully operable minimum U-Factor 0.37 and R-Value 2.7, including insulated door, thermal-break frame and threshold.
 - 3. Level/Model: Level 3 and Physical Performance Level A (Extra Heavy Duty), Minimum 16 gauge (0.053 inch 1.3-mm) thick steel, Model 2.
 - 4. Vertical Edges: Vertical edges to be mechanically interlocked with hairline seam. Beveled Lock Edge, 1/8 inch in 2 inches (3 mm in 50 mm).
 - 5. Top and Bottom Edges: Reinforce tops and bottoms of doors with a continuous steel channel not less than 16 gauge, extending the full width of the door and welded to the face sheet. Doors with an inverted top channel to include a steel closure channel, screw attached, with the web of the channel flush with the face sheets of the door. Plastic or composite channel fillers are not acceptable.
 - 6. Hinge Reinforcement: Minimum 7 gauge (3/16") plate 1-1/4" x 9".
 - 7. Hardware Reinforcements: Fabricate according to ANSI/SDI A250.6 with reinforcing plates from same material as door face sheets.
- C. Interior Doors: Face sheets fabricated of commercial quality cold rolled steel that complies with ASTM A 1008/A 1008M. Provide doors complying with requirements indicated below by referencing ANSI/SDI A250.8 for level and model and ANSI/SDI A250.4 for physical performance level:
 - 1. Design: Flush panel.
 - a. Fire Door Core: As required to provide fire-protection and temperature-rise ratings indicated.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 2. Level/Model: Level 2 and Physical Performance Level B (Heavy Duty), Minimum 18 gauge (0.042-inch 1.0-mm) thick steel, Model 2.
- 3. Vertical Edges: Vertical edges to have the face sheets spot welded and filled full height with an epoxy filler. Welds are to be ground, filled and dressed smooth. Beveled Lock Edge, 1/8 inch in 2 inches (3 mm in 50 mm).
- 4. Top and Bottom Edges: Reinforce tops and bottoms of doors with a continuous steel channel not less than 16 gauge, extending the full width of the door and welded to the face sheet.
- 5. Hinge Reinforcement: Minimum 7 gauge (3/16") plate 1-1/4" x 9" or minimum 14 gauge continuous channel with pierced holes, drilled and tapped.
- 6. Hardware Reinforcements: Fabricate according to ANSI/SDI A250.6 with reinforcing plates from same material as door face sheets.
- D. Manufacturers Basis of Design:
 - 1. CECO Door Products (C) Energy Efficient Trio-E Series (exterior doors).

2.04 HOLLOW METAL FRAMES

- A. General: Comply with ANSI/SDI A250.8 and with details indicated for type and profile.
- B. Thermal Break Frames: Subject to the same compliance standards and requirements as standard hollow metal frames. Tested for thermal performance in accordance with NFRC 102, and resistance to air infiltration in accordance with NFRC 400. Where indicated provide thermally broken frame profiles available for use in both masonry and drywall construction. Fabricate with 1/16" positive thermal break and integral vinyl weatherstripping.
- C. Exterior Frames: Fabricated of hot-dipped zinc coated steel that complies with ASTM A 653/A 653M, Coating Designation A60.
 - 1. Fabricate frames with mitered or coped corners. Profile as indicated on drawings.
 - 2. Frames: Minimum 14 gauge (0.067-inch -1.7-mm) thick steel sheet.
 - 3. Manufacturers Basis of Design:
 - a. CECO Door Products (C) Thermal Break TQB Series.
- D. Interior Frames: Fabricated from cold-rolled steel sheet that complies with ASTM A 1008/A 1008M.
 - 1. Fabricate frames with mitered or coped corners. Profile as indicated on drawings.
 - 2. Frames: Minimum 16 gauge (0.053-inch -1.3-mm) thick steel sheet for door openings up to 48 inches in width.
 - 3. Frames: Minimum 14 gauge (0.067-inch -1.7-mm) thick steel sheet for door openings greater than 48 inches in width.
 - 4. Manufacturers Basis of Design:
 - a. CECO Door Products (C) DU Series.
 - b. CECO Door Products (C) SU Series.
- E. Fire rated frames: Fabricate frames in accordance with NFPA 80, listed and labeled by a qualified testing agency, for fire-protection ratings indicated.
- F. Hardware Reinforcement: Fabricate according to ANSI/SDI A250.6 Table 4 with reinforcement plates from same material as frames.

2.05 FRAME ANCHORS

- A. Jamb Anchors:
 - 1. Masonry Type: Adjustable strap-and-stirrup or T-shaped anchors to suit frame size, formed from A60 metallic coated material, not less than 0.042 inch thick, with corrugated or perforated straps not less than 2 inches wide by 10 inches long; or wire anchors not less than 0.177 inch thick.
 - 2. Stud Wall Type: Designed to engage stud and not less than 0.042 inch thick.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- B. Floor Anchors: Floor anchors to be provided at each jamb, formed from A60 metallic coated material, not less than 0.042 inches thick.
- C. Mortar Guards: Formed from same material as frames, not less than 0.016 inches thick.

2.06 LIGHT OPENINGS AND GLAZING

- A. Stops and Moldings: Provide stops and moldings around glazed lites where indicated. Form corners of stops and moldings with butted or mitered hairline joints at fabricator's shop. Fixed and removable stops to allow multiple glazed lites each to be removed independently. Coordinate frame rabbet widths between fixed and removable stops with the type of glazing and installation indicated.
- B. Moldings for Glazed Lites in Doors and Loose Stops for Glazed Lites in Frames: Minimum 20 gauge thick, fabricated from same material as door face sheet in which they are installed.
- C. Fixed Frame Moldings: Formed integral with hollow metal frames, a minimum of 5/8 inch (16 mm) high unless otherwise indicated. Provide fixed frame moldings and stops on outside of exterior and on secure side of interior doors and frames.
- D. Preformed Metal Frames for Light Openings: Manufacturer's standard frame formed of 0.048inch-thick, cold rolled steel sheet; with baked enamel or powder coated finish; and approved for use in doors of fire protection rating indicated. Match pre-finished door paint color where applicable.

2.07 ACCESSORIES

- A. Mullions and Transom Bars: Join to adjacent members by welding or rigid mechanical anchors.
- B. Grout Guards: Formed from same material as frames, not less than 0.016 inches thick.

2.08 FABRICATION

- A. Fabricate hollow metal work to be rigid and free of defects, warp, or buckle. Accurately form metal to required sizes and profiles, with minimum radius for thickness of metal. Where practical, fit and assemble units in manufacturer's plant. When shipping limitations so dictate, frames for large openings are to be fabricated in sections for splicing or splining in the field by others.
- B. Tolerances: Fabricate hollow metal work to tolerances indicated in ANSI/SDI A250.8.
- C. Hollow Metal Doors:
 - 1. Exterior Doors: Provide optional weep-hole openings in bottom of exterior doors to permit moisture to escape where specified.
 - 2. Glazed Lites: Factory cut openings in doors with applied trim or kits to fit. Factory install glazing where indicated.
 - 3. Astragals: Provide overlapping astragals as noted in door hardware sets in Division 08 Section "Door Hardware" on one leaf of pairs of doors where required by NFPA 80 for fireperformance rating or where indicated. Extend minimum 3/4 inch beyond edge of door on which astragal is mounted.
 - 4. Continuous Hinge Reinforcement: Provide welded continuous 12 gauge strap for continuous hinges specified in hardware sets in Division 08 Section "Door Hardware".
- D. Hollow Metal Frames:
 - 1. Shipping Limitations: Where frames are fabricated in sections due to shipping or handling limitations, provide alignment plates or angles at each joint, fabricated of same thickness metal as frames.
 - 2. Welded Frames: Weld flush face joints continuously; grind, fill, dress, and make smooth, flush, and invisible.
 - a. Welded frames are to be provided with two steel spreaders temporarily attached to the bottom of both jambs to serve as a brace during shipping and handling. Spreader bars are for bracing only and are not to be used to size the frame opening.

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- 3. Sidelight and Transom Bar Frames: Provide closed tubular members with no visible face seams or joints, fabricated from same material as door frame. Fasten members at crossings and to jambs by butt welding.
- 4. High Frequency Hinge Reinforcement: Provide high frequency hinge reinforcements at door openings 48-inches and wider with mortise butt type hinges at top hinge locations.
- 5. Continuous Hinge Reinforcement: Provide welded continuous 12 gauge straps for continuous hinges specified in hardware sets in Division 08 Section "Door Hardware".
- 6. Provide countersunk, flat- or oval-head exposed screws and bolts for exposed fasteners unless otherwise indicated for removable stops, provide security screws at exterior locations.
- 7. Mortar Guards: Provide guard boxes at back of hardware mortises in frames at all hinges and strike preps regardless of grouting requirements.
- 8. Floor Anchors: Weld anchors to bottom of jambs and mullions with at least four spot welds per anchor.
- 9. Jamb Anchors: Provide number and spacing of anchors as follows:
 - a. Masonry Type: Locate anchors not more than 18 inches from top and bottom of frame. Space anchors not more than 32 inches o.c. and as follows:
 - 1) Two anchors per jamb up to 60 inches high.
 - 2) Three anchors per jamb from 60 to 90 inches high.
 - 3) Four anchors per jamb from 90 to 120 inches high.
 - 4) Four anchors per jamb plus 1 additional anchor per jamb for each 24 inches or fraction thereof above 120 inches high.
 - b. Stud Wall Type: Locate anchors not more than 18 inches from top and bottom of frame. Space anchors not more than 32 inches o.c. and as follows:
 - 1) Three anchors per jamb up to 60 inches high.
 - 2) Four anchors per jamb from 60 to 90 inches high.
 - 3) Five anchors per jamb from 90 to 96 inches high.
 - 4) Five anchors per jamb plus 1 additional anchor per jamb for each 24 inches or fraction thereof above 96 inches high.
 - 5) Two anchors per head for frames above 42 inches wide and mounted in metal stud partitions.
- Door Silencers: Except on weatherstripped or gasketed doors, drill stops to receive door silencers. Silencers to be supplied by frame manufacturer regardless if specified in Division 08 Section "Door Hardware".
- 11. Bituminous Coating: Where frames are fully grouted with an approved Portland Cement based grout or mortar, coat inside of frame throat with a water based bituminous or asphaltic emulsion coating to a minimum thickness of 3 mils DFT, tested in accordance with UL 10C and applied to the frame under a 3rd party independent follow-up service procedure.
- E. Hardware Preparation: Factory prepare hollow metal work to receive template mortised hardware; include cutouts, reinforcement, mortising, drilling, and tapping according to the Door Hardware Schedule and templates furnished as specified in Division 08 Section "Door Hardware."
 - 1. Locate hardware as indicated, or if not indicated, according to ANSI/SDI A250.8.
 - 2. Reinforce doors and frames to receive non-template, mortised and surface mounted door hardware.
 - 3. Comply with applicable requirements in ANSI/SDI A250.6 and ANSI/DHI A115 Series specifications for preparation of hollow metal work for hardware.
 - 4. Coordinate locations of conduit and wiring boxes for electrical connections with Division 26 Sections.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

2.09 STEEL FINISHES

- A. Prime Finishes: Doors and frames to be cleaned, and chemically treated to insure maximum finish paint adhesion. Surfaces of the door and frame exposed to view to receive a factory applied coat of rust inhibiting shop primer.
 - 1. Shop Primer: Manufacturer's standard, fast-curing, lead and chromate free primer complying with ANSI/SDI A250.10 acceptance criteria; recommended by primer manufacturer for substrate; and compatible with substrate and field-applied coatings.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. General Contractor to verify the accuracy of dimensions given to the steel door and frame manufacturer for existing openings or existing frames (strike height, hinge spacing, hinge back set, etc.).
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.02 PREPARATION

- A. Remove welded in shipping spreaders installed at factory. Restore exposed finish by grinding, filling, and dressing, as required to make repaired area smooth, flush, and invisible on exposed faces.
- B. Prior to installation, adjust and securely brace welded hollow metal frames for square, level, twist, and plumb condition.
- C. Tolerances shall comply with SDI-117 "Manufacturing Tolerances Standard Steel Doors and Frames."
- D. Drill and tap doors and frames to receive non-template, mortised, and surface-mounted door hardware.
- E. Verify tolerances against manufacturers installations instructions for tornado and hurricane storm shelter openings.

3.03 INSTALLATION

- A. General: Install hollow metal work plumb, rigid, properly aligned, and securely fastened in place; comply with Drawings and manufacturer's written instructions.
- B. Hollow Metal Frames: Install hollow metal frames of size and profile indicated. Comply with ANSI/SDI A250.11 and NFPA 80 at fire rated openings.
 - 1. Set frames accurately in position, plumbed, leveled, aligned, and braced securely until permanent anchors are set. After wall construction is complete and frames properly set and secured, remove temporary braces, leaving surfaces smooth and undamaged. Shim as necessary to comply with installation tolerances.
 - 2. Floor Anchors: Provide floor anchors for each jamb and mullion that extends to floor, and secure with post-installed expansion anchors.
 - 3. Masonry Walls: Coordinate installation of frames to allow for solidly filling space between frames and masonry with mortar.
 - 4. Grout Requirements: Do not grout head of frames unless reinforcing has been installed in head of frame. Do not grout vertical or horizontal closed mullion members.
- C. Hollow Metal Doors: Fit hollow metal doors accurately in frames, within clearances specified below. Shim as necessary.
 - 1. Non-Fire-Rated Standard Steel Doors:
 - a. Jambs and Head: 1/8 inch plus or minus 1/16 inch.
 - b. Between Edges of Pairs of Doors: 1/8 inch plus or minus 1/16 inch.
 - c. Between Bottom of Door and Top of Threshold: Maximum 3/8 inch.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- d. Between Bottom of Door and Top of Finish Floor (No Threshold): Maximum 3/4 inch.
- 2. Fire-Rated Doors: Install doors with clearances according to NFPA 80.
- D. Field Glazing: Comply with installation requirements in Division 08 Section "Glazing" and with hollow metal manufacturer's written instructions.

3.04 ADJUSTING AND CLEANING

- A. Final Adjustments: Check and readjust operating hardware items immediately before final inspection. Leave work in complete and proper operating condition. Remove and replace defective work, including hollow metal work that is warped, bowed, or otherwise unacceptable.
- B. Remove grout and other bonding material from hollow metal work immediately after installation.
- C. Prime-Coat and Painted Finish Touchup: Immediately after erection, sand smooth rusted or damaged areas of prime coat, or painted finishes, and apply touchup of compatible air drying, rust-inhibitive primer, zinc rich primer (exterior and galvanized openings) or finish paint.

3.05 FIELD QUALITY CONTROL

- A. Field Inspection (Punch Report): Reference Division 01 Sections "Closeout Procedures". Produce project punch report for each installed door opening indicating compliance with approved submittals and verification hardware is properly installed, operating and adjusted. Include list of items to be completed and corrected, indicating the reasons or deficiencies causing the Work to be incomplete or rejected.
 - 1. Organization of List: Include separate Door Opening and Deficiencies and Corrective Action Lists organized by Mark, Opening Remarks and Comments, and related Opening Images and Video Recordings.

END OF SECTION 081113

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 081416 FLUSH WOOD DOORS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Flush wood doors; flush and flush glazed configuration; fire-rated and non-rated.

1.02 RELATED REQUIREMENTS

- A. Section 081113 Hollow Metal Doors and Frames.
- B. Section 088000 Glazing.

1.03 REFERENCE STANDARDS

- A. ASTM C1048 Standard Specification for Heat-Strengthened and Fully Tempered Flat Glass; 2018.
- B. AWI/AWMAC/WI (AWS) Architectural Woodwork Standards, 2nd Edition; 2014, with Errata (2016).
- C. AWMAC/WI (NAAWS) North American Architectural Woodwork Standards; 2021, with Errata.
- D. NFPA 80 Standard for Fire Doors and Other Opening Protectives; 2025.
- E. NFPA 105 Standard for Smoke Door Assemblies and Other Opening Protectives; 2025.
- F. UL 10C Standard for Positive Pressure Fire Tests of Door Assemblies; Current Edition, Including All Revisions.

1.04 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Product Data: Indicate door core materials and construction; veneer species, type and characteristics.
- C. Shop Drawings: Show doors and frames, elevations, sizes, types, swings, undercuts, beveling, blocking for hardware, factory machining, factory finishing, cutouts for glazing and other details.
- D. Samples: Submit two samples of door veneer, 12 in. by 12 in. in size illustrating wood grain, stain color, and sheen.

1.05 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section, with not less than three years of documented experience.
 - 1. Company with at least one project within past five years with value of woodwork within at least 20 percent of cost of woodwork for this project.
 - 2. Accredited participant in the specified certification program prior to the commencement of fabrication and throughout the duration of the project.
- B. Installer Qualifications: Company specializing in performing work of the type specified in this section, with not less than three years of documented experience.

1.06 DELIVERY, STORAGE, AND HANDLING

- A. Package, deliver and store doors in accordance with specified quality standard.
- B. Accept doors on site in manufacturer's packaging, and inspect for damage.
- C. Protect doors with resilient packaging sealed with heat shrunk plastic; do not store in damp or wet areas or areas where sunlight might bleach veneer; seal top and bottom edges with tinted sealer if stored more than one week, and break seal on site to permit ventilation.

1.07 WARRANTY

A. See Section 017800 - Closeout Submittals for additional warranty requirements.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Wood Veneer Faced Doors:
 - 1. Haley Brothers: www.haleybros.com/#sle.
 - 2. Horton Automatics, a division of Overhead Door Corporation; FlexBarn: www.overheaddoor.com/#sle.
 - 3. Krieger Specialty Products: www.kriegerproducts.com/#sle.
 - 4. Masonite Architectural; Aspiro Select Wood Veneer Doors: www.architectural.masonite.com/#sle.
 - 5. Oregon Door: www.oregondoor.com/#sle.
 - 6. VT Industries. Inc: www.vtindustries.com/#sle.
 - 7. Substitutions: See Section 016000 Product Requirements.

2.02 DOORS

- A. Doors: See drawings for locations and additional requirements.
 - 1. Quality Standard: Premium Grade, Heavy Duty performance, in accordance with AWI/AWMAC/WI (AWS), unless noted otherwise.
 - 2. Wood Veneer Faced Doors: 5 or 7 ply unless otherwise indicated.
- B. Interior Doors: 1-3/4 inches (44 mm) thick unless otherwise indicated; flush construction.
 - 1. Provide solid core doors at each location.
 - 2. Fire Rated Doors: Tested to ratings indicated on drawings in accordance with UL 10C -Positive Pressure; Underwriters Laboratories Inc (UL) or Intertek/Warnock Hersey (WHI) labeled without any visible seals when door is open.
 - 3. Wood veneer facing with factory transparent finish.

2.03 DOOR AND PANEL CORES

- A. Non-Rated Solid Core and 20 Minute Rated Doors: Type staved lumber core (SLC), plies and faces as indicated.
- B. Fire-Rated Doors: Mineral core type, with fire resistant composite core (FD), plies and faces as indicated above; with core blocking as required to provide adequate anchorage of hardware without through-bolting.

2.04 DOOR FACINGS

- A. Veneer Facing for Transparent Finish: White birch, veneer grade in accordance with quality standard indicated, rift cut, with slip match between leaves of veneer, running match of spliced veneer leaves assembled on door or panel face.
- B. Veneer Facing for Opaque Finish: Closed grain hardwood veneer, in compliance with indicated quality standard.

2.05 DOOR CONSTRUCTION

- A. Fabricate doors in accordance with door quality standard specified.
- B. Cores Constructed with stiles and rails bonded to core, then entire unit abrasive planed before veneering:
 - 1. Provide solid blocks at lock edge for hardware reinforcement.
 - 2. Provide solid blocking for other throughbolted hardware.
- C. Glazed Openings: Non-removable stops on non-secure side; sizes and configurations as indicated on drawings.
- D. Factory machine doors for hardware other than surface-mounted hardware, in accordance with hardware requirements and dimensions.
- E. Factory fit doors for frame opening dimensions identified on shop drawings, with edge clearances in accordance with specified quality standard.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 1. Exception: Doors to be field finished.
- F. Provide edge clearances in accordance with the quality standard specified.

2.06 FINISHES - WOOD VENEER DOORS

- A. Finish work in accordance with AWI/AWMAC/WI (AWS), Section 5 Finishing for grade specified and as follows:
 - 1. Transparent:
 - a. System 11, Polyurethane, Catalyzed.
 - b. Sheen: Satin.

2.07 ACCESSORIES

- A. Hollow Metal Doors and Frames: See Section 081113.
- B. Wood Louvers:
 - 1. Material and Finish: species and finish compatible with door facings.
- C. Glazed Openings:
 - 1. Heat-Strengthened and Fully Tempered Glass: ASTM C1048.
 - 2. Glazing: Single vision units, 1/4 inch (6.4 mm) thick glass.
 - 3. Tint: Clear.
- D. Door Window Frames: Door window frames with glazing securely fastened within door opening.
 - 1. Size: As indicated on drawings.
- E. Glazing Stops: Wood, of same species as door facing, corners; prepared for countersink style tamper proof screws.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify existing conditions before starting work.
- B. Verify that opening sizes and tolerances are acceptable.
- C. Do not install doors in frame openings that are not plumb or are out-of-tolerance for size or alignment.

3.02 INSTALLATION

- A. Install doors in accordance with manufacturer's instructions and specified quality standard.
 - 1. Install fire-rated doors in accordance with NFPA 80 requirements.
 - 2. Install smoke and draft control doors in accordance with NFPA 105 requirements.
- B. Factory-Finished Doors: Do not field cut or trim; if fit or clearance is not correct, replace door.
- C. Use machine tools to cut or drill for hardware.
- D. Coordinate installation of doors with installation of frames and hardware.
- E. Coordinate installation of glazing.
- F. Install door louvers plumb and level.

3.03 TOLERANCES

- A. Comply with specified quality standard for fit and clearance tolerances.
- B. Comply with specified quality standard for telegraphing, warp, and squareness.

3.04 ADJUSTING

- A. Adjust doors for smooth and balanced door movement.
- B. Adjust closers for full closure.

END OF SECTION 081416

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 083100 ACCESS DOORS AND PANELS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Wall- and ceiling-mounted access units.

1.02 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Product Data: Provide sizes, types, finishes, hardware, scheduled locations, and details of adjoining work.
- C. Shop Drawings: Indicate exact position of each access door and/or panel unit.
- D. Manufacturer's Installation Instructions: Indicate installation requirements.

1.03 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum three years documented experience.
- B. Installer Qualifications: Company specializing in performing work of the type specified and with at least three years documented experience.

PART 2 PRODUCTS

2.01 WALL- AND CEILING-MOUNTED ACCESS UNITS

- A. Manufacturers:
 - 1. Activar Construction Products Group, Inc. JL Industries: www.activarcpg.com/#sle.
 - 2. ACUDOR Products Inc: www.acudor.com/#sle.
 - 3. Babcock-Davis: www.babcockdavis.com/#sle.
 - 4. BAUCO Access Panel Solutions Inc: www.accesspanelsolutions.com/#sle.
 - 5. Best Access Doors: www.bestaccessdoors.com/#sle.
 - 6. Cendrex, Inc: www.cendrex.com/#sle.
 - 7. FF Systems, Inc: www.ffsystemsinc.com/#sle.
 - 8. Karp Associates, Inc: www.karpinc.com/#sle.
 - 9. Nystrom, Inc; HVAC Access Doors: www.nystrom.com/#sle.
 - 10. The Williams Brothers Corporation of America; DWAL412 Series Hidden Panels: www.wbdoors.com/#sle.
- B. Wall- and Ceiling-Mounted Units: Factory-fabricated door and frame, fully assembled units with corner joints welded, filled and ground flush; square and without rack or warp; coordinate requirements with type of installation assembly being used for each unit.
 - 1. Material: Steel, hot-dipped zinc or zinc-aluminum-alloy coated.
 - 2. Style: Frame concealed by door panel.
 - 3. Door Style: Single thickness with rolled or turned in edges.
 - 4. Size: 2'-0" x 2'-0" unless noted otherwise.
 - 5. Frames: 16-gauge, 0.0598-inch (1.52 mm) minimum thickness.
 - 6. Steel Finish: Primed.
 - 7. Hardware:
 - a. Hinges for Non-Fire-Rated Units: Concealed, constant force closure spring type.
 - b. Handle: No handle.
 - c. Latch/Lock: Screw driver slot for quarter turn cam latch.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that rough openings are correctly sized and located.

B. Begin installation only after substrates have been properly prepared, and if the responsibility of another installer, notify Architect of unsatisfactory preparation before proceeding.

3.02 PREPARATION

- A. Clean surfaces thoroughly prior to proceeding with this work.
- B. Prepare surfaces using methods recommended by manufacturer for applicable substrates in accordance with project conditions.

3.03 INSTALLATION

- A. Install units in accordance with manufacturer's instructions.
- B. Install frames plumb and level in openings, and secure units rigidly in place.
- C. Position units to provide convenient access to concealed equipment when necessary.

END OF SECTION 083100

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 084313 ALUMINUM-FRAMED STOREFRONTS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Aluminum-framed storefront, with vision glass.
- B. Aluminum doors and frames.
- C. Weatherstripping.

1.02 RELATED REQUIREMENTS

- A. Section 072500 Weather Barriers: Sealing framing to water-resistive barrier installed on adjacent construction.
- B. Section 079200 Joint Sealants: Sealing joints between frames and adjacent construction.
- C. Section 087100 Door Hardware: Hardware items other than specified in this section.
- D. Section 088000 Glazing: Glass and glazing accessories.

1.03 REFERENCE STANDARDS

- A. AAMA CW-10 Care and Handling of Architectural Aluminum from Shop to Site; 2015.
- B. AAMA 501.2 Quality Assurance and Diagnostic Water Leakage Field Check of Installed Storefronts, Curtain Walls, and Sloped Glazing Systems; 2015.
- C. AAMA 503 Voluntary Specification for Field Testing of Newly Installed Storefronts, Curtain Walls and Sloped Glazing Systems; 2014.
- D. AAMA 611 Specification for Anodized Architectural Aluminum; 2024.
- E. AAMA 1503 Voluntary Test Method for Thermal Transmittance and Condensation Resistance of Windows, Doors and Glazed Wall Sections; 2009.
- F. ASCE 7 Minimum Design Loads and Associated Criteria for Buildings and Other Structures; Most Recent Edition Cited by Referring Code or Reference Standard.
- G. ASTM B221 Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes; 2021.
- H. ASTM B221M Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes (Metric); 2021.
- I. ASTM E283/E283M Standard Test Method for Determining Rate of Air Leakage Through Exterior Windows, Skylights, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen; 2019.
- J. ASTM E330/E330M Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference; 2014 (Reapproved 2021).
- K. ASTM E1105 Standard Test Method for Field Determination of Water Penetration of Installed Exterior Windows, Skylights, Doors, and Curtain Walls, by Uniform or Cyclic Static Air Pressure Difference; 2015 (Reapproved 2023).

1.04 ADMINISTRATIVE REQUIREMENTS

- A. Coordinate with installation of other components that comprise the exterior enclosure.
- B. Preinstallation Meeting: Conduct a preinstallation meeting one week before starting work of this section; require attendance by all affected installers.

1.05 SUBMITTALS

A. See Section 013000 - Administrative Requirements for submittal procedures.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- B. Product Data: Provide component dimensions, describe components within assembly, anchorage and fasteners, glass and infill, door hardware, and internal drainage details.
- C. Shop Drawings: Indicate system dimensions, framed opening requirements and tolerances, affected related work, expansion and contraction joint location and details, and field welding required, signed and sealed by a Structural Engineer licensed in the state in which The Work is being performed.
 - 1. Include design engineer's stamp or seal on shop drawings for attachments and anchors.
- D. Samples: Submit two samples illustrating finished aluminum surface, glass, infill panels, glazing materials.
- E. Design Data: Provide framing member structural and physical characteristics, engineering calculations, and dimensional limitations.
- F. Hardware Schedule: Complete itemization of each item of hardware to be provided for each door, cross-referenced to door identification numbers in Contract Documents.
- G. Field Quality Control Submittals: Report of field testing for water penetration and air leakage.
- H. Designer's qualification statement.
- I. Manufacturer's qualification statement.
- J. Installer's qualification statement.
- K. Specimen warranty.

1.06 QUALITY ASSURANCE

- A. Designer Qualifications: Design structural support framing components under direct supervision of a Professional Structural Engineer experienced in design of this Work and licensed in the State in which the Project is located.
- B. Manufacturer Qualifications: Company specializing in performing work of type specified and with at least three years of documented experience.
 - 1. Provide certified glass products through ANSI accredited certifications that include plant audits and independent laboratory performance testing.
- C. Installer Qualifications: Company specializing in performing work of type specified and with at least three years of documented experience.
 - 1. Provide company, field supervisors, and installers that hold active ANSI accredited certifications in appropriate categories for work specified.

1.07 MOCK-UPS

- A. See Section 014000 Quality Requirements for additional requirements.
- B. Construct mock-up, to review seals, inside and outside corner units, and adjacent flashing to units..

1.08 DELIVERY, STORAGE, AND HANDLING

- A. Handle products of this section in accordance with AAMA CW-10.
- B. Protect finished aluminum surfaces with wrapping. Do not use adhesive papers or sprayed coatings that bond to aluminum when exposed to sunlight or weather.

1.09 FIELD CONDITIONS

A. Do not install sealants when ambient temperature is less than 40 degrees F (5 degrees C). Maintain this minimum temperature during and 48 hours after installation.

1.10 WARRANTY

- A. See Section 017800 Closeout Submittals for additional warranty requirements.
- B. Correct defective Work within a five year period after Date of Substantial Completion.

0% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- C. Provide five year manufacturer warranty against failure of glass seal on insulating glass units, including interpane dusting or misting. Include provision for replacement of failed units.
- D. Provide five year manufacturer warranty against excessive degradation of exterior finish. Include provision for replacement of units with excessive fading, chalking, or flaking.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Aluminum-Framed Storefronts:
 - 1. Arcadia, Inc: www.arcadiainc.com/#sle.
 - 2. Kawneer North America: www.kawneer.com/#sle.
 - 3. Oldcastle BuildingEnvelope: www.oldcastlebe.com/#sle.
 - 4. Tubelite, IncT14000: www.tubeliteinc.com/#sle. Basis of Design.
 - 5. Trulite Glass & Aluminum Solutions, LLC: www.trulite.com/#sle.
 - 6. Substitutions: See Section 016000 Product Requirements.

2.02 BASIS OF DESIGN -- SWINGING DOORS

- A. Medium Stile, Insulating Glazing, Thermally-Broken:
 - 1. Thickness: 1-3/4 inches (43 mm).

2.03 ALUMINUM-FRAMED STOREFRONT

- A. Aluminum-Framed Storefront: Factory fabricated, factory finished aluminum framing members with infill, and related flashings, anchorage and attachment devices.
 - 1. Glazing Position: Centered (front to back) at 4 1/2" portions and front set at 6 1/2" sections.
 - 2. Finish: Class I color anodized.
 - a. Factory finish all surfaces that will be exposed in completed assemblies.
 - 3. Finish Color: Extra Dark Bronze.
 - 4. Fabrication: Joints and corners flush, hairline, and weatherproof, accurately fitted and secured; prepared to receive anchors and hardware; fasteners and attachments concealed from view; reinforced as required for imposed loads.
 - 5. Construction: Eliminate noises caused by wind and thermal movement, prevent vibration harmonics, and prevent "stack effect" in internal spaces.
 - 6. System Internal Drainage: Drain to the exterior by means of a weep drainage network any water entering joints, condensation occurring in glazing channel, and migrating moisture occurring within system.
 - 7. Expansion/Contraction: Provide for expansion and contraction within system components caused by cycling temperature range of 170 degrees F (95 degrees C) over a 12 hour period without causing detrimental effect to system components, anchorages, and other building elements.
 - 8. Movement: Allow for movement between storefront and adjacent construction, without damage to components or deterioration of seals.
 - 9. Perimeter Clearance: Minimize space between framing members and adjacent construction while allowing expected movement.
 - 10. Maintain continuous air barrier and/or vapor retarder seal throughout assembly, primarily in line with inside pane of glazing and inner sheet of infill panel, and heel bead of glazing compound.
- B. Performance Requirements
 - 1. Wind Loads: Design and size components to withstand the specified load requirements without damage or permanent set, when tested in accordance with ASTM E330/E330M, using loads 1.5 times the design wind loads and 10 second duration of maximum load.
 - a. Design Wind Loads: Comply with requirements of ASCE 7.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- b. Member Deflection: Limit member deflection to flexure limit of glass in any direction, with full recovery of glazing materials.
- Air Leakage: 0.06 cfm/sq ft (0.3 L/sec sq m) maximum leakage of storefront wall area when tested in accordance with ASTM E283/E283M at 1.57 psf (75 Pa) pressure difference.
- 3. Condensation Resistance Factor of Framing: 50, minimum, measured in accordance with AAMA 1503.

2.04 COMPONENTS

- A. Aluminum Framing Members: Tubular aluminum sections, thermally broken with interior section insulated from exterior, drainage holes and internal weep drainage system.
 - 1. Glazing Stops: Flush.
 - 2. Structurally Reinforced Members: Extruded aluminum with internal reinforcement of structural steel member.
- B. Glazing: See Section 088000.
- C. Swing Doors: Glazed aluminum.
 - 1. Thickness: 1-3/4 inches (43 mm).
 - 2. Top Rail: 4 inches (100 mm) wide.
 - 3. Vertical Stiles: 4-1/2 inches (115 mm) wide.
 - 4. Bottom Rail: 10 inches (254 mm) wide.
 - 5. Finish: Same as storefront.

2.05 MATERIALS

- A. Extruded Aluminum: ASTM B221 (ASTM B221M).
- B. Fasteners: Stainless steel.
- C. Glazing Gaskets: Type to suit application to achieve weather, moisture, and air infiltration requirements.

2.06 FINISHES

- A. Class I Color Anodized Finish: AAMA 611 AA-M12C22A44 Electrolytically deposited colored anodic coating not less than 0.7 mils (0.018 mm) thick.
- B. Touch-Up Materials: As recommended by coating manufacturer for field application.

2.07 HARDWARE

- A. For each door, include weatherstripping, sill sweep strip, and threshold.
- B. Other Door Hardware: See Section 087100.
- C. Weatherstripping: Wool pile, continuous and replaceable; provide on all doors.
- D. Sill Sweep Strips: Resilient seal type, retracting, of neoprene; provide on all doors.
- E. Threshold: Extruded aluminum, one piece per door opening, ribbed surface; provide on all doors.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify dimensions, tolerances, and method of attachment with other work.
- B. Verify that storefront wall openings and adjoining water-resistive and/or air barrier seal materials are ready to receive work of this section.

3.02 INSTALLATION

- A. Install wall system in accordance with manufacturer's instructions.
- B. Attach to structure to permit sufficient adjustment to accommodate construction tolerances and other irregularities.
FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- C. Provide alignment attachments and shims to permanently fasten system to building structure.
- D. Align assembly plumb and level, free of warp or twist. Maintain assembly dimensional tolerances.
- E. Provide thermal isolation where components penetrate or disrupt building insulation.
- F. Install sill flashings. Turn up ends and edges; seal to adjacent work to form water tight dam.
- G. Where fasteners penetrate sill flashings, make watertight by seating and sealing fastener heads to sill flashing.
- H. Pack fibrous insulation in shim spaces at perimeter of assembly to maintain continuity of thermal barrier.
- I. Set thresholds in bed of sealant and secure.
- J. Touch-up minor damage to factory applied finish; replace components that cannot be satisfactorily repaired.

3.03 TOLERANCES

- A. Maximum Variation from Plumb: 0.06 inch per 3 feet (1.5 mm per m) non-cumulative or 0.06 inch per 10 feet (1.5 mm per 3 m), whichever is less.
- B. Maximum Misalignment of Two Adjoining Members Abutting in Plane: 1/32 inch (0.8 mm).

3.04 FIELD QUALITY CONTROL

- A. See Section 014000 Quality Requirements for independent field testing and inspection requirements, and requirements for monitoring quality of specified product installations.
- B. Water-Spray Test: Provide water spray quality test of installed storefront components in accordance with AAMA 501.2 during construction process and before installation of interior finishes.
 - 1. Perform a minimum of two tests in each designated area as indicated on drawings.
 - 2. Conduct tests in each area prior to 10 percent and 50 percent completion of this work.
- C. Provide field testing of installed storefront system by independent laboratory in accordance with AAMA 503 during construction process and before installation of interior finishes.
 - 1. Perform a minimum of two tests in each designated area as indicated on drawings.
 - 2. Conduct tests in each area prior to 10 percent and 50 percent completion of this work.
 - 3. Field test for water penetration in accordance with ASTM E1105 with uniform static air pressure difference (Procedure A) not less than 4.18 psf (200 Pa).
 - a. Maximum allowable rate of water penetration in 15-minute test is 0.5 ounce (14 gram) that is not contained in an area with provisions to drain to exterior, or collected on surface of interior horizontal framing member.
- D. Repair or replace storefront components that have failed designated field testing, and retest to verify performance complies with specified requirements.

3.05 ADJUSTING

A. Adjust operating hardware and sash for smooth operation.

3.06 CLEANING

- A. Remove protective material from pre-finished aluminum surfaces.
- B. Wash down surfaces with a solution of mild detergent in warm water, applied with soft, clean wiping cloths, and take care to remove dirt from corners and to wipe surfaces clean.

3.07 PROTECTION

A. Protect installed products from damage until Date of Substantial Completion.

END OF SECTION 084313

FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 084435 PROTECTIVE FRAMED GLAZING ASSEMBLIES

PART 1 GENERAL

1.01 REFERENCE STANDARDS

- A. AAMA CW-10 Care and Handling of Architectural Aluminum from Shop to Site; 2015.
- B. AAMA 501.2 Quality Assurance and Diagnostic Water Leakage Field Check of Installed Storefronts, Curtain Walls, and Sloped Glazing Systems; 2015.
- C. ASTM B221 Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes; 2021.
- D. ASTM E119 Standard Test Methods for Fire Tests of Building Construction and Materials; 2022.
- E. ASTM E283/E283M Standard Test Method for Determining Rate of Air Leakage Through Exterior Windows, Skylights, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen; 2019.
- F. ASTM E1300 Standard Practice for Determining Load Resistance of Glass in Buildings; 2016.
- G. ITS (DIR) Directory of Listed Products; Current Edition.
- H. UL (DIR) Online Certifications Directory; Current Edition.
- I. UL 263 Standard for Fire Tests of Building Construction and Materials; Current Edition, Including All Revisions.

1.02 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Product Data: Provide evidence of compliance with fire performance criteria and manufacturer's published product data on framing components, glazing, anchorage and fasteners, and doors, if any.
- C. Shop Drawings: Indicate system dimensions, framed opening requirements and tolerances, affected related work, expansion and contraction joint location and details, and field welding required.
- D. Design Data: Submit framing member structural and physical characteristics and engineering calculations, and identify dimensional limitations.
- E. Test Reports: Submit results of full-size mock-up testing for criteria other than fire performance. Reports of tests previously performed on the same design are acceptable.
- F. Field Quality Control Submittals: Submit report of field testing for water leakage.
- G. Manufacturer's Qualification Statement.
- H. Installer's Qualification Statement.
- I. Warranty Documentation: Submit manufacturer warranty and ensure forms have been completed in Owner's name and registered with manufacturer.

1.03 QUALITY ASSURANCE

- A. Designer Qualifications: Perform design under direct supervision of a Professional Structural Engineer experienced in design of this type of work and licensed in the State in which the Project is located.
- B. Manufacturer Qualifications: Company specializing in manufacturing products specified in this section with at least ten years documented experience.
- C. Installer Qualifications: Company specializing in performing work of the type specified and with at least three years documented experience.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

1.04 DELIVERY, STORAGE, AND HANDLING

- A. Handle products of this section in accordance with AAMA CW-10.
- B. Protect finished surfaces with wrapping. Do not use adhesive papers or sprayed coatings that bond to substrate when exposed to sunlight or weather.

1.05 FIELD CONDITIONS

A. Do not install sealants when ambient temperature is less than 40 degrees F (5 degrees C), and maintain above this minimum temperature during and for 48 hours after installation.

1.06 WARRANTY

- A. See Section 017800 Closeout Submittals for additional warranty requirements.
- B. Provide five year manufacturer warranty against failure of glass seal on insulating glass units, including interpane dusting or misting. Include provision for replacement of failed units.
- C. Provide five year manufacturer warranty against excessive degradation of exterior finish. Include provision for replacement of units with excessive fading, chalking, or flaking.

PART 2 PRODUCTS

2.01 EXTERIOR PROTECTIVE FRAMED GLAZING ASSEMBLIES

- A. Provide factory fabricated, factory finished framing members with glazing and related flashings, anchorage and attachment devices.
 - 1. Construction: Eliminate noises caused by wind and thermal movement, prevent vibration harmonics, and prevent "stack effect" within internal spaces.
 - 2. System Internal Drainage: Drain to the exterior by means of a weep drainage network any water entering joints, condensation occurring in glazing channel, and migrating moisture occurring within system.
 - 3. Air and Vapor Seal: Maintain continuous air barrier and vapor retarder throughout assembly, primarily in line with inside pane of glazing and inner sheet of infill panel and heel bead of glazing compound.
 - 4. Perimeter Clearance: Minimize space between framing members and adjacent construction while allowing expected movement.
 - 5. Preparation for Window Treatments: Provide reinforced interior horizontal head rail.
- B. Fire Performance: Provide hourly fire-resistance-rating as indicated; tested as an assembly including glazing in compliance with ASTM E119 or UL 263 and requirements of local authorities having jurisdiction.
 - 1. Exterior Wall Fire-Rating at Ground Level: 1 hour.
 - 2. Fire-Rating of Doors at Ground Level: 45 minutes.
 - 3. Acceptable evidence of compliance includes listing by UL (DIR), ITS (DIR), or testing agency acceptable to authorities having jurisdiction.
- C. Structural Performance: Design and size components to withstand the following loading without damage or permanent set.
 - 1. Design Live Loads: Comply with requirements of ASCE 7
 - 2. Comply with ASTM E1300 for design load resistance of glass type, thickness, dimensions, and maximum lateral deflection of supported glass.
 - 3. Provide glass edge support system sufficiently stiff to limit the lateral deflection of supported glass edges to less than 1/175 of their lengths or 3/4 inch (19 mm), whichever is less, under specified design load.
 - 4. Movement: Accommodate the following movement without damage to components or deterioration of seals:
 - a. Expansion and contraction caused by 180 degrees F (82 degrees C) surface temperature.

FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- b. Expansion and contraction caused by cycling temperature range of 170 degrees F (95 degrees C) over a 12 hour period.
- c. Movement of wall relative to perimeter framing.
- d. Deflection of structural support framing, under permanent and dynamic loads.
- D. Water Penetration: No uncontrolled water on indoor face when tested as follows:
 1. Test Pressure Differential: 10 pound-force per square foot (480 Pa).
- E. Air Leakage: 0.06 cfm/sq ft (0.3 L/sec sq m) maximum leakage of wall area when tested at 1.57 psf (75 Pa) pressure difference in accordance with ASTM E283/E283M.

2.02 COMPONENTS

- A. Framing Members: Formed steel structural members with aluminum cladding and noncombustible thermally-resistive material as required for fire rating.
 - 1. Fabrication: Joints and corners flush, hairline, and weatherproof, accurately fitted and secured; prepared to receive anchors; fasteners and attachments concealed from view; reinforced as required for imposed loads.

2.03 MATERIALS

A. Extruded Aluminum: ASTM B221 (ASTM B221M).

2.04 FINISHES

- A. Finishing: Apply factory finish to surfaces that will be exposed in completed assemblies.
 1. Touch-up surfaces cut during fabrication so that no natural metal surfaces are visible in
 - completed assemblies, including joint edges.
- B. Aluminum Finish: Class I natural anodized.
 - 1. Apply factory finish to surfaces that will be exposed in completed assemblies.
 - 2. Coat concealed metal surfaces that will be in contact with cementitious materials or dissimilar metals with bituminous paint.
- C. Color: As selected by Architect from manufacturer's standard range.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify dimensions, tolerances, and method of attachment with other work.
- B. Verify that wall openings and adjoining water-resistive barrier materials are ready to receive work of this section; see Section 072700 for additional information.
- C. Verify that anchorage devices have been properly installed and located.

3.02 INSTALLATION

- A. Install wall system in accordance with limitations of fire rating and with manufacturer's instructions.
- B. Attach to structure to permit sufficient adjustment to accommodate construction tolerances and other irregularities.
- C. Provide alignment attachments and shims to permanently fasten system to building structure.
- D. Align assembly plumb and level, free of warp or twist. Maintain assembly dimensional tolerances, aligning with adjacent work.
- E. Provide thermal isolation where components penetrate or disrupt building insulation.
- F. Install sill flashings. Turn up ends and edges; seal to adjacent work to form water tight dam.
- G. Where fasteners penetrate sill flashings, make watertight by seating and sealing fastener heads to sill flashing.
- H. Pack fibrous insulation in shim spaces at perimeter of assembly to maintain continuity of thermal barrier.

LAHC – WORKFORCE
EDUCATION RESOURCE AND
DEVELOPMENT CENTER

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

I. Touch-up minor damage to factory applied finish; replace components that cannot be satisfactorily repaired.

3.03 TOLERANCES

- A. Maximum Variation from Plumb: 1/16 inch every 3 feet (1.6 mm every 0.914 m) non-cumulative or 1/2 inch per 100 ft (12.7 mm per 30.5 m), whichever is less.
- B. Maximum Misalignment of Two Adjoining Members Abutting in Plane: 1/32 inch (0.8 mm).
- C. Sealant Space Between Mullions and Adjacent Construction: Maximum of 3/4 inch (19 mm) and minimum of 1/4 inch (6.4 mm).

3.04 FIELD QUALITY CONTROL

- A. Exterior Walls: Test installed wall for water leakage in accordance with AAMA 501.2 hose test.
- B. Replace components that have failed field testing and retest until performance is satisfactory.

3.05 CLEANING

- A. Remove protective material from pre-finished surfaces.
- B. Wash down surfaces with a solution of mild detergent in warm water, applied with soft, clean wiping cloths. Take care to remove dirt from corners. Wipe surfaces clean.

3.06 PROTECTION

A. Protect installed products from damage until Date of Substantial Completion.

END OF SECTION 084435

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 087100

DOOR HARDWARE

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes commercial door hardware for the following:
 - 1. Swinging doors.
- B. Door hardware includes, but is not necessarily limited to, the following:
 - 1. Mechanical door hardware.
 - 2. Electromechanical door hardware.
- C. Related Sections:
 - 1. Division 06 Section "Rough Carpentry".
 - 2. Division 08 Section "Door Schedule".
 - 3. Division 08 Section "Door Hardware Schedule".
 - 4. Division 08 Section "Hollow Metal Doors and Frames".
 - 5. Division 08 Section "Flush Wood Doors".
 - 6. Division 08 Section "Aluminum-Framed Entrances and Storefronts".
- D. Codes and References: Comply with the version year adopted by the Authority Having Jurisdiction.
 - 1. ANSI A117.1 Accessible and Usable Buildings and Facilities.
 - 2. ICC/IBC International Building Code.
 - 3. NFPA 70 National Electrical Čode.
 - 4. NFPA 80 Fire Doors and Windows.
 - 5. NFPA 101 Life Safety Code.
 - 6. NFPA 105 Installation of Smoke Door Assemblies.
 - 7. State Building Codes, Local Amendments.
- E. Standards: All hardware specified herein shall comply with the following industry standards as applicable. Any undated reference to a standard shall be interpreted as referring to the latest edition of that standard:
 - 1. ANSI/BHMA Certified Product Standards A156 Series.
 - 2. UL10C Positive Pressure Fire Tests of Door Assemblies.

3. UL 305 - Panic Hardware.

1.3 SUBMITTALS

- A. Product Data: Manufacturer's product data sheets including installation details, material descriptions, dimensions of individual components and profiles, operational descriptions and finishes.
- B. Door Hardware Schedule: Prepared by or under the supervision of supplier, detailing, fabrication and assembly of door hardware, as well as procedures and diagrams. Coordinate the final Door Hardware Schedule with doors, frames, and related work to ensure proper size, thickness, hand, function, and finish of door hardware.
 - 1. Format: Comply with scheduling sequence and vertical format in DHI's "Sequence and Format for the Hardware Schedule."
 - 2. Organization: Organize the Door Hardware Schedule into door hardware sets indicating complete designations of every item required for each door or opening. Organize door hardware sets in same order as in the Door Hardware Sets at the end of Part 3. Submittals that do not follow the same format and order as the Door Hardware Sets will be rejected and subject to resubmission.
 - 3. Content: Include the following information:
 - a. Type, style, function, size, label, hand, and finish of each door hardware item.
 - b. Manufacturer of each item.
 - c. Fastenings and other pertinent information.
 - d. Location of door hardware set, cross-referenced to Drawings, both on floor plans and in door and frame schedule.
 - e. Explanation of abbreviations, symbols, and codes contained in schedule.
 - f. Mounting locations for door hardware.
 - g. Door and frame sizes and materials.
 - h. Warranty information for each product.
 - 4. Submittal Sequence: Submit the final Door Hardware Schedule at earliest possible date, particularly where approval of the Door Hardware Schedule must precede fabrication of other work that is critical in the Project construction schedule. Include Product Data, Samples, Shop Drawings of other work affected by door hardware, and other information essential to the coordinated review of the Door Hardware Schedule.
- C. Shop Drawings: Details of electrified access control hardware indicating the following:
 - 1. Wiring Diagrams: Upon receipt of approved schedules, submit detailed system wiring diagrams for power, signaling, monitoring, communication, and control of the access control system electrified hardware. Differentiate between manufacturer-installed and field-installed wiring. Include the following:
 - a. Elevation diagram of each unique access controlled opening showing location and interconnection of major system components with respect to their placement in the respective door openings.
 - b. Complete (risers, point-to-point) access control system block wiring diagrams.
 - c. Wiring instructions for each electronic component scheduled herein.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 2. Electrical Coordination: Coordinate with related sections the voltages and wiring details required at electrically controlled and operated hardware openings.
- D. Keying Schedule: After a keying meeting with the owner has taken place prepare a separate keying schedule detailing final instructions. Submit the keying schedule in electronic format. Include keying system explanation, door numbers, key set symbols, hardware set numbers and special instructions. Owner must approve submitted keying schedule prior to the ordering of permanent cylinders/cores.
- E. Informational Submittals:
 - 1. Product Test Reports: Indicating compliance with cycle testing requirements, based on evaluation of comprehensive tests performed by manufacturer and witnessed by a qualified independent testing agency.

1.4 CLOSEOUT SUBMITTALS

- A. Operating and Maintenance Manuals: Provide manufacturers operating and maintenance manuals for each item comprising the complete door hardware installation in quantity as required in Division 01, Closeout Procedures.
- B. Project Record Documents: Provide record documentation of as-built door hardware sets in digital format (.pdf, .docx, .xlsx, .csv) and as required in Division 01, Project Record Documents.

1.5 QUALITY ASSURANCE

- A. Manufacturers Qualifications: Engage qualified manufacturers with a minimum 5 years of documented experience in producing hardware and equipment similar to that indicated for this Project and that have a proven record of successful in-service performance.
- B. Certified Products: Where specified, products must maintain a current listing in the Builders Hardware Manufacturers Association (BHMA) Certified Products Directory (CPD).
- C. Installer Qualifications: A minimum 3 years documented experience installing both standard and electrified door hardware similar in material, design, and extent to that indicated for this Project and whose work has resulted in construction with a record of successful in-service performance.
- D. Door Hardware Supplier Qualifications: Experienced commercial door hardware distributors with a minimum 5 years documented experience supplying both mechanical and electromechanical hardware installations comparable in material, design, and extent to that indicated for this Project. Supplier recognized as a factory direct distributor by the manufacturers of the primary materials with a warehousing facility in Project's vicinity. Supplier to have on staff a certified Architectural Hardware Consultant (AHC) available during the course of the Work to consult with Contractor, Architect, and Owner concerning both standard and electromechanical door hardware and keying.
- E. Source Limitations: Obtain each type and variety of door hardware specified in this section from a single source unless otherwise indicated.
 - 1. Provide electromechanical door hardware from the same manufacturer as mechanical door hardware, unless otherwise indicated.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- F. Each unit to bear third party permanent label indicating compliance with the referenced testing standards.
- G. Keying Conference: Conduct conference to comply with requirements in Division 01 Section "Project Meetings." Keying conference to incorporate the following criteria into the final keying schedule document:
 - 1. Function of building, purpose of each area and degree of security required.
 - 2. Plans for existing and future key system expansion.
 - 3. Requirements for key control storage and software.
 - 4. Installation of permanent keys, cylinder cores and software.
 - 5. Address and requirements for delivery of keys.
- H. Pre-Submittal Conference: Conduct coordination conference in compliance with requirements in Division 01 Section "Project Meetings" with attendance by representatives of Supplier(s), Installer(s), and Contractor(s) to review proper methods and the procedures for receiving, handling, and installing door hardware.
 - 1. Prior to installation of door hardware, conduct a project specific training meeting to instruct the installing contractors' personnel on the proper installation and adjustment of their respective products. Product training to be attended by installers of door hardware (including electromechanical hardware) for aluminum, hollow metal and wood doors. Training will include the use of installation manuals, hardware schedules, templates and physical product samples as required.
 - 2. Inspect and discuss electrical roughing-in, power supply connections, and other preparatory work performed by other trades.
 - 3. Review sequence of operation narratives for each unique access controlled opening.
 - 4. Review and finalize construction schedule and verify availability of materials.
 - 5. Review the required inspecting, testing, commissioning, and demonstration procedures
- I. At completion of installation, provide written documentation that components were applied according to manufacturer's instructions and recommendations and according to approved schedule.

1.6 DELIVERY, STORAGE AND HANDLING

- A. Inventory door hardware on receipt and provide secure lock-up and shelving for door hardware delivered to Project site. Do not store electronic access control hardware, software or accessories at Project site without prior authorization.
- B. Tag each item or package separately with identification related to the final Door Hardware Schedule, and include basic installation instructions with each item or package.
- C. Deliver, as applicable, permanent keys, cylinders, cores, access control credentials, software and related accessories directly to Owner via registered mail or overnight package service. Instructions for delivery to the Owner shall be established at the "Keying Conference".

1.7 COORDINATION

A. Templates: Obtain and distribute to the parties involved templates for doors, frames, and other work specified to be factory prepared for installing standard and electrified hardware. Check

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

Shop Drawings of other work to confirm that adequate provisions are made for locating and installing hardware to comply with indicated requirements.

- B. Door Hardware and Electrical Connections: Coordinate the layout and installation of scheduled electrified door hardware and related access control equipment with required connections to source power junction boxes, low voltage power supplies, detection and monitoring hardware, and fire and detection alarm systems.
- C. Door and Frame Preparation: Doors and corresponding frames are to be prepared, reinforced and pre-wired (if applicable) to receive the installation of the specified electrified, monitoring, signaling and access control system hardware without additional in-field modifications.

1.8 WARRANTY

- A. General Warranty: Reference Division 01, General Requirements. Special warranties specified in this Article shall not deprive Owner of other rights Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by Contractor under requirements of the Contract Documents.
- B. Warranty Period: Written warranty, executed by manufacturer(s), agreeing to repair or replace components of standard and electrified door hardware that fails in materials or workmanship within specified warranty period after final acceptance by the Owner. Failures include, but are not limited to, the following:
 - 1. Structural failures including excessive deflection, cracking, or breakage.
 - 2. Faulty operation of the hardware.
 - 3. Deterioration of metals, metal finishes, and other materials beyond normal weathering.
 - 4. Electrical component defects and failures within the systems operation.
- C. Warranty Period: Unless otherwise indicated, warranty shall be one year from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 BUTT HINGES

- A. Hinges: ANSI/BHMA A156.1 butt hinges with number of hinge knuckles and other options as specified in the Door Hardware Sets.
 - 1. Quantity: Provide the following hinge quantity:
 - a. Two Hinges: For doors with heights up to 60 inches.
 - b. Three Hinges: For doors with heights 61 to 90 inches.
 - c. Four Hinges: For doors with heights 91 to 120 inches.
 - d. For doors with heights more than 120 inches, provide 4 hinges, plus 1 hinge for every 30 inches of door height greater than 120 inches.
 - 2. Hinge Size: Provide the following, unless otherwise indicated, with hinge widths sized for door thickness and clearances required:
 - a. Widths up to 3'0": 4-1/2" standard or heavy weight as specified.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- b. Sizes from 3'1" to 4'0": 5" standard or heavy weight as specified.
- 3. Hinge Weight and Base Material: Unless otherwise indicated, provide the following:
 - a. Exterior Doors: Heavy weight, non-ferrous, ball bearing or oil impregnated bearing hinges unless Hardware Sets indicate standard weight.
 - b. Interior Doors: Standard weight, steel, ball bearing or oil impregnated bearing hinges unless Hardware Sets indicate heavy weight.
- 4. Hinge Options: Comply with the following:
 - a. Non-removable Pins: With the exception of electric through wire hinges, provide set screw in hinge barrel that, when tightened into a groove in hinge pin, prevents removal of pin while door is closed; for all out-swinging lockable doors.
- 5. Manufacturers:
 - a. Hager Companies (HA) BB Series, 5-knuckle.
 - b. Ives (IV) 5BB Series, 5-knuckle.
 - c. McKinney (MK) TA/T4A Series, 5-knuckle.

2.2 CONTINUOUS HINGES

- A. Continuous Geared Hinges: ANSI/BHMA A156.26 Grade 1-600 continuous geared hinge. with minimum 0.120-inch thick extruded 6063-T6 aluminum alloy hinge leaves and a minimum overall width of 4 inches. Hinges are non-handed, reversible and fabricated to template screw locations. Factory trim hinges to suit door height and prepare for electrical cut-outs.
 - 1. Where specified, provide modular continuous geared hinges that ship in two or three pieces and form a single continuous hinge upon installation.
 - 2. Manufacturers:.
 - a. Hager Companies (HA).
 - b. Pemko (PE).

2.3 **POWER TRANSFER DEVICES**

- A. Concealed Quick Connect Electric Power Transfers: Provide concealed wiring pathway housing mortised into the door and frame for low voltage electrified door hardware. Furnish with Molex™ standardized plug connectors and sufficient number of concealed wires (up to 12) to accommodate the electrified functions specified in the Door Hardware Sets. Connectors plug directly to through-door wiring harnesses for connection to electric locking devices and power supplies. Wire nut connections are not acceptable.
 - 1. Manufacturers:
 - a. Securitron (SU) EL-CEPT Series.
- B. Electric Door Wire Harnesses: Provide electric/data transfer wiring harnesses with standardized plug connectors to accommodate up to twelve (12) wires. Connectors plug directly to throughdoor wiring harnesses for connection to electric locking devices and power supplies. Provide

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

sufficient number and type of concealed wires to accommodate electric function of specified hardware. Provide a connector for through-door electronic locking devices and from hinge to junction box above the opening. Wire nut connections are not acceptable. Determine the length required for each electrified hardware component for the door type, size and construction, minimum of two per electrified opening.

- 1. Provide one each of the following tools as part of the base bid contract:
 - a. McKinney (MK) Electrical Connecting Kit: QC-R001.
 - b. McKinney (MK) Connector Hand Tool: QC-R003.
- 2. Manufacturers:
 - a. McKinney (MK) QC-C Series.

2.4 DOOR OPERATING TRIM

- A. Door Push Plates and Pulls: ANSI/BHMA A156.6 door pushes and pull units of type and design specified in the Hardware Sets. Coordinate and provide proper width and height as required where conflicting hardware dictates.
 - 1. Push/Pull Plates: Minimum .050 inch thick, size as indicated in hardware sets, with beveled edges, secured with exposed screws unless otherwise indicated.
 - 2. Door Pull and Push Bar Design: Size, shape, and material as indicated in the hardware sets. Minimum clearance of 2 1/2-inches from face of door unless otherwise indicated.
 - 3. Offset Pull Design: Size, shape, and material as indicated in the hardware sets. Minimum clearance of 2 1/2-inches from face of door and offset of 90 degrees unless otherwise indicated.
 - 4. Pulls, where applicable, shall be provided with a 10" clearance from the finished floor on the push side to accommodate wheelchair accessibility.
 - 5. Fasteners: Provide manufacturer's designated fastener type as indicated in Hardware Sets. When through-bolt fasteners are in the same location as a push plate, countersink the fasteners flush with the door face allowing the push plate to sit flat against the door.
 - 6. Manufacturers:
 - a. Burns Manufacturing (BU).
 - b. Hiawatha, Inc. (HI).
 - c. Rockwood (RO).

2.5 CYLINDERS AND KEYING

- A. General: Cylinder manufacturer to have minimum (10) years experience designing secured master key systems and have on record a published security keying system policy.
- B. Cylinder Types: Original manufacturer cylinders able to supply the following cylinder formats and types:
 - 1. Threaded mortise cylinders with rings and cams to suit hardware application.
 - 2. Rim cylinders with back plate, flat-type vertical or horizontal tailpiece, and raised trim ring.
 - 3. Bored or cylindrical lock cylinders with tailpieces as required to suit locks.
 - 4. Tubular deadlocks and other auxiliary locks.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 5. Mortise and rim cylinder collars to be solid and recessed to allow the cylinder face to be flush and be free spinning with matching finishes.
- 6. Keyway: Match Facility Standard.
- C. Keying System: Each type of lock and cylinders to be factory keyed.
 - 1. Supplier shall conduct a "Keying Conference" to define and document keying system instructions and requirements.
 - 2. Furnish factory cut, nickel-silver large bow permanently inscribed with a visual key control number as directed by Owner.
 - 3. Existing System: Field verify and key cylinders to match Owner's existing system.
- D. Key Quantity: Provide the following minimum number of keys:
 - 1. Change Keys per Cylinder: Two (2)
 - 2. Construction Keys (where required): Ten (10).
- E. Construction Keying: Provide construction master keyed cylinders.

2.6 CYLINDRICAL LOCKS AND LATCHING DEVICES

- A. Cylindrical Locksets, Grade 1 (Heavy Duty): ANSI/BHMA A156.2, Series 4000, Operational Grade 1 Certified Products Directory (CPD) listed cylindrical locksets. Listed manufacturers shall meet all functions and features as specified herein.
 - 1. Manufacturers:
 - a. ASSA ABLOY ACCENTRA (YA) 5400LN Series.
 - b. Corbin Russwin Hardware (RU) CLX3300 Series.
 - c. Sargent Manufacturing (SA) 10X Line.
- B. Cylindrical Indicator Locksets, Grade 1 (Commercial Duty): ANSI/BHMA A156.2, Series 4000, Operational Grade 1 Certified Products Directory (CPD) listed. Listed manufacturers shall meet all functions and features as specified herein.
 - 1. Provide locksets with functions and features as follows:
 - a. Visual status indicators in rose, displaying bold visuals for vacant or occupied lock status.
 - b. Meets ANSI/BHMA A156.41 for single motion egress.
 - c. Meets UL and CUL Standard 10C Positive Pressure, Fire Test of Door Assemblies with levers that meet A117.1 Accessibility Code.
 - d. Three-year limited warranty.
 - 2. Manufacturers:
 - a. ASSA ABLOY ACCENTRA (YA) YPL Series.

2.7 LOCK AND LATCH STRIKES

- A. Strikes: Provide manufacturer's standard strike with strike box for each latch or lock bolt, with curved lip extended to protect frame, finished to match door hardware set, unless otherwise indicated, and as follows:
 - 1. Flat-Lip Strikes: For locks with three-piece antifriction latchbolts, as recommended by manufacturer.
 - 2. Extra-Long-Lip Strikes: For locks used on frames with applied wood casing trim.
 - 3. Aluminum-Frame Strike Box: Provide manufacturer's special strike box fabricated for aluminum framing.
 - 4. Double-lipped strikes: For locks at double acting doors. Furnish with retractable stop for rescue hardware applications.
- B. Standards: Comply with the following:
 - 1. Strikes for Mortise Locks and Latches: BHMA A156.13.
 - 2. Strikes for Bored Locks and Latches: BHMA A156.2.
 - 3. Strikes for Auxiliary Deadlocks: BHMA A156.36.
 - 4. Dustproof Strikes: BHMA A156.16.

2.8 CONVENTIONAL EXIT DEVICES

- A. General Requirements: All exit devices specified herein shall meet or exceed the following criteria:
 - 1. Exit devices shall have a five-year warranty.
 - 2. At doors not requiring a fire rating, provide devices complying with NFPA 101 and listed and labeled for "Panic Hardware" according to UL305. Provide proper fasteners as required by manufacturer including sex nuts and bolts at openings specified in the Hardware Sets.
 - 3. Where exit devices are required on fire rated doors, provide devices complying with NFPA 80 and with UL labeling indicating "Fire Exit Hardware". Provide devices with the proper fasteners for installation as tested and listed by UL. Consult manufacturer's catalog and template book for specific requirements.
 - 4. Except on fire rated doors, provide exit devices with hex key dogging device to hold the pushbar and latch in a retracted position. Provide optional keyed cylinder dogging on devices where specified in Hardware Sets.
 - 5. Devices must fit flat against the door face with no gap that permits unauthorized dogging of the push bar. The addition of filler strips is required in any case where the door light extends behind the device as in a full glass configuration.
 - 6. Flush End Caps: Provide flush end caps made of architectural metal in the same finish as the devices as in the Hardware Sets. Plastic end caps will not be acceptable.
 - 7. Lever Operating Trim: Where exit devices require lever trim, furnish manufacturer's heavy duty escutcheon trim with threaded studs for thru-bolts.
 - a. Lock Trim Design: As indicated in Hardware Sets, provide finishes and designs to match that of the specified locksets.
 - b. Where function of exit device requires a cylinder, provide a cylinder (Rim or Mortise) as specified in Hardware Sets.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 8. Vertical Rod Exit Devices: Where surface or concealed vertical rod exit devices are used at interior openings, provide as less bottom rod (LBR) unless otherwise indicated. Provide dust proof strikes where thermal pins are required to project into the floor.
- 9. Narrow Stile Applications: At doors constructed with narrow stiles, or as specified in Hardware Sets, provide devices designed for maximum 2" wide stiles.
- 10. Dummy Push Bar: Nonfunctioning push bar matching functional push bar.
- 11. Rail Sizing: Provide exit device rails factory sized for proper door width application.
- 12. Through Bolt Installation: For exit devices and trim as indicated in Door Hardware Sets.
- B. Conventional Push Rail Exit Devices (Heavy Duty): ANSI/BHMA A156.3, Grade 1 Certified Products Directory (CPD) listed exit devices. Listed manufacturers shall meet all functions and features as specified herein.
 - 1. Manufacturers:
 - a. ASSA ABLOY ACCENTRA (YA) 6000 Series.
 - b. Corbin Russwin Hardware (RU) ED4000 / ED5000 Series.
 - c. Sargent Manufacturing (SA) 80 Series.

2.9 SURFACE DOOR CLOSERS

- A. All door closers specified herein shall meet or exceed the following criteria:
 - 1. General: Door closers to be from one manufacturer, matching in design and style, with the same type door preparations and templates regardless of application or spring size. Closers to be non-handed with full sized covers.
 - 2. Standards: Closers to comply with UL-10C for Positive Pressure Fire Test and be U.L. listed for use of fire rated doors.
 - 3. Cycle Testing: Provide closers which have surpassed 15 million cycles.
 - 4. Size of Units: Comply with manufacturer's written recommendations for sizing of door closers depending on size of door, exposure to weather, and anticipated frequency of use. Where closers are indicated for doors required to be accessible to the Americans with Disabilities Act, provide units complying with ANSI ICC/A117.1.
 - 5. Closer Arms: Provide heavy duty, forged steel closer arms unless otherwise indicated in Hardware Sets.
 - 6. Closers shall not be installed on exterior or corridor side of doors; where possible install closers on door for optimum aesthetics.
 - 7. Closer Accessories: Provide door closer accessories including custom templates, special mounting brackets, spacers and drop plates as required for proper installation. Provide through-bolt and security type fasteners as specified in the hardware sets.
- B. Door Closers, Surface Mounted (Heavy Duty): ANSI/BHMA A156.4, Grade 1 Certified Products Directory (CPD) listed surface mounted, heavy duty door closers with complete spring power adjustment, sizes 1 thru 6; and fully operational adjustable according to door size, frequency of use, and opening force. Closers to be rack and pinion type, one piece cast iron or aluminum alloy body construction, with adjustable backcheck and separate non-critical valves for closing sweep and latch speed control. Provide non-handed units standard.
 - 1. Heavy duty surface mounted door closers shall have a 30-year warranty.
 - 2. Manufacturers:
 - a. Corbin Russwin Hardware (RU) DC6000 Series.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- b. Norton Rixson (NO) 7500 Series.
- c. Sargent Manufacturing (SA) 351 Series.
- C. Door Closers, Surface Mounted (Unitrol): ANSI/BHMA A156.4, Grade 1 Certified Products Directory (CPD) listed surface mounted closers with door stop mechanism to absorb dead stop shock on arm and top hinge. Hold-open arms to have a spring loaded mechanism in addition to shock absorber assembly. Arms to be provided with rigid steel main arm and secondary arm lengths proportional to the door width.
 - 1. Manufacturers:
 - a. Corbin Russwin Hardware (RU) Unitrol Series.
 - b. Norton Rixson (NO) Unitrol Series.

2.10 DOOR STOPS AND HOLDERS

- A. General: Door stops and holders to be of type and design as specified below or in the Hardware Sets.
- B. Door Stops and Bumpers: ANSI/BHMA A156.16, Grade 1 door stops and wall bumpers. Provide wall bumpers, either convex or concave types with anchorage as indicated, unless floor or other types of door stops are specified in Hardware Sets. Do not mount floor stops where they will impede traffic. Where floor or wall bumpers are not appropriate, provide overhead type stops and holders.
 - 1. Manufacturers:
 - a. Burns Manufacturing (BU).
 - b. Hiawatha, Inc. (HI).
 - c. Rockwood (RO).

2.11 ARCHITECTURAL SEALS

- A. General: Thresholds, weatherstripping, and gasket seals to be of type and design as specified below or in the Hardware Sets. Provide continuous weatherstrip gasketing on exterior doors and provide smoke, light, or sound gasketing on interior doors where indicated. At exterior applications provide non-corrosive fasteners and elsewhere where indicated.
- B. Smoke Labeled Gasketing: Assemblies complying with NFPA 105 that are listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction, for smoke control ratings indicated, based on testing according to UL 1784.
 - 1. Provide smoke labeled perimeter gasketing at all smoke labeled openings.
- C. Fire Labeled Gasketing: Assemblies complying with NFPA 80 that are listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction, for fire ratings indicated, based on testing according to UL-10C.
 - 1. Provide intumescent seals as indicated to meet UL10C Standard for Positive Pressure Fire Tests of Door Assemblies, and NFPA 252, Standard Methods of Fire Tests of Door Assemblies.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- D. Sound-Rated Gasketing: Assemblies that are listed and labeled by a testing and inspecting agency, for sound ratings indicated.
- E. Replaceable Seal Strips: Provide only those units where resilient or flexible seal strips are easily replaceable and readily available from stocks maintained by manufacturer.
- F. Manufacturers:
 - 1. National Guard Products (NG).
 - 2. Pemko (PE).
 - 3. Reese Enterprises, Inc. (RE).

2.12 ELECTRONIC ACCESSORIES

- A. Door Position Switches: Door position magnetic reed contact switches specifically designed for use in commercial door applications. On recessed models the contact and magnetic housing snap-lock into a 1" diameter hole. Surface mounted models include wide gap distance design complete with armored flex cabling. Provide SPDT, N/O switches with optional Rare Earth Magnet installation on steel doors with flush top channels.
 - 1. Manufacturers:
 - a. Sargent Manufacturing (SA) 3280 Series.
 - b. Security Door Controls (SD) DPS Series.
 - c. Securitron (SU) DPS Series.
- B. Intelligent Switching Power Supplies: Provide the least number of power supplies at the appropriate amperage level sufficient to exceed the required total draw for the specified electrified hardware and access control equipment.
 - 1. Power supplies shall meet all functions and features as specified herein.
 - a. UL listed dual voltage 12 or 24 VDC field selectable continuous output.
 - b. Dedicated fast charger to prolong battery life with low battery cutoff to protect batteries from deep discharge.
 - c. Enhanced surge immunity for input/output protection
 - d. Separate, dedicated battery charging circuit to keep locks cooler.
 - e. Dual-color LED visual notification to prevent applying incorrect voltages to the power supply.
 - f. Instant auto-switch to battery on AC loss.
 - g. Expandable up to 16 outputs in the standard enclosure
 - h. Integrated fire alarm interface to allow main output shutdown or disconnect on a per output basis when using an R8 output module.
 - i. Network ready and remotely manage locks and connected devices when using an M8 managed output module on network models.
 - j. Lifetime replacement, no-fault, no questions asked warranty.
 - 2. Manufacturers:
 - a. Life Safety Power (LP).
 - b. Securitron (SU) AQL Series.

2.13 FABRICATION

A. Fasteners: Provide door hardware manufactured to comply with published templates generally prepared for machine, wood, and sheet metal screws. Provide screws according to manufacturers recognized installation standards for application intended.

2.14 FINISHES

- A. Standard: Designations used in the Hardware Sets and elsewhere indicate hardware finishes complying with ANSI/BHMA A156.18, including coordination with traditional U.S. finishes indicated by certain manufacturers for their products.
- B. Provide quality of finish, including thickness of plating or coating (if any), composition, hardness, and other qualities complying with manufacturer's standards, but in no case less than specified by referenced standards for the applicable units of hardware
- C. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine scheduled openings, with Installer present, for compliance with requirements for installation tolerances, labeled fire door assembly construction, wall and floor construction, and other conditions affecting performance.
- B. Notify architect of any discrepancies or conflicts between the door schedule, door types, drawings and scheduled hardware. Proceed only after such discrepancies or conflicts have been resolved in writing.

3.2 **PREPARATION**

- A. Hollow Metal Doors and Frames: Comply with ANSI/DHI A115 series.
- B. Wood Doors: Comply with ANSI/DHI A115-W series.

3.3 INSTALLATION

- A. Install each item of mechanical and electromechanical hardware and access control equipment to comply with manufacturer's written instructions and according to specifications.
 - 1. Installers are to be trained and certified by the manufacturer on the proper installation and adjustment of fire, life safety, and security products including: hanging devices; locking devices; closing devices; and seals.
- B. Mounting Heights: Mount door hardware units at heights indicated in following applicable publications, unless specifically indicated or required to comply with governing regulations:

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 1. Standard Steel Doors and Frames: DHI's "Recommended Locations for Architectural Hardware for Standard Steel Doors and Frames."
- 2. DHI TDH-007-20: Installation Guide for Doors and Hardware.
- 3. Where indicated to comply with accessibility requirements, comply with ANSI A117.1 "Accessibility Guidelines for Buildings and Facilities."
- 4. Provide blocking in drywall partitions where wall stops or other wall mounted hardware is located.
- C. Retrofitting: Install door hardware to comply with manufacturer's published templates and written instructions. Where cutting and fitting are required to install door hardware onto or into surfaces that are later to be painted or finished in another way, coordinate removal, storage, and reinstallation of surface protective trim units with finishing work specified in Division 9 Sections. Do not install surface-mounted items until finishes have been completed on substrates involved.
- D. Push Plates and Door Pulls: When through-bolt fasteners are in the same location as a push plate, countersink the fasteners flush with the door face allowing the push plate to sit flat against the door.
- E. Thresholds: Set thresholds for exterior and acoustical doors in full bed of sealant complying with requirements specified in Division 7 Section "Joint Sealants."
- F. Storage: Provide a secure lock up for hardware delivered to the project but not yet installed. Control the handling and installation of hardware items so that the completion of the work will not be delayed by hardware losses before and after installation.

3.4 FIELD QUALITY CONTROL

- A. Field Inspection (Punch Report): Reference Division 01 Sections "Closeout Procedures". Produce project punch report for each installed door opening indicating compliance with approved submittals and verification hardware is properly installed, operating and adjusted. Include list of items to be completed and corrected, indicating the reasons or deficiencies causing the Work to be incomplete or rejected.
 - 1. Organization of List: Include separate Door Opening and Deficiencies and Corrective Action Lists organized by Mark, Opening Remarks and Comments, and related Opening Images and Video Recordings.

3.5 ADJUSTING

A. Initial Adjustment: Adjust and check each operating item of door hardware and each door to ensure proper operation or function of every unit. Replace units that cannot be adjusted to operate as intended. Adjust door control devices to compensate for final operation of heating and ventilating equipment and to comply with referenced accessibility requirements.

3.6 CLEANING AND PROTECTION

- A. Protect all hardware stored on construction site in a covered and dry place. Protect exposed hardware installed on doors during the construction phase. Install any and all hardware at the latest possible time frame.
- B. Clean adjacent surfaces soiled by door hardware installation.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

C. Clean operating items as necessary to restore proper finish. Provide final protection and maintain conditions that ensure door hardware is without damage or deterioration at time of owner occupancy.

3.7 DEMONSTRATION

A. Instruct Owner's maintenance personnel to adjust, operate, and maintain mechanical and electromechanical door hardware.

3.8 DOOR HARDWARE SETS

- A. The hardware sets represent the design intent and direction of the owner and architect. They are a guideline only and should not be considered a detailed hardware schedule. Discrepancies, conflicting hardware and missing items should be brought to the attention of the architect with corrections made prior to the bidding process. Omitted items not included in a hardware set should be scheduled with the appropriate additional hardware required for proper application and functionality.
 - 1. Quantities listed are for each pair of doors, or for each single door.
 - 2. The supplier is responsible for handing and sizing all products.
 - 3. Where multiple options for a piece of hardware are given in a single line item, the supplier shall provide the appropriate application for the opening.
 - 4. At existing openings with new hardware the supplier shall field inspect existing conditions prior to the submittal stage to verify the specified hardware will work as required. Provide alternate solutions and proposals as needed.
- B. Refer to Section 080671, Door Hardware Sets, for hardware sets.

END OF SECTION 087100

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 088000 GLAZING

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Insulating glass units.
- B. Glazing units.
- C. Glass coatings.
- D. Glazing compounds.

1.02 RELATED REQUIREMENTS

- A. Section 072700 Air Barriers.
- B. Section 079200 Joint Sealants: Sealants for other than glazing purposes.
- C. Section 084313 Aluminum-Framed Storefronts: Glazing provided as part of storefront assembly.

1.03 REFERENCE STANDARDS

- A. 16 CFR 1201 Safety Standard for Architectural Glazing Materials; Current Edition.
- B. ANSI Z97.1 American National Standard for Safety Glazing Materials Used in Buildings -Safety Performance Specifications and Methods of Test; 2015 (Reaffirmed 2020).
- C. ASCE 7 Minimum Design Loads and Associated Criteria for Buildings and Other Structures; Most Recent Edition Cited by Referring Code or Reference Standard.
- D. ASTM C864 Standard Specification for Dense Elastomeric Compression Seal Gaskets, Setting Blocks, and Spacers; 2005 (Reapproved 2019).
- E. ASTM C1036 Standard Specification for Flat Glass; 2021.
- F. ASTM C1048 Standard Specification for Heat-Strengthened and Fully Tempered Flat Glass; 2018.
- G. ASTM C1172 Standard Specification for Laminated Architectural Flat Glass; 2019.
- H. ASTM C1193 Standard Guide for Use of Joint Sealants; 2016 (Reapproved 2023).
- I. ASTM C1376 Standard Specification for Pyrolytic and Vacuum Deposition Coatings on Flat Glass; 2021a.
- J. ASTM E1300 Standard Practice for Determining Load Resistance of Glass in Buildings; 2016.
- K. ASTM E2190 Standard Specification for Insulating Glass Unit Performance and Evaluation; 2019.
- L. GANA (SM) GANA Sealant Manual; 2008.
- M. NFRC 100 Procedure for Determining Fenestration Product U-factors; 2023.
- N. NFRC 200 Procedure for Determining Fenestration Product Solar Heat Gain Coefficient and Visible Transmittance at Normal Incidence; 2023.
- O. NFRC 300 Test Method for Determining the Solar Optical Properties of Glazing Materials and Systems; 2023.

1.04 ADMINISTRATIVE REQUIREMENTS

A. Preinstallation Meeting: Convene a preinstallation meeting one week before starting work of this section; require attendance by each of the affected installers.

1.05 SUBMITTALS

A. See Section 013000 - Administrative Requirements for submittal procedures.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- B. Product Data on Insulating Glass Unit Glazing Types: Provide structural, physical and environmental characteristics, size limitations, special handling and installation requirements.
- C. Product Data on Glazing Compounds and Accessories: Provide chemical, functional, and environmental characteristics, limitations, special application requirements, and identify available colors.
- D. Samples: Submit two samples 12" by 12" in size of glass units.
- E. Samples: Submit bead of glazing sealant, color as selected.
- F. Certificate: Certify that products of this section meet or exceed specified requirements.
- G. Manufacturer's qualification statement.
- H. Installer's qualification statement.
- I. Warranty Documentation: Submit manufacturer warranty and ensure that forms have been completed in Owner's name and registered with manufacturer.

1.06 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum 10 years of documented experience.
- B. Installer Qualifications: Company specializing in performing work of the type specified and with at least three years documented experience.

1.07 MOCK-UPS

- A. See Section 014000 Quality Requirements for additional requirements.
- B. Provide mock-up of exterior wall including glass and air barrier and vapor retarder seal.
- C. Locate as indicated by Architect.

1.08 FIELD CONDITIONS

- A. Do not install glazing when ambient temperature is less than 40 degrees F (4 degrees C).
- B. Maintain minimum ambient temperature before, during and 24 hours after installation of glazing compounds.

1.09 WARRANTY

- A. See Section 017800 Closeout Submittals for additional warranty requirements.
- B. Insulating Glass Units: Provide a five (5) year manufacturer warranty to include coverage for seal failure, interpane dusting or misting, including providing products to replace failed units.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Glass Fabricators:
 - 1. GGI General Glass International: www.generalglass.com/#sle.
 - 2. Standard Bent Glass Corp: www.standardbent.com/#sle.
 - 3. Tecnoglass; Insulating Glass: www.tecnoglass.com/#sle.
 - 4. Thompson I.G., LLC: www.thompsonig.com/#sle.
 - 5. Trulite Glass & Aluminum Solutions, LLC: www.trulite.com/#sle.
 - 6. Viracon, Inc: www.viracon.com/#sle.
 - 7. Substitutions: See Section 016000 Product Requirements.
- B. Float Glass Manufacturers:
 - 1. Cardinal Glass Industries: www.cardinalcorp.com/#sle.
 - 2. Guardian Glass, LLC: www.guardianglass.com/#sle.
 - 3. Pilkington North America Inc: www.pilkington.com/na/#sle.
 - 4. Saint Gobain North America: www.saint-gobain.com/#sle.

LAHC – WORKFORCE
EDUCATION RESOURCE AND
DEVELOPMENT CENTER

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 5. Vitro Architectural Glass (formerly PPG Glass): www.vitroglazings.com/#sle.
- 6. Substitutions: See Section 016000 Product Requirements.

2.02 PERFORMANCE REQUIREMENTS - EXTERIOR GLAZING ASSEMBLIES

- A. Provide type and thickness of exterior glazing assemblies to support assembly dead loads, and to withstand live loads caused by positive and negative wind pressure acting normal to plane of glass.
 - 1. Design Pressure: Calculated in accordance with ASCE 7.
 - 2. Comply with ASTM E1300 for design load resistance of glass type, thickness, dimensions, and maximum lateral deflection of supported glass.
 - 3. Provide glass edge support system sufficiently stiff to limit the lateral deflection of supported glass edges to less than 1/175 of their lengths under specified design load.
 - 4. Glass thicknesses listed are minimum.
- B. Weather-Resistive Barrier Seals: Provide completed assemblies that maintain continuity of building enclosure water-resistive barrier, vapor retarder, and/or air barrier.
 - 1. In conjunction with weather barrier related materials described in other sections, as follows:
 - a. Air Barriers: See Section 072700.
 - 2. To utilize inner pane of multiple pane insulating glass units for continuity of vapor retarder and/or air barrier seal.
 - 3. To maintain a continuous vapor retarder and/or air barrier throughout glazed assembly from glass pane to heel bead of glazing sealant.
- C. Thermal and Optical Performance: Provide exterior glazing products with performance properties as indicated. **BASIS OF DESIGN IS VIRACON 1" VRE1 38 INSULATING UNIT.** Performance properties are in accordance with manufacturer's published data as determined with the following procedures and/or test methods:
 - 1. Center of Glass U-Value: Comply with NFRC 100 using Lawrence Berkeley National Laboratory (LBNL) WINDOW 6.3 computer program.
 - 2. Center of Glass Solar Heat Gain Coefficient (SHGC): Comply with NFRC 200 using Lawrence Berkeley National Laboratory (LBNL) WINDOW 6.3 computer program.
 - 3. Solar Optical Properties: Comply with NFRC 300 test method.

2.03 GLASS MATERIALS

- A. Float Glass: Provide float glass based glazing unless otherwise indicated.
 - 1. Annealed Type: ASTM C1036, Type I Transparent Flat, Class 1 Clear, Quality Q3.
 - 2. Kind HS Heat-Strengthened Type: Complies with ASTM C1048.
 - 3. Kind FT Fully Tempered Type: Complies with ASTM C1048.
 - 4. Fully Tempered Safety Glass: Complies with ANSI Z97.1 or 16 CFR 1201 criteria for safety glazing used in hazardous locations.
 - 5. Impact Resistant Safety Glass: Complies with ANSI Z97.1 Class B, or 16 CFR 1201 Category I criteria.
 - 6. Thicknesses: As indicated; provide greater thickness as required for exterior glazing wind load design.

2.04 INSULATING GLASS UNITS

- A. Manufacturers:
 - 1. Cardinal Glass Industries: www.cardinalcorp.com/#sle.
 - 2. Guardian Glass, LLC: www.guardianglass.com/#sle.
 - 3. Pilkington North America Inc: www.pilkington.com/na/#sle.Pilkington North America Inc: www.pilkington.com/na/#sle.
 - 4. Viracon, Apogee Enterprises, Inc: www.viracon.com/#sle.
 - 5. Vitro Architectural Glass (formerly PPG Glass): www.vitroglazings.com/#sle.
 - 6. Substitutions: See Section 016000 Product Requirements.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- B. Fabricator: Certified by glass manufacturer for type of glass, coating, and treatment involved and capable of providing specified warranty.
- C. Insulating Glass Units: Types as indicated.
 - 1. Durability: Certified by an independent testing agency to comply with ASTM E2190.
 - Coated Glass: Comply with requirements of ASTM C1376 for pyrolytic (hard-coat) or magnetic sputter vapor deposition (soft-coat) type coatings on flat glass; coated vision glass, Kind CV; coated overhead glass, Kind CO; or coated spandrel glass, Kind CS.
 - 3. Metal-Edge Spacers: Aluminum, bent and soldered corners.
 - 4. Spacer Color: Aluminum.
 - 5. Edge Seal:
 - a. Dual-Sealed System: Provide polyisobutylene sealant as primary seal applied between spacer and glass panes, and silicone, polysulfide, or polyurethane sealant as secondary seal applied around perimeter.
 - b. Color: Black.
 - 6. Purge interpane space with dry air, hermetically sealed.
- D. Type GT-1 Insulating Glass Units: Vision glass, double glazed.
 - 1. Applications: Exterior glazing unless otherwise indicated.
 - 2. Space between lites filled with argon.
 - 3. Outboard Lite: Annealed float glass, 1/4 inch (6.4 mm) thick, minimum. a. Tint: Clear.
 - b. Coating: Low-E (solar control type), on #2 surface.
 - Inboard Lite: Annealed float glass, 1/4 inch (6.4 mm) thick, minimum.
 a. Tint: Clear.
 - 5. Total Thickness: 1 inch (25.4 mm).
 - 6. Thermal Transmittance (U-Value), Summer Center of Glass: 0.26, nominal.
 - 7. Visible Light Transmittance (VLT): 36% percent, nominal.
 - 8. Solar Heat Gain Coefficient (SHGC): 0.23
 - 9. Visible Light Reflectance, Outside: 44 percent, nominal.
 - 10. Glazing Method: Dry glazing method, tape and gasket spline.

2.05 GLAZING UNITS

- A. Type GT-1 Monolithic Interior Vision Glazing:
 - 1. Applications: Interior glazing unless otherwise indicated.
 - 2. Glass Type: Fully tempered float glass.
 - 3. Tint: Clear.
 - 4. Thickness: 1/4 inch (6.4 mm), nominal.

2.06 LAMINATED GLASS INTERLAYERS

- A. Type LGI-1 Polyvinyl Butyral (PVB) Interlayer for Laminated Glazing:
 - 1. Functionality: Post-breakage safety and security.
 - 2. Applications: Outer lite of insuated glazing units
 - 3. Color: Clear.
 - 4. Thickness: As required for indicated performance of laminated glass application.

2.07 ACCESSORIES

- A. Setting Blocks: Silicone, with 80 to 90 Shore A durometer hardness; ASTM C864 Option II. Length of 0.1 inch for each square foot (25 mm for each square meter) of glazing or minimum 4 inch (100 mm) by width of glazing rabbet space minus 1/16 inch (1.5 mm) by height to suit glazing method and pane weight and area.
- B. Spacer Shims: Neoprene, 50 to 60 Shore A durometer hardness; ASTM C864 Option II. Minimum 3 inch (75 mm) long by one half the height of the glazing stop by thickness to suit application, self adhesive on one face.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- C. Glazing Tape, Back Bedding Mastic Type: Preformed, butyl-based, 100 percent solids compound with integral resilient spacer rod applicable to application indicated; 5 to 30 cured Shore A durometer hardness; coiled on release paper; black color.
 - 1. Width: As required for application.
 - 2. Thickness: As required for application.
 - 3. Spacer Rod Diameter: As required for application.
 - 4. Manufacturers:
 - a. Pecora Corporation: www.pecora.com/#sle.
 - b. Tremco Global Sealants: www.tremcosealants.com/#sle.
- D. Glazing Splines: Resilient silicone extruded shape to suit glazing channel retaining slot; ASTM C864 Option II; color black.

PART 3 EXECUTION

3.01 VERIFICATION OF CONDITIONS

- A. Verify that openings for glazing are correctly sized and within tolerances, including those for size, squareness, and offsets at corners.
- B. Verify that the minimum required face and edge clearances are being provided.
- C. Verify that surfaces of glazing channels or recesses are clean, free of obstructions that may impede moisture movement, weeps are clear, and support framing is ready to receive glazing system.
- D. Verify that sealing between joints of glass framing members has been completed effectively.
- E. Proceed with glazing system installation only after unsatisfactory conditions have been corrected.

3.02 PREPARATION

- A. Clean contact surfaces with appropriate solvent and wipe dry within maximum of 24 hours before glazing. Remove coatings that are not tightly bonded to substrates.
- B. Seal porous glazing channels or recesses with substrate compatible primer or sealer.
- C. Prime surfaces scheduled to receive sealant where required for proper sealant adhesion.

3.03 INSTALLATION, GENERAL

- A. Install glazing in compliance with written instructions of glass, gaskets, and other glazing material manufacturers, unless more stringent requirements are indicated, including those in glazing referenced standards.
- B. Install glazing sealants in accordance with ASTM C1193, GANA (SM), and manufacturer's instructions.
- C. Do not exceed edge pressures around perimeter of glass lites as stipulated by glass manufacturer.
- D. Set glass lites of system with uniform pattern, draw, bow, and similar characteristics.
- E. Set glass lites in proper orientation so that coatings face exterior or interior as indicated.
- F. Prevent glass from contact with any contaminating substances that may be the result of construction operations such as, and not limited to the following; weld splatter, fire-safing, plastering, mortar droppings, and paint.

3.04 INSTALLATION - DRY GLAZING METHOD (TAPE AND GASKET SPLINE GLAZING)

3.05 INSTALLATION - PRESSURE GLAZED SYSTEMS

- A. Application Exterior Glazed: Set glazing infills from exterior side of building.
- B. Place setting blocks at 1/4 points with edge block no more than 6 inch (152 mm) from corners.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- C. Rest glazing on setting blocks and push against fixed stop with sufficient pressure on gasket to attain full contact.
- D. Install pressure plates without displacing glazing gasket; exert pressure for full continuous contact.
- E. Install cover plate.

3.06 CLEANING

- A. See Section 017419 Construction Waste Management and Disposal, for additional requirements.
- B. Remove excess glazing materials from finish surfaces immediately after application using solvents or cleaners recommended by manufacturers.
- C. Remove nonpermanent labels immediately after glazing installation is complete.
- D. Clean glass and adjacent surfaces after sealants are fully cured.
- E. Clean glass on both exposed surfaces not more than 4 days prior to Date of Substantial Completion in accordance with glass manufacturer's written recommendations.

3.07 PROTECTION

- A. After installation, mark pane with an 'X' by using removable plastic tape or paste; do not mark heat absorbing or reflective glass units.
- B. Remove and replace glass that is damaged during construction period prior to Date of Substantial Completion.

3.08 SCHEDULES

- A. Aluminum-Framed Storefront Glazing: Glass Type IG-1 (Except South Elevation of Gym, install glass using dry method, and with glass thickness as required to comply with performance requirements indicated in Section 084313.
- B. Glazed Aluminum Curtain Wall Glazing: Glass Type IG-1, install glass using dry method, and with glass thickness required to comply with performance requirements indicated in Section 084413.

END OF SECTION 088000

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 088813 FIRE-RATED GLAZING

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Fire-rated glazing units.
- B. Glazing compounds.

1.02 RELATED REQUIREMENTS

A. Section 084435 - Protective Framed Glazing Assemblies: Glazing tested and provided as part of the wall assembly.

1.03 REFERENCE STANDARDS

- A. 16 CFR 1201 Safety Standard for Architectural Glazing Materials; Current Edition.
- B. ASTM C864 Standard Specification for Dense Elastomeric Compression Seal Gaskets, Setting Blocks, and Spacers; 2005 (Reapproved 2019).
- C. ASTM C920 Standard Specification for Elastomeric Joint Sealants; 2018.
- D. ASTM C1193 Standard Guide for Use of Joint Sealants; 2016 (Reapproved 2023).
- E. ASTM E1300 Standard Practice for Determining Load Resistance of Glass in Buildings; 2016.
- F. GANA (SM) GANA Sealant Manual; 2008.
- G. ICC (IBC) International Building Code; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- H. ITS (DIR) Directory of Listed Products; Current Edition.
- I. NFPA 252 Standard Methods of Fire Tests of Door Assemblies; 2022.
- J. NFPA 257 Standard on Fire Test for Window and Glass Block Assemblies; 2022.
- K. NFRC 100 Procedure for Determining Fenestration Product U-factors; 2023.
- L. NFRC 200 Procedure for Determining Fenestration Product Solar Heat Gain Coefficient and Visible Transmittance at Normal Incidence; 2023.
- M. NFRC 300 Test Method for Determining the Solar Optical Properties of Glazing Materials and Systems; 2023.
- N. UL (DIR) Online Certifications Directory; Current Edition.
- O. UL 9 Standard for Fire Tests of Window Assemblies; Current Edition, Including All Revisions.
- P. UL 10B Standard for Fire Tests of Door Assemblies; Current Edition, Including All Revisions.
- Q. UL 10C Standard for Positive Pressure Fire Tests of Door Assemblies; Current Edition, Including All Revisions.

1.04 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Product Data on Glazing Compounds and Accessories: Provide chemical, functional, and environmental characteristics, limitations, special application requirements, and identify available colors.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Glass Fabricators:
 - 1. Trulite Glass & Aluminum Solutions, LLC: www.trulite.com/#sle.
 - 2. Viracon, Inc: www.viracon.com/#sle.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- B. Float Glass Manufacturers:
 - 1. Cardinal Glass Industries: www.cardinalcorp.com/#sle.
 - 2. Guardian Glass, LLC: www.guardianglass.com/#sle.
 - 3. Pilkington North America Inc: www.pilkington.com/#sle.
 - 4. Vitro Architectural Glass (formerly PPG Glass): www.vitroglazings.com/#sle.
- C. Fire-Resistance-Rated Glass:
 - 1. Fabricators:
 - a. McGrory Glass, Inc: www.mcgrory.com/#sle.
 - b. Technical Glass Products; Pilkington Pyrostop: www.fireglass.com/#sle.
 - 2. Manufacturers:
 - a. SAFTIFIRST, a division of O'Keeffe's Inc; SuperLite II-XL: www.safti.com/#sle.
 - b. Pilkington North America Inc: www.pilkington.com/#sle.

2.02 PERFORMANCE REQUIREMENTS

- A. Provide type and thickness of exterior glazing assemblies to support assembly dead loads and withstand live loads caused by positive and negative wind pressure acting normal to plane of glass.
 - 1. Comply with ASTM E1300 for design load resistance of glass type, thickness, dimensions, and maximum lateral deflection of supported glass.
 - 2. Provide glass edge support system sufficiently stiff to limit lateral deflection of supported glass edges to less than 1/175 of their lengths under specified design load.
 - 3. Glass thicknesses listed are minimum.
- B. Vapor Retarder and Air Barrier Seals: Provide completed assemblies that maintain building enclosure vapor retarder and air barrier continuity.
- C. Thermal and Optical Performance: Provide exterior glazing products with performance properties as indicated, in accordance with manufacturer's published data as determined with the following procedures or test methods:
 - 1. Center of Glass U-Value: Comply with NFRC 100 using Lawrence Berkeley National Laboratory (LBNL) WINDOW software.
 - 2. Center of Glass Solar Heat Gain Coefficient (SHGC): Comply with NFRC 200 using Lawrence Berkeley National Laboratory (LBNL) WINDOW software.
 - 3. Solar Optical Properties: Comply with NFRC 300 test method.

2.03 GLASS MATERIALS

2.04 GLAZING UNITS

- A. Type FPG-1 Fire-Protection-Rated Glazing: Type, thickness, and configuration of glazing that contains flame, smoke, and does not block radiant heat, as required to achieve indicated fire rating period of 90 minutes or less.
 - 1. Applications:
 - a. Glazing in fire-resistance-rated door assembly.
 - b. Glazing in fire-resistance-rated window assembly.
 - 2. Provide products listed by ITS (DIR) or UL (DIR) and approved by authorities having jurisdiction.
 - 3. Safety Glazing Certification: 16 CFR 1201 Category II.
 - 4. Fire-Rating Period: As indicated on drawings.
 - 5. Markings for Fire-Protection-Rated Glazing Assemblies: Provide permanent markings on fire-protection-rated glazing in compliance with ICC (IBC), local building code, and authorities having jurisdiction
 - a. "D" meets fire door assembly criteria of NFPA 252, UL 10B, or UL 10C fire test standards.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- b. "OH" meets fire window assembly criteria, including hose stream test of NFPA 257 or UL 9 fire test standards.
- c. "H" meets fire door assembly hose stream test of NFPA 252, UL 10B, or UL 10C fire tests standards.
- d. "XXX" placeholder that represents fire-rating period, in minutes.

2.05 GLAZING COMPOUNDS

- A. Type GC-1 Silicone Sealant: Single component; neutral curing; capable of water immersion without loss of properties; nonbleeding, nonstaining; ASTM C920 Type S, Grade NS, Class 25, Uses M, A, and G; with cured Shore A hardness range of 15 to 25; _____ color.
 - 1. Manufacturers:
 - a. BASF Corporation: www.basf.com/#sle.
 - b. Bostik Inc: www.bostik-us.com/#sle.
 - c. Dow Corning Corporation: www.dowcorning.com/construction/#sle.
 - d. Momentive Performance Materials, Inc: www.momentive.com/#sle.
 - e. Pecora Corporation; ____: www.pecora.com/#sle.

2.06 ACCESSORIES

- A. Setting Blocks: Aluminum silicate, with 80 to 90 Shore A durometer hardness; ASTM C864 Option II. Length of 0.1 inch for each square foot (25 mm for each square meter) of glazing or minimum 4 inch (100 mm) by width of glazing rabbet space minus 1/16 inch (1.5 mm) by height to suit glazing method and pane weight and area.
- B. Glazing Tape: Closed-cell polyvinyl chloride (PVC) foam, coiled on release paper over adhesive on two sides, maximum water absorption by volume of 2 percent, designed for compression of 25 percent to affect air barrier and vapor retarder seal.
 - 1. Manufacturers:
 - a. Pecora Corporation: www.pecora.com/#sle.
 - b. Saint-Gobain Performance Plastics: www.plastics.saint-gobain.com/#sle.
- C. Glazing Gaskets: Flexible intumescent seals.
- D. Glazing Splines: Resilient silicone extruded shape to suit glazing channel retaining slot; ASTM C864 Option II; color black.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that openings for glazing are correctly sized and within tolerances, including those for size, squareness, and offsets at corners.
- B. Verify that surfaces of glazing channels or recesses are clean, free of obstructions that may impede moisture movement, weeps are clear, and support framing is ready to receive glazing system.

3.02 PREPARATION

- A. Clean contact surfaces with appropriate solvent and wipe dry within maximum of 24 hours before glazing. Remove coatings that are not tightly bonded to substrates.
- B. Seal porous glazing channels or recesses with substrate compatible primer or sealer.
- C. Prime surfaces scheduled to receive sealant where required for proper sealant adhesion.

3.03 INSTALLATION - GENERAL

- A. Install glazing in compliance with written instructions of glass, gaskets, and other glazing material manufacturers unless more stringent requirements are indicated, including those in referenced glazing standards.
- B. Install glazing sealants in accordance with ASTM C1193, GANA (SM), and manufacturer's instructions.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- C. Do not exceed edge pressures around perimeter of glass lites as stipulated by glass manufacturer.
- D. Set glass lites of system with uniform pattern, draw, bow, and similar characteristics.
- E. Set glass lites in proper orientation so that coatings face exterior or interior as indicated.
- F. Prevent glass from contact with contaminating substances that may result from construction operations including, but not limited to weld spatter, fire-safing, plastering, mortar droppings, etc.

3.04 CLEANING

- A. See Section 017000 Execution and Closeout Requirements for additional requirements.
- B. Remove excess glazing materials from finish surfaces immediately after application using solvents or cleaners recommended by manufacturers.
- C. Remove nonpermanent labels immediately after glazing installation is complete.
- D. Clean glass and adjacent surfaces after sealants are fully cured.
- E. Clean glass on both exposed surfaces not more than four days prior to Date of Substantial Completion in accordance with glass manufacturer's written recommendations.

3.05 PROTECTION

- A. After installation, mark pane with 'X' by using removable plastic tape or paste; do not mark heat-absorbing or reflective glass units.
- B. Remove and replace glass that is damaged during construction period prior to Date of Substantial Completion.

END OF SECTION 088813

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 092116 GYPSUM BOARD ASSEMBLIES

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Performance criteria for gypsum board assemblies.
- B. Metal stud wall framing.
- C. Metal channel ceiling framing.
- D. Acoustic insulation.
- E. Gypsum wallboard.
- F. Joint treatment and accessories.
- G. Plenum space sound control.

1.02 RELATED REQUIREMENTS

- A. Section 061000 Rough Carpentry: Building framing and sheathing.
- B. Section 072500 Weather Barriers: Water-resistive barrier over sheathing.

1.03 REFERENCE STANDARDS

- A. AISI S220 North American Standard for Cold-Formed Steel Nonstructural Framing; 2020.
- B. AISI S240 North American Standard for Cold-Formed Steel Structural Framing; 2015, with Errata (2020).
- C. ASHRAE Std 62.1 Ventilation for Acceptable Indoor Air Quality; Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
- D. ASTM A36/A36M Standard Specification for Carbon Structural Steel; 2019.
- E. ASTM A1003/A1003M Standard Specification for Steel Sheet, Carbon, Metallic- and Nonmetallic-Coated for Cold-Formed Framing Members; 2015.
- F. ASTM B221 Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes; 2021.
- G. ASTM C1007 Standard Specification for Installation of Load Bearing (Transverse and Axial) Steel Studs and Related Accessories; 2020.
- H. ASTM C475/C475M Standard Specification for Joint Compound and Joint Tape for Finishing Gypsum Board; 2017 (Reapproved 2022).
- I. ASTM C665 Standard Specification for Mineral-Fiber Blanket Thermal Insulation for Light Frame Construction and Manufactured Housing; 2023.
- J. ASTM C754 Standard Specification for Installation of Steel Framing Members to Receive Screw-Attached Gypsum Panel Products; 2020.
- K. ASTM C840 Standard Specification for Application and Finishing of Gypsum Board; 2023.
- L. ASTM C954 Standard Specification for Steel Drill Screws for the Application of Gypsum Panel Products or Metal Plaster Bases to Steel Studs from 0.033 in. (0.84 mm) to 0.112 in. (2.84 mm) in Thickness; 2022.
- M. ASTM C1002 Standard Specification for Steel Self-Piercing Tapping Screws for Application of Gypsum Panel Products or Metal Plaster Bases to Wood Studs or Steel Studs; 2022.
- N. ASTM C1047 Standard Specification for Accessories for Gypsum Wallboard and Gypsum Veneer Base; 2019.
- O. ASTM C1396/C1396M Standard Specification for Gypsum Board; 2017.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- P. ASTM D3273 Standard Test Method for Resistance to Growth of Mold on the Surface of Interior Coatings in an Environmental Chamber; 2021.
- Q. ASTM E84 Standard Test Method for Surface Burning Characteristics of Building Materials; 2023d.
- R. ASTM E90 Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements; 2023.
- S. ASTM E413 Classification for Rating Sound Insulation; 2022.
- T. GA-216 Application and Finishing of Gypsum Panel Products; 2024.
- U. UL 723 Standard for Test for Surface Burning Characteristics of Building Materials; Current Edition, Including All Revisions.
- V. UL 2079 Standard for Tests for Fire Resistance of Building Joint Systems; Current Edition, Including All Revisions.

1.04 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Product Data:
 - 1. Provide data on metal framing, gypsum board, accessories, and joint finishing system.
- C. Shop Drawings: Indicate special details associated with fireproofing and acoustic seals.

1.05 QUALITY ASSURANCE

A. Designer Qualifications: Perform design under direct supervision of a Professional Engineer experienced in design of this type of work and licensed in the State in which the Project is located.

1.06 DELIVERY, STORAGE, AND HANDLING

- A. See Section 017419 Construction Waste Management and Disposal for packaging waste requirements.
- B. Store gypsum products and accessories indoors and keep above freezing. Elevate boards above floor, on nonwicking supports, in accordance with manufacturer's recommendations.
- C. Store metal products to prevent corrosion, under cover and above grade.

PART 2 PRODUCTS

2.01 GYPSUM BOARD ASSEMBLIES

- A. Provide completed assemblies complying with ASTM C840 and GA-216.
- B. Interior Partitions, Indicated as Acoustic: Provide completed assemblies with the following characteristics:
 - 1. Acoustic Attenuation: STC as indicated calculated in accordance with ASTM E413, based on tests conducted in accordance with ASTM E90.
- C. Shaft Walls at HVAC Shafts: Provide completed assemblies with the following characteristics:
 - 1. Air Pressure Within Shaft: Sustained loads of 5 lbf/sq ft (0.24 kPa) with maximum midspan deflection of L/240.
 - 2. Acoustic Attenuation: STC of 39 calculated in accordance with ASTM E413, based on tests conducted in accordance with ASTM E90.
- D. Fire-Resistance-Rated Assemblies: Provide completed assemblies per partition details on architectural sheets.

2.02 BOARD MATERIALS

- A. Manufacturers Gypsum-Based Board:
 - 1. American Gypsum Company; www.americangypsum.com/#sle.
 - 2. CertainTeed Corporation; www.certainteed.com/#sle.

FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- 3. Georgia-Pacific Gypsum: www.gpgypsum.com/#sle.
- 4. Gold Bond Building Products, LLC provided by National Gypsum Company: www.goldbondbuilding.com/#sle.
- 5. PABCO Gypsum: www.pabcogypsum.com/#sle.
- 6. USG Corporation: www.usg.com/#sle.
- 7. Substitutions: See Section 016000 Product Requirements.
- B. Gypsum Wallboard: Paper-faced gypsum panels as defined in ASTM C1396/C1396M; sizes to minimize joints in place; ends square cut.
 - 1. Application: Use for vertical surfaces and ceilings, unless otherwise indicated.
 - 2. At Assemblies Indicated with Fire-Resistance Rating: Use type required by indicated tested assembly; if no tested assembly is indicated, use Type X board, UL or WH listed.
 - 3. Thickness:
 - a. Vertical Surfaces: 5/8 inch (16 mm).
 - b. Ceilings: 5/8 inch (16 mm).
 - 4. Paper-Faced Products:
 - a. American Gypsum Company; FireBloc Type X Gypsum Wallboard: www.americangypsum.com/#sle.
 - b. CertainTeed Corporation; Type X Drywall: www.certainteed.com/#sle.
 - c. Georgia-Pacific Gypsum; ToughRock Fireguard X: www.gpgypsum.com/#sle.
 - d. Gold Bond Building Products, LLC provided by National Gypsum Company; Gold Bond Fire-Shield C 5/8" Gypsum Board: www.goldbondbuilding.com/#sle.
 - e. USG Corporation; Sheetrock Brand EcoSmart Panels Firecode X 5/8 in. (15.9 mm): www.usg.com/#sle.
 - f. Substitutions: See Section 016000 Product Requirements.
 - 5. Glass Mat Faced Products:
 - a. CertainTeed Corporation; 5/8" GlasRoc Interior Type X: www.certainteed.com/#sle.
 - b. Georgia-Pacific Gypsum; DensArmor Plus Fireguard C: www.gpgypsum.com/#sle.
 - c. Gold Bond Building Products, LLC provided by National Gypsum Company; Gold Bond eXP Interior Extreme Fire-Shield Gypsum Panel: www.goldbondbuilding.com/#sle.
 - d. USG Corporation; Sheetrock Brand Glass-Mat Panels Mold Tough Regular 5/8 in. (15.9 mm): www.usg.com/#sle.
 - e. Substitutions: See Section 016000 Product Requirements.
- C. Impact Resistant Wallboard:
 - 1. Application: High-traffic areas indicated.
 - 2. Mold Resistance: Score of 10, when tested in accordance with ASTM D3273.
 - 3. Type: Fire-resistance-rated Type X, UL or WH listed.
 - 4. Thickness: 5/8 inch (16 mm).
 - 5. Edges: Tapered.
- D. Backing Board For Non-Wet Areas: Water-resistant gypsum backing board as defined in ASTM C1396/C1396M; sizes to minimum joints in place; ends square cut.
 - 1. Application: Vertical surfaces behind thinset tile, except in wet areas.
 - 2. Mold Resistance: Score of 10, when tested in accordance with ASTM D3273.
 - 3. Type: Type X, in locations indicated.
 - 4. Type X Thickness: 5/8 inch (16 mm).
 - 5. Regular Board Thickness: 5/8 inch (16 mm).
 - 6. Edges: Tapered.
 - 7. Products:
 - a. American Gypsum Company; M-Bloc: www.americangypsum.com/#sle.
 - b. American Gypsum Company; M-Bloc Type X: www.americangypsum.com/#sle.

FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- c. Georgia-Pacific Gypsum; ToughRock Mold-Guard Gypsum Board: www.gpgypsum.com/#sle.
- d. Georgia-Pacific Gypsum; DensArmor Plus: www.gpgypsum.com/#sle.
- e. Gold Bond Building Products, LLC provided by National Gypsum Company; Gold Bond XP Fire-Shield Gypsum Board: www.goldbondbuilding.com/#sle.
- f. Substitutions: See Section 016000 Product Requirements.
- E. Exterior Sheathing Board: See Section 061000.
- F. Shaftwall and Coreboard: Type X; 1 inch (25 mm) thick by 24 inches (600 mm) wide, beveled long edges, ends square cut.
 - 1. Paper-Faced Type: Gypsum shaftliner board or gypsum coreboard as defined ASTM C1396/C1396M; water-resistant faces.
 - 2. Paper-Faced Products:
 - a. American Gypsum Company; M-Bloc Shaft Liner: www.americangypsum.com/#sle.
 - b. CertainTeed Corporation; M2Tech Type X Shaftliner: www.certainteed.com/#sle.
 - c. Georgia-Pacific Gypsum; ToughRock Shaftliner: www.gpgypsum.com/#sle.
 - d. Gold Bond Building Products, LLC provided by National Gypsum Company; Gold Bond Shaftliner XP: www.goldbondbuilding.com/#sle.
 - e. USG Corporation; Sheetrock Brand Gypsum Liner Panels 1 in. (25.4 mm) SLX: www.usg.com/#sle.
 - f. Substitutions: See Section 016000 Product Requirements.

2.03 PLENUM SPACE SOUND CONTROL

- A. Description: Acoustical extension wall board for noise control within ceiling plenums above wall partitions.
- B. General Requirements:
 - 1. Airstream surfaces installed in return air plenum to comply with requirements in ASHRAE Std 62.1.
- C. Materials:

1.

- Mineral Fiber Insulation Board:
 - a. Surface Burning Characteristics: Flame spread/smoke development index of 0/0 when tested in accordance with ASTM E84 or UL 723.
- 2. Return-Air Silencer:
 - a. Fabricate in accordance with SMACNA (DCS) HVAC Duct Construction Standards.

2.04 GYPSUM BOARD ACCESSORIES

- A. Acoustic Insulation: ASTM C665; preformed mineral-fiber, friction fit type, unfaced; thickness per partition details.
- B. Acoustic Sealant: Acrylic emulsion latex or water-based elastomeric sealant; do not use solvent-based non-curing butyl sealant.
 - 1. Products:
 - a. Franklin International, Inc; Titebond Acoustical Smoke & Sound Sealant: www.titebond.com/#sle.
 - b. Liquid Nails, a brand of PPG Architectural Coatings: www.liquidnails.com/#sle.
 - c. Specified Technologies Inc; Smoke N Sound Acoustical Sealant: www.stifirestop.com/#sle.
 - d. Substitutions: See Section 016000 Product Requirements.
- C. Sound Barrier Mullion Trim Cap: Extruded aluminum trim for maintaining sound barriers at intersections between gypsum walls and glazing assemblies.
 - 1. STC: 55.
 - 2. Fire Rating: 1 hour at rated partition shown in drawings, when tested in accordance with UL 2079.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 3. Gasket Thickness: 1/2 inch (12.7 mm).
- 4. Finish: Match glazing assembly framing finish.
- 5. Products:
 - a. Mull-It-Over Products, Inc; Mull-It-Over 55 Classic: mullitoverproducts.com/#sle.
 - b. Substitutions: See Section 016000 Product Requirements.
- D. Water-Resistive Barrier: See Section 072500.
- E. Beads, Joint Accessories, and Other Trim: ASTM C1047, rigid plastic, galvanized steel, or rolled zinc, unless noted otherwise.
 - 1. Corner Beads: Low profile, for 90 degree outside corners.
 - 2. Expansion Joints:
 - a. Products:
 - 1) Phillips Manufacturing Co; 093 Expansion Control Joint:
 - www.phillipsmfg.com/#sle.
 - 2) Substitutions: See Section 016000 Product Requirements.
- F. Joint Materials: ASTM C475/C475M and as recommended by gypsum board manufacturer for project conditions.
 - 1. Paper Tape: 2 inch (50 mm) wide, creased paper tape for joints and corners, except as otherwise indicated.
 - 2. Joint Compound: Drying type, vinyl-based, at:
 - a. Embedding tape and first coat on joints, fasteners and trim flanges.
 - b. For fill coat (second coat) and third coat.
 - 3. Joint Compound: Setting type, field-mixed at:
 - a. Prefilling at open joints, rounded or beveled panel edges and damaged surface areas.
- G. Finishing Compound: Surface coat and primer, takes the place of skim coating.
- H. Screws for Fastening of Gypsum Panel Products to Cold-Formed Steel Studs Less than 0.033 inches (0.84 mm) in Thickness and Wood Members: ASTM C1002; self-piercing tapping screws, corrosion-resistant.
- I. Screws for Fastening of Gypsum Panel Products to Steel Members from 0.033 to 0.112 inch (0.84 to 2.84 mm) in Thickness: ASTM C954; steel drill screws, corrosion-resistant.
- J. Exterior Soffit Vents: One piece, perforated, ASTM B221 6063 T5 alloy aluminum, with edge suitable for direct application to gypsum board and manufactured especially for soffit application. Provide continuous vent.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that project conditions are appropriate for work of this section to commence.

3.02 SHAFT WALL INSTALLATION

- A. Shaft Wall Framing: Install in accordance with manufacturer's installation instructions.
 - 1. Fasten runners to structure with short leg to finished side, using appropriate power-driven fasteners at not more than 24 inches (600 mm) on center.
 - 2. Install studs at spacing required to meet performance requirements.
- B. Shaft Wall Liner: Cut panels to accurate dimensions and install sequentially between special friction studs.

3.03 FRAMING INSTALLATION

- A. Metal Framing: Install in accordance with ASTM C1007AISI S220 and manufacturer's instructions.
- B. Studs: Space studs at 16 inches on center (at 406 mm on center).
FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- 1. Extend partition framing to structure where indicated and to ceiling in other locations.
- 2. Partitions Terminating at Ceiling: Attach ceiling runner securely to ceiling track in accordance with manufacturer's instructions.
- 3. Partitions Terminating at Structure: Attach extended leg top runner to structure, maintain clearance between top of studs and structure, and brace both flanges of studs with continuous bridging.
- C. Standard Wall Furring: Install at concrete and masonry walls scheduled to receive gypsum board, not more than 4 inches (100 mm) from floor and ceiling lines and abutting walls. Secure in place on alternate channel flanges at maximum 24 inches (600 mm) on center.
- D. Acoustic Furring: Install resilient channels at maximum 24 inches (600 mm) on center. Locate joints over framing members. DO NOT ATTACH WALLBOARD AT STUDS.
- E. Blocking: Install mechanically fastened steel sheet blocking for support of:
 - 1. Framed openings.
 - 2. Wall-mounted cabinets.
 - 3. Plumbing fixtures.
 - 4. Toilet partitions.
 - 5. Toilet accessories.
 - 6. Wall-mounted door hardware.

3.04 ACOUSTIC ACCESSORIES INSTALLATION

- A. Acoustic Insulation: Place tightly within spaces, around cut openings, behind and around electrical and mechanical items within partitions, and tight to items passing through partitions.
- B. Acoustic Sealant: Install in accordance with manufacturer's instructions.
 - 1. Place one bead continuously on each side of head track and runner at sill, as shown on drawings.
 - 2. Seal around all penetrations by conduit, pipe, ducts, and rough-in boxes, except where firestopping is provided.
- C. Sound Barrier Mullion Trim Cap Installation: Install in accordance with manufacturer's instructions for installation of fire-rated mullion trim caps.

3.05 BOARD INSTALLATION

- A. Comply with ASTM C840, GA-216, and manufacturer's instructions. Install to minimize butt end joints, especially in highly visible locations.
- B. Fire-Resistance-Rated Construction: Install gypsum board in strict compliance with requirements of assembly listing.
- C. Exposed Gypsum Board in Interior Wet Areas: Seal joints, cut edges, and holes with waterresistant sealant.

3.06 INSTALLATION OF TRIM AND ACCESSORIES

- A. Control Joints: Place control joints consistent with lines of building spaces and as indicated.
 - 1. Not more than 30 feet (10 meters) apart on walls and ceilings over 50 feet (16 meters) long.
- B. Corner Beads: Install at external corners, using longest practical lengths.
- C. Edge Trim: Install at locations where gypsum board abuts dissimilar materials.
- D. Exterior Soffit Vents: Install according to manufacturer's written instructions and in locations indicated on drawings. Provide vent area specified.

3.07 JOINT TREATMENT

A. Glass Mat Faced Gypsum Board and Exterior Glass Mat Faced Sheathing: Use fiberglass joint tape, embed and finish with setting type joint compound.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- B. Finish gypsum board in accordance with levels defined in ASTM C840, as follows:
 - 1. Level 5: Walls and ceilings to receive semi-gloss or gloss paint finish and other areas specifically indicated.
 - 2. Level 4: Walls and ceilings to receive paint finish or wall coverings, unless otherwise indicated.
 - 3. Level 3: Walls to receive textured wall finish.
 - 4. Level 2: In utility areas, behind cabinetry, and on backing board to receive tile finish.
 - 5. Level 1: Fire-resistance-rated wall areas above finished ceilings, whether or not accessible in the completed construction.
- C. Tape, fill, and sand exposed joints, edges, and corners to produce smooth surface ready to receive finishes.
 - 1. Feather coats of joint compound so that camber is maximum 1/32 inch (0.8 mm).
 - 2. Taping, filling, and sanding are not required at surfaces behind adhesive applied ceramic tile and fixed cabinetry.
- D. Where Level 5 finish is indicated, spray apply high build drywall surfacer over entire surface after joints have been properly treated; achieve a flat and tool mark-free finish.

3.08 TOLERANCES

A. Maximum Variation of Finished Gypsum Board Surface from True Flatness: 1/8 inch in 10 feet (3 mm in 3 m) in any direction.

3.09 PROTECTION

A. Protect installed gypsum board assemblies from subsequent construction operations.

FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 092216 NON-STRUCTURAL METAL FRAMING

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Metal partition, ceiling, and soffit framing.

1.02 REFERENCE STANDARDS

- A. AISI S100 North American Specification for the Design of Cold-Formed Steel Structural Members; 2016, with Supplement (2020).
- B. AISI S220 North American Standard for Cold-Formed Steel Nonstructural Framing; 2020.
- C. ASTM A36/A36M Standard Specification for Carbon Structural Steel; 2019.
- D. ASTM A653/A653M Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process; 2023.
- E. ASTM A1003/A1003M Standard Specification for Steel Sheet, Carbon, Metallic- and Nonmetallic-Coated for Cold-Formed Framing Members; 2015.
- F. ASTM C754 Standard Specification for Installation of Steel Framing Members to Receive Screw-Attached Gypsum Panel Products; 2020.
- G. ASTM C1002 Standard Specification for Steel Self-Piercing Tapping Screws for Application of Gypsum Panel Products or Metal Plaster Bases to Wood Studs or Steel Studs; 2022.

1.03 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Shop Drawings:
 - 1. Indicate prefabricated work, component details, stud layout, framed openings, anchorage to structure, acoustic details, type and location of fasteners, accessories, and items of other related work.
 - 2. Describe method for securing studs to tracks, splicing, and for blocking and reinforcement of framing connections.
- C. Product Data: Provide manufacturer's data on partition head to structure connectors, showing compliance with requirements.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Metal Framing, Connectors, and Accessories:
 - 1. CEMCO: www.cemcosteel.com/#sle.
 - 2. ClarkDietrich: www.clarkdietrich.com/#sle.
 - 3. Jaimes Industries: www.jaimesind.com/#sle.
 - 4. MarinoWARE: www.marinoware.com/#sle.
 - 5. R-stud: www.rstud.com/#sle.
 - 6. SCAFCO Corporation: www.scafco.com/#sle.
 - 7. Simpson Strong Tie: www.strongtie.com/#sle.
 - 8. Substitutions: See Section 016000 Product Requirements.

2.02 FRAMING MATERIALS

- A. Non-Loadbearing Framing System Components: AISI S220; sheet steel, of size and properties necessary for the spacing indicated, with maximum deflection of wall framing of L/240 at 5 psf (L/240 at 240 Pa).
 - 1. Studs: C-shaped with flat faces.
 - a. Products:
 - 1) CEMCO; CT Studs: www.cemcosteel.com/#sle.

FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- 2) ClarkDietrich; ProSTUD: www.clarkdietrich.com/#sle.
- 3) MarinoWARE; ViperStud Drywall Framing: www.marinoware.com/#sle.
- 4) MBA Building Supplies; ProSTUD: www.mbastuds.com/#sle.
- 5) R-stud; R-stud: www.rstud.com/#sle.
- 6) Super Stud Building Products, Inc; The EDGE: www.buysuperstud.com/#sle.
- 2. Runners: U-shaped, sized to match studs.
- 3. Ceiling Channels: C-shaped.
- 4. Furring: Hat-shaped sections, minimum depth of 7/8 inch (22 mm).
- B. Shaft Wall Studs and Accessories: AISI S220; galvanized sheet steel, of size and properties necessary to comply with ASTM C754 and specified performance requirements.
- C. Partition Head to Structure Connections: Provide mechanical anchorage devices that accommodate deflection using slotted holes, screws, and anti-friction bushings, preventing rotation of studs while maintaining structural performance of partition.
 - 1. Structural Performance: Maintain lateral load resistance and vertical movement capacity required by applicable code when evaluated in accordance with AISI S100.
 - 2. Material: ASTM A653/A653M steel sheet, SS Grade 50.
- D. Non-Loadbearing Framing Accessories:
 - 1. Ceiling Hangers: Type and size as specified in ASTM C754 for spacing required.
 - 2. Partial Height Wall Framing Support: Provides stud reinforcement and anchored connection to floor.
 - a. Materials: ASTM A36/A36M formed sheet steel support member with factory-welded ASTM A1003/A1003M steel plate base.
 - b. Height: 47-3/4 inches (1213 mm).
 - c. Products:
 - 1) ClarkDietrich; Pony Wall (PW): www.clarkdietrich.com/#sle.
 - 2) Simpson Strong-Tie; RCKW Kneewall Connector: www.strongtie.com/#sle.
 - 3) Substitutions: See Section 016000 Product Requirements.
 - 3. Sheet Metal Backing: 0.0395 inch (1.01 mm) thick.
 - 4. Fasteners: ASTM C1002 self-piercing self-tapping screws.

2.03 FABRICATION

- A. Fabricate assemblies of framed sections to sizes and profiles required.
- B. Fit, reinforce, and brace framing members to suit design requirements.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify existing conditions before starting work.
- B. Verify that rough-in utilities are in proper location.

3.02 INSTALLATION OF STUD FRAMING

- A. Extend partition framing to structure where indicated and to ceiling in other locations.
- B. Partitions Terminating at Ceiling: Attach ceiling runner securely to ceiling track in accordance with manufacturer's instructions.
- C. Partitions Terminating at Structure: Attach extended leg top runner to structure, maintain clearance between top of studs and structure, and brace both flanges of studs as indicated.
- D. Align and secure top and bottom runners at 24 inches (600 mm) on center.
- E. Fit runners under and above openings; secure intermediate studs to same spacing as wall studs.
- F. Align stud web openings horizontally.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- G. Secure studs to tracks using crimping method. Do not weld.
- H. Fabricate corners using a minimum of three studs.
- I. Install double studs at wall openings, door and window jambs, not more than 2 inches (50 mm) from each side of openings.
- J. Coordinate installation of bucks, anchors, and blocking with electrical, mechanical, and other work to be placed within or behind stud framing.
- K. Furring: Install at spacing and locations shown on drawings. Lap splices a minimum of 6 inches (150 mm).

3.03 CEILING AND SOFFIT FRAMING

- A. Install furring after work above ceiling or soffit is complete. Coordinate the location of hangers with other work.
- B. Install furring independent of walls, columns, and above-ceiling work.
- C. Securely anchor hangers to structural members or embed them in structural slab. Space hangers as required to limit deflection to criteria indicated. Use rigid hangers at exterior soffits.
- D. Space main carrying channels at maximum 72 inches (1 800 mm) on center, and not more than 6 inches (150 mm) from wall surfaces. Lap splice securely.
- E. Securely fix carrying channels to hangers to prevent turning or twisting and to transmit full load to hangers.
- F. Place furring channels perpendicular to carrying channels, not more than 2 inches (50 mm) from perimeter walls, and rigidly secure. Lap splices securely.

3.04 TOLERANCES

- A. Maximum Variation From True Position: 1/8 inch in 10 feet (3 mm in 3 m).
- B. Maximum Variation From Plumb: 1/8 inch in 10 feet (3 mm in 3 m).

FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 093000 TILING

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Tile for floor applications.
- B. Tile for wall applications.
- C. Coated glass mat backer board as tile substrate.
- D. Ceramic accessories.
- E. Ceramic trim.
- F. Non-ceramic trim.

1.02 REFERENCE STANDARDS

- A. ANSI A108/A118/A136 American National Standard Specifications for the Installation of Ceramic Tile (Compendium); 2024.
- B. ANSI A108.1a American National Standard Specifications for Installation of Ceramic Tile in the Wet-Set Method, with Portland Cement Mortar; 2023.
- C. ANSI A108.1b Installation of Ceramic Tile on a Cured Portland Cement Mortar Setting Bed with Dry-Set, Modified Dry-Set, or Improved Modified Dry-Set Cement Mortar; 2023.
- D. ANSI A108.1c Contractor's Option: Installation of Ceramic Tile in the Wet-Set Method with Portland Cement Mortar or Installation of Ceramic Tile on a Cured Portland Cement Mortar Setting Bed with Dry-Set, Modified Dry-Set, or Improved Modified Dry-Set Cement Mortar; 2023.
- E. ANSI A108.2 American National Standard General Requirements: Materials, Environmental and Workmanship; 2019.
- F. ANSI A108.4 American National Standard Specifications for Installation of Ceramic Tile with Organic Adhesive or Water Cleanable Tile-Setting Epoxy Adhesive; 2023.
- G. ANSI A108.5 Setting of Ceramic Tile with Dry-Set Cement Mortar, Modified Dry-Set Cement Mortar, EGP (Exterior Glue Plywood) Modified Dry-Set Cement Mortar, or Improved Modified Dry-Set Cement Mortar; 2023.
- H. ANSI A108.6 American National Standard Specifications for Installation of Ceramic Tile with Chemical Resistant, Water Cleanable Tile-Setting and -Grout Epoxy; 2023.
- I. ANSI A108.8 American National Standard Specifications for Installation of Ceramic Tile with Chemical Resistant Furan Resin Mortar and Grout; 1999 (Reaffirmed 2024).
- J. ANSI A108.9 American National Standard Specifications for Installation of Ceramic Tile with Modified Epoxy Emulsion Mortar/Grout; 2023.
- K. ANSI A108.10 American National Standard Specifications for Installation of Grout in Tilework; 2017 (Reaffirmed 2022).
- L. ANSI A108.11 American National Standard Specifications for Interior Installation of Cementitious Backer Units; 2023.
- M. ANSI A108.12 Installation of Ceramic Tile with EGP (Exterior Glue Plywood) Modified Dry-Set Mortar; 2023.
- N. ANSI A108.13 American National Standard for Installation of Load Bearing, Bonded, Waterproof Membranes for Thin-Set Ceramic Tile and Dimension Stone; 2005 (Reaffirmed 2021).
- O. ANSI A108.19 American National Standard Specifications for Interior Installation of Gauged Porcelain Tiles and Gauged Porcelain Tile Panels/Slabs by the Thin-Bed Method Bonded with

Modified Dry-Set Cement Mortar or Improved Modified Dry-Set Cement Mortar; 2020.

- P. ANSI A108.20 American National Standard Specifications for Exterior Installation of Gauged Porcelain Tile Panels/Slabs; 2020.
- Q. ANSI A118.3 American National Standard Specifications for Chemical Resistant, Water Cleanable Tile-Setting and -Grouting Epoxy and Water Cleanable Tile-Setting Epoxy Adhesive; 2021.
- R. ANSI A118.4 American National Standard Specifications for Modified Dry-Set Cement Mortar; 2023.
- S. ANSI A118.6 American National Standard Specifications for Standard Cement Grouts for Tile Installation; 2019.
- T. ANSI A118.7 American National Standard Specifications for High Performance Cement Grouts for Tile Installation; 2019.
- U. ANSI A118.10 American National Standard Specifications for Load Bearing, Bonded, Waterproof Membranes for Thin-Set Ceramic Tile and Dimension Stone Installation; 2023.
- V. ANSI A118.12 American National Standard Specifications for Crack Isolation Membranes for Thin-Set Ceramic Tile and Dimension Stone Installation; 2014 (Reaffirmed 2019).
- W. ANSI A118.15 American National Standard Specifications for Improved Modified Dry-Set Cement Mortar; 2023.
- X. ANSI A136.1 American National Standard Specifications for Organic Adhesives for Installation of Ceramic Tile; 2020.
- Y. ANSI A137.1 American National Standard Specifications for Ceramic Tile; 2022.
- Z. ASTM C373 Standard Test Methods for Determination of Water Absorption and Associated Properties by Vacuum Method for Pressed Ceramic Tiles and Glass Tiles and Boil Method for Extruded Ceramic Tiles and Non-tile Fired Ceramic Whiteware Products; 2018 (Reapproved 2023).
- AA. ASTM C1178/C1178M Standard Specification for Coated Glass Mat Water-Resistant Gypsum Backing Panel; 2018.
- BB. ASTM F710 Standard Practice for Preparing Concrete Floors to Receive Resilient Flooring; 2022.
- CC. ASTM F1869 Standard Test Method for Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride; 2023.
- DD. ASTM F2170 Standard Test Method for Determining Relative Humidity in Concrete Floor Slabs Using in situ Probes; 2019a.
- EE. TCNA (HB) Handbook for Ceramic, Glass, and Stone Tile Installation; 2024.

1.03 ADMINISTRATIVE REQUIREMENTS

A. Preinstallation Meeting: Convene a preinstallation meeting one week before starting work of this section; require attendance by affected installers.

1.04 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Product Data: Provide manufacturers' data sheets on tile, mortar, grout, and accessories. Include instructions for using grouts and adhesives.
- C. Shop Drawings: Indicate tile layout, patterns, color arrangement, perimeter conditions, junctions with dissimilar materials, control and expansion joints, thresholds, ceramic accessories, and setting details.
- D. Samples: Mount tile and apply grout on two plywood panels, minimum 18 by 18 inches (457 by 457 mm) in size illustrating pattern, color variations, and grout joint size variations.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- E. Manufacturer's Certificate: Certify that products meet or exceed specified requirements.
- F. Master Grade Certificate: Submit for each type of tile, signed by the tile manufacturer and tile installer.
- G. Installer's Qualification Statement:
 - 1. Submit documentation of National Tile Contractors Association (NTCA) or Tile Contractors' Association of America (TCAA) accreditation.
- H. Maintenance Data: Include recommended cleaning methods, cleaning materials, and stain removal methods.
- I. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
 - 1. See Section 016000 Product Requirements, for additional provisions.
 - 2. Extra Tile: 2 percent of each size, color, and surface finish combination.

1.05 QUALITY ASSURANCE

- A. Maintain one copy of ANSI A108/A118/A136 and TCNA (HB) on site.
- B. Installer Qualifications: Natural Stone Institute (NSI) Accredited Commercial B Contractor (light commercial): www.naturalstoneinstitute.org/#sle.
- C. Installer Qualifications:
 - 1. Company specializing in performing tile installation, with minimum of five years of documented experience.

1.06 MOCK-UPS

- A. See Section 014000 Quality Requirements for general requirements for mock-up.
- B. Construct tile mock-up where indicated on drawings, incorporating all components specified for the location.
 - 1. Minimum size of mock-up is indicated on drawings.
 - 2. Approved mock-up may remain as part of work.

1.07 DELIVERY, STORAGE, AND HANDLING

A. Protect adhesives from freezing or overheating in accordance with manufacturer's instructions.

1.08 FIELD CONDITIONS

- A. Do not install solvent-based products in an unventilated environment.
- B. Maintain ambient and substrate temperature above 50 degrees F (10 degrees C) and below 100 degrees F (38 degrees C) during installation and curing of setting materials.

PART 2 PRODUCTS

2.01 TILE

- A. Manufacturers: All products of each type by the same manufacturer.
 - 1. American Olean Corporation: www.americanolean.com/#sle.
 - 2. Architessa: www.architessa.com/#sle.
 - 3. Dal-Tile Corporation: www.daltile.com/#sle.
 - 4. Emser Tile, LLC: www.emser.com/#sle.
 - 5. Florim USA: www.milestonetiles.com/#sle.
 - 6. Virginia Tile.
 - 7. Substitutions: See Section 016000 Product Requirements.
- B. Glazed Wall Tile: **WT-1** ANSI A137.1 standard grade.
 - 1. Moisture Absorption: 7.0 to 20.0 percent as tested in accordance with ASTM C373.
 - 2. Size: 12 X 24 inch (76 by 152 mm), nominal.
 - 3. Edges: Cushioned.
 - 4. Color(s): To be selected by Architect from manufacturer's standard range.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 5. Trim Units: Matching bead, bullnose, cove, and base shapes in sizes coordinated with field tile.
- 6. Products:
 - a. Substitutions: See Section 016000 Product Requirements.
- C. Porcelain Tile: Types ANSI A137.1 standard grade.
 - 1. Moisture Absorption: 0 to 0.5 percent as tested in accordance with ASTM C373.
 - 2. Size: 12" by 24", nominal.
 - 3. Thickness: 3/8 inch (9.5 mm).
 - 4. Edges: Cushioned.
 - 5. Color(s): To be selected by Architect from manufacturer's standard range.
 - 6. Trim Units: Matching cove base and cove base corner shapes in sizes coordinated with field tile.
 - 7. Products:
 - a. Architessa: www.architessa.com/#sle.
 - b. Dal-Tile Corporation; Revo-Tile: www.daltile.com/#sle. BASIS OF DESIGN
 - c. Florim USA: www.milestonetiles.com/#sle.
 - d. Substitutions: See Section 016000 Product Requirements.

2.02 TRIM AND ACCESSORIES

- A. Ceramic Accessories: Glazed finish, same color and finish as adjacent field tile; same manufacturer as tile.
- B. Ceramic Trim: Matching bullnose, double bullnose, cove base, and cove ceramic shapes in sizes coordinated with field tile.
 - 1. Applications:
 - a. Open Edges: Bullnose.
 - b. Inside Corners: Jointed.
 - c. Floor to Wall Joints: Cove base.
 - 2. Manufacturers: Same as for tile.
- C. Non-Ceramic Trim: Satin natural anodized extruded aluminum, style and dimensions to suit application, set with tile mortar or adhesive.
 - 1. Applications:
 - a. Open edges of wall tile.
 - b. Inside and outside wall corners.
 - c. Transition between floor finishes of different heights.
 - d. Thresholds at door openings.
 - e. Floor and wall expansion and control joints.
 - f. Floor-to-wall joints.
 - g. Borders and other trim as indicated on drawings.
 - 2. Manufacturers:
 - a. Blanke Corporation; Blanke Trims and Profiles: www.blankecorp.com/#sle.
 - b. Genesis APS International: www.genesis-aps.com/#sle.
 - c. LATICRETE International, Inc: www.laticrete.com/#sle.
 - d. Schluter-Systems: www.schluter.com/#sle.
 - e. Substitutions: See Section 016000 Product Requirements.

2.03 SETTING MATERIALS

- A. Provide setting and grout materials from same manufacturer.
- B. Manufacturers:
 - 1. ARDEX Engineered Cements: www.ardexamericas.com/#sle.
 - 2. Bostik Inc: www.bostik-us.com/#sle.
 - 3. Custom Building Products: www.custombuildingproducts.com/#sle.

FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 4. H.B. Fuller Construction Products, Inc: www.tecspecialty.com/#sle.
- 5. LATICRETE International, Inc: www.laticrete.com/#sle.
- 6. Substitutions: See Section 016000 Product Requirements.
- C. Latex-Portland Cement Mortar Bond Coat: ANSI A118.4.
 - 1. Applications: Use this type of bond coat where Large and Heavy Tile (LHT) mortar is indicated.
 - 2. Products:
 - a. ARDEX Engineered Cements; ARDEX X 5: www.ardexamericas.com/#sle.
 - b. Custom Building Products; ProLite Premium Rapid Setting Large Format Tile Mortar, with Multi-Surface Bonding Primer: www.custombuildingproducts.com/#sle.
 - c. H.B. Fuller Construction Products, Inc; TEC TotalFlex 110 Universal Mortar: www.tecspecialty.com/#sle.
 - d. LATICRETE International, Inc; TRI-LITE: www.laticrete.com/#sle.
 - e. Merkrete, by Parex USA, Inc; Merkrete 735 Premium Flex: www.merkrete.com/#sle.
 - f. Sika Corp; SikaTile 300 Set: www.sika.com/#sle.
- D. Improved Latex-Portland Cement Mortar Bond Coat: ANSI A118.15.
 - 1. Applications: Use this type of bond coat where indicated, and where no other type of bond coat is indicated.
 - 2. Products:
 - a. ARDEX Engineered Cements; S 28: www.ardexamericas.com/#sle.
 - b. Custom Building Products; Complete Contact-LFT Premium Rapid Setting Large Format Tile Mortar, with Multi-Surface Bonding Primer: www.custombuildingproducts.com/#sle.
 - c. H.B. Fuller Construction Products, Inc; TEC TotalFlex 150 Universal Mortar: www.tecspecialty.com/#sle.
 - d. LATICRETE International, Inc; MULTIMAX LITE: www.laticrete.com/#sle.
- E. Epoxy Adhesive and Mortar Bond Coat: ANSI A118.3.
- F. Organic Adhesive: ANSI A136.1, thinset mastic type.

2.04 GROUTS

- A. Provide setting and grout materials from same manufacturer.
- B. Manufacturers:
 - 1. ARDEX Engineered Cements: www.ardexamericas.com/#sle.
 - 2. Bostik Inc: www.bostik-us.com/#sle.
 - 3. Custom Building Products: www.custombuildingproducts.com/#sle.
 - 4. H.B. Fuller Construction Products, Inc: www.tecspecialty.com/#sle.
 - 5. LATICRETE International, Inc: www.laticrete.com/#sle.
 - 6. Substitutions: See Section 016000 Product Requirements.
- C. Standard Grout: ANSI A118.6 standard cement grout.
 - 1. Applications: Use this type of grout where indicated and where no other type of grout is indicated.
 - 2. Use sanded grout for joints 1/8 inch (3.2 mm) wide and larger; use unsanded grout for joints less than 1/8 inch (3.2 mm) wide.
 - 3. Products:
 - a. Custom Building Products; Polyblend Sanded Grout: www.custombuildingproducts.com/#sle.
 - b. H.B. Fuller Construction Products, Inc; TEC AccuColor Premium Sanded Grout: www.tecspecialty.com/#sle.
 - c. LATICRETE International, Inc; LATICRETE 1500 Sanded Grout: www.laticrete.com/#sle.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- d. Sika Corp; SikaTile 800 Grout Sanded: www.sika.com/#sle.
- e. Mapei; Keracolor S: www.mapei.com/#sle
- f. Substitutions: See Section 016000 Product Requirements.

2.05 MAINTENANCE MATERIALS

- A. Tile Sealant: Gunnable, silicone, siliconized acrylic, or urethane sealant; moisture and mildew resistant type.
 - 1. Applications: Between tile and plumbing fixtures.
 - 2. Color(s): As selected by Architect from manufacturer's full line.
 - 3. Products:
 - a. ARDEX Engineered Cements; ARDEX SX: www.ardexamericas.com/#sle.
 - b. Custom Building Products; Commercial 100% Silicone Caulk: www.custombuildingproducts.com/#sle.
 - c. LATICRETE International, Inc; LATICRETE LATASIL: www.laticrete.com/#sle.
 - d. Rust-Oleum Corporation; Merkrete Colored Caulking: www.rustoleum.com/#sle.
 - e. Substitutions: See Section 016000 Product Requirements.
- B. Grout Sealer: Liquid-applied, moisture and stain protection for existing or new Portland cement grout.
 - 1. Composition: Water-based colorless silicone.
 - 2. Products:
 - a. STONETECH, a Division of LATICRETE International, Inc; STONETECH Heavy Duty Grout Sealer: www.laticrete.com/#sle.
 - b. Merkrete, by Parex USA, Inc; Merkrete Revive: www.merkrete.com/#sle.
 - c. Substitutions: See Section 016000 Product Requirements.
- C. Grout Release: Temporary, water-soluble pre-grout coating.
 - 1. Products:
 - a. Custom Building Products; Aqua Mix Grout Release: www.custombuildingproducts.com/#sle.

2.06 ACCESSORY MATERIALS

- A. Concrete Floor Slab Crack Isolation Membrane: Material complying with ANSI A118.12; not intended as waterproofing.
 - 1. Crack Resistance: No failure at 1/8 inch (3.2 mm) gap, minimum.
 - 2. Fluid or Trowel Applied Type:
 - a. Material: Synthetic rubber or Acrylic.
 - b. Thickness: 40 mils (1 mm), maximum.
 - c. Products:
 - 1) H.B. Fuller Construction Products, Inc; TEC HydraFlex Waterproofing Crack Isolation Membrane: www.tecspecialty.com/#sle.
 - 2) LATICRETE International, Inc; LATICRETE FRACTURE BAN SC: www.laticrete.com/#sle.
 - 3) Merkrete, by Parex USA, Inc; Merkrete Fracture Guard: www.merkrete.com/#sle.
 - 4) Sika Corp; SikaTile 200 Fracture Guard Rapid: www.sika.com/#sle.
 - 5) Substitutions: See Section 016000 Product Requirements.
- B. Waterproofing Membrane at Floors: Specifically designed for bonding to cementitious substrate under thick mortar bed or thin-set tile; complying with ANSI A118.10.
 - 1. Crack Resistance: No failure at 1/16 inch (1.6 mm) gap, minimum; comply with ANSI A118.12.
 - 2. Fluid or Trowel Applied Type:
 - a. Material: Synthetic rubber or Acrylic.
 - b. Thickness: 25 mils (0.6 mm), minimum, dry film thickness.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- c. Products:
 - 1) ARDEX Engineered Cements; ARDEX 8+9: www.ardexamericas.com/#sle.
 - 2) Custom Building Products; RedGard Crack Prevention and Waterproofing Membrane: www.custombuildingproducts.com/#sle.
 - 3) H.B. Fuller Construction Products, Inc; TEC HydraFlex Waterproofing Crack Isolation Membrane: www.tecspecialty.com/#sle.
 - 4) LATICRETE International, Inc; LATICRETE HYDRO BAN: www.laticrete.com/#sle.
 - 5) Merkrete, by Parex USA, Inc; Merkrete Hydro Guard 1: www.merkrete.com/#sle.
 - 6) Polycoat Products; Aquatight: www.polycoatusa.com/#sle.
 - 7) Protecto Wrap; Protecto LM: www.protectowrap.com/#sle.
 - 8) Sika Corp; SikaTile 100 Moisture Guard: www.sika.com/#sle.
 - 9) USG Corporation; Durock Brand Waterproofing Membrane: www.usg.com/#sle.
- C. Reinforcing Underlayment: Specifically designed for bonding to thin-set setting mortar; not primarily waterproofing material and having the following characteristics:
 - 1. Thickness: 1/25 inch (0.9 mm).
 - 2. Uncoupling Function: Allow for separation between membrane and mortar adhering tile to membrane when subjected to excessive substrate movement.
 - 3. Suitable for installation over green concrete.
- D. Drainage Membrane: Studded drainage layer with fleece fabric backing.
 - 1. Composition: Membrane formulated from recycled high impact polystyrene (HIPS) studs laminated to double-woven, glass fiber mesh; backed with non-vapor-retarding protective decoupling fleece.
 - 2. Thickness: 1/3 inch (8.4 mm).
- E. Backer Board: Coated glass mat type complying with ASTM C1178/C1178M; inorganic fiberglass mat on both surfaces and integral acrylic coating vapor retarder.
- F. Mesh Tape: 2 inch (50 mm) wide self-adhesive fiberglass mesh tape.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that subfloor surfaces are smooth and flat within the tolerances specified for that type of work and are ready to receive tile.
- B. Verify that wall surfaces are smooth and flat within the tolerances specified for that type of work, are dust-free, and are ready to receive tile.
- C. Verify that subfloor surfaces are dust free and free of substances that could impair bonding of setting materials to subfloor surfaces.
- D. Cementitious Subfloor Surfaces: Verify that substrates are ready for tiling installation by testing for moisture and alkalinity (pH).
 - 1. Test as Follows:
 - a. Alkalinity (pH): ASTM F710.
 - b. Internal Relative Humidity: ASTM F2170.
 - c. Moisture Vapor Emission: ASTM F1869.
 - 2. Obtain instructions if test results are not within limits recommended by tiling material manufacturer and setting material manufacturer.

3.02 PREPARATION

- A. Protect surrounding work from damage.
- B. Vacuum clean surfaces and damp clean.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- C. Seal substrate surface cracks with filler. Level existing substrate surfaces to acceptable flatness tolerances.
- D. Install backer board in accordance with ANSI A108.11 and board manufacturer's instructions. Tape joints and corners, cover with skim coat of setting material to a feather edge.

3.03 INSTALLATION - GENERAL

- A. Install tile and thresholds and grout in accordance with applicable requirements of ANSI A108.1a through ANSI A108.20, manufacturer's instructions, and TCNA (HB) recommendations.
- B. Lay tile to pattern indicated. Do not interrupt tile pattern through openings.
- C. Cut and fit tile to penetrations through tile, leaving sealant joint space. Form corners and bases neatly. Align floor joints.
- D. Place tile joints uniform in width, subject to variance in tolerance allowed in tile size. Make grout joints without voids, cracks, excess mortar or excess grout, or too little grout.
- E. Form internal angles square and external angles .
- F. Install ceramic accessories rigidly in prepared openings.
- G. Install non-ceramic trim in accordance with manufacturer's instructions.
- H. Sound tile after setting. Replace hollow sounding units.
- I. Keep control and expansion joints free of mortar, grout, and adhesive.
- J. Prior to grouting, allow installation to completely cure; minimum of 48 hours.
- K. Grout tile joints unless otherwise indicated. Use standard grout unless otherwise indicated.
- L. At changes in plane and tile-to-tile control joints, use tile sealant instead of grout, with either bond breaker tape or backer rod as appropriate to prevent three-sided bonding.

3.04 INSTALLATION - FLOORS - THIN-SET METHODS

A. Over interior concrete substrates, install in accordance with TCNA (HB) Method F113, dry-set or latex-Portland cement bond coat, with standard grout, unless otherwise indicated.

3.05 INSTALLATION - WALL TILE

A. Over coated glass mat backer board on studs, install in accordance with TCNA (HB) Method W245.

3.06 CLEANING

A. Clean tile and grout surfaces.

3.07 PROTECTION

A. Do not permit traffic over finished floor surface for 4 days after installation.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 095100 ACOUSTICAL CEILINGS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Suspended metal grid ceiling system.
- B. Acoustical units.

1.02 REFERENCE STANDARDS

- A. ASTM A653/A653M Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process; 2023.
- B. ASTM B209/B209M Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate; 2021a.
- C. ASTM C635/C635M Standard Specification for Manufacture, Performance, and Testing of Metal Suspension Systems for Acoustical Tile and Lay-in Panel Ceilings; 2022.
- D. ASTM C636/C636M Standard Practice for Installation of Metal Ceiling Suspension Systems for Acoustical Tile and Lay-In Panels; 2019.
- E. ASTM E1264 Standard Classification for Acoustical Ceiling Products; 2023.

1.03 ADMINISTRATIVE REQUIREMENTS

- A. Sequence work to ensure acoustical ceilings are not installed until building is enclosed, sufficient heat is provided, dust generating activities have terminated, and overhead work is completed, tested, and approved.
- B. Do not install acoustical units until after interior wet work is dry.

1.04 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Shop Drawings: Indicate grid layout and related dimensioning.
- C. Product Data: Provide data on suspension system components and acoustical units.
- D. Samples: Submit two full size samples illustrating material and finish of acoustical units.
- E. Samples: Submit two samples each, 8" inches (200 mm) long, of suspension system main runner, cross runner, and perimeter molding.
- F. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
 - 1. See Section 016000 Product Requirements, of Core and Shell Package for additional provisions.
 - 2. Extra Acoustical Units: Quantity equal to 5 percent of total installed.

1.05 QUALITY ASSURANCE

A. Suspension System Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum three years documented experience.

1.06 FIELD CONDITIONS

A. Maintain uniform temperature of minimum 60 degrees F (16 degrees C), and maximum humidity of 40 percent prior to, during, and after acoustical unit installation.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Acoustic Tiles/Panels:
 - 1. Armstrong World Industries, Inc: www.armstrongceilings.com/#sle.
 - 2. Acoustic Ceiling Products, Inc: www.acpideas.com/#sle.
 - 3. Acoustics First Corporationh: www.acousticsfirst.com/#sle.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

- 4. Ceilings4U: www.ceilings4u.com/#sle.
- 5. Certainteed Architectural: www.certainteed.com/ceilings-and-walls/#sle.
- 6. Rockfon: www.rockfon.com/#sle.
- 7. TECHLITE: www.techlite.com/#sle.
- 8. USG Corporation: www.usg.com/ceilings/#sle.
- 9. Substitutions: See Section 016000 Product Requirements.

2.02 ACOUSTICAL UNITS

- A. Acoustical Units General: ASTM E1264, Class A.
- B. Acoustical Panels: Painted mineral fiber, with the following characteristics:
 - 1. Classification: ASTM E1264 Type III.
 - a. Form: 2, water felted.
 - b. Pattern: "E" lightly textured.
 - 2. Size: 24 by 48 inches (610 by 1219 mm).
 - 3. Thickness: 7/8 inch (22 mm).
 - 4. Light Reflectance: 0.85 percent, determined in accordance with ASTM E1264.
 - 5. NRC Range: 0.85, determined in accordance with ASTM E1264.
 - 6. Articulation Class (AC): 170, determined in accordance with ASTM E1264.
 - 7. Panel Edge: Reveal. Basis of Design is Armstrong Ultima High NRC 9/16" Beveled Tegular.
 - 8. Suspension System: Exposed grid. Basis of Design Armstrong Suprafine.

2.03 SUSPENSION SYSTEM(S)

- A. Metal Suspension Systems General: Complying with ASTM C635/C635M; die cut and interlocking components, with perimeter moldings and splices as required.
 - 1. Materials:
 - a. Steel Grid: ASTM A653/A653M, G30 coating, unless otherwise indicated.
 - b. Aluminum Grid: Aluminum sheet, ASTM B209/B209M.
- B. Exposed Suspension System: Hot-dipped galvanized steel grid with steel cap.
 - 1. Structural Classification: Intermediate-duty, when tested in accordance with ASTM C635/C635M.
 - 2. Profile: Tee; 15/16 inch (24 mm) face width. Basis of Design is Armstrong Suprafine.
 - 3. Color: White.

2.04 ACCESSORIES

- A. Support Channels and Hangers: Galvanized steel; size and type to suit application, seismic requirements, and ceiling system flatness requirement specified.
- B. Hanger Wire: Galvanized steel wire. ASTM A641/A 641M Select wire diameter so its stress at 3 times hanger design load (ASTM C 635, Table 1, "Direct Hung") will be less than yield stress of wire, but provide not less than 0.106" (2.69 mm) dia. wire.
- C. Perimeter Moldings: Same metal and finish as grid.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify existing conditions before starting work.
- B. Verify that layout of hangers will not interfere with other work.

3.02 PREPARATION

- A. Install after major above-ceiling work is complete.
- B. Coordinate the location of hangers with other work.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

3.03 INSTALLATION - SUSPENSION SYSTEM

- A. Install suspension system in accordance with ASTM C636/C636M and manufacturer's instructions and as supplemented in this section.
- B. Rigidly secure system, including integral mechanical and electrical components, for maximum deflection of 1:240.
- C. Lay out system to a balanced grid design with edge units no less than 50 percent of acoustical unit size.
- D. Perimeter Molding: Install at intersection of ceiling and vertical surfaces and at junctions with other interruptions.
 - 1. Use longest practical lengths.
- E. Suspension System, Non-Seismic: Hang suspension system independent of walls, columns, ducts, pipes and conduit. Where carrying members are spliced, avoid visible displacement of face plane of adjacent members.
- F. Where ducts or other equipment prevent the regular spacing of hangers, reinforce the nearest affected hangers and related carrying channels to span the extra distance.
- G. Do not support components on main runners or cross runners if weight causes total dead load to exceed deflection capability.
- H. Support fixture loads using supplementary hangers located within 6 inches (152 mm) of each corner, or support components independently.
- I. Do not eccentrically load system or induce rotation of runners.

3.04 INSTALLATION - ACOUSTICAL UNITS

- A. Install acoustical units in accordance with manufacturer's instructions.
- B. Fit acoustical units in place, free from damaged edges or other defects detrimental to appearance and function.
- C. Fit border trim neatly against abutting surfaces.
- D. Install acoustical units level, in uniform plane, and free from twist, warp, and dents.
- E. Cutting Acoustical Units:
 - 1. Make field cut edges of same profile as factory edges.
- F. Where round obstructions occur, provide preformed closures to match perimeter molding.

3.05 TOLERANCES

- A. Maximum Variation from Flat and Level Surface: 1/8 inch in 10 feet (3 mm in 3 m).
- B. Maximum Variation from Plumb of Grid Members Caused by Eccentric Loads: 2 degrees.

3.06 CLEANING

- A. See Section 017000 Execution and Closeout Requirements for additional requirements.
- B. Clean surfaces.
- C. Replace damaged or abraded components.

FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 096500 RESILIENT FLOORING

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Resilient sheet flooring.
- B. Resilient base.
- C. Installation accessories.

1.02 REFERENCE STANDARDS

- A. ASTM F710 Standard Practice for Preparing Concrete Floors to Receive Resilient Flooring; 2022.
- B. ASTM F970 Standard Test Method for Measuring Recovery Properties of Floor Coverings after Static Loading; 2022.
- C. ASTM F1303 Standard Specification for Sheet Vinyl Floor Covering with Backing; 2004 (Reapproved 2021).
- D. ASTM F1861 Standard Specification for Resilient Wall Base; 2021.
- E. ASTM F1869 Standard Test Method for Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride; 2023.
- F. ASTM F2170 Standard Test Method for Determining Relative Humidity in Concrete Floor Slabs Using in situ Probes; 2019a.
- G. RFCI (RWP) Recommended Work Practices for Removal of Resilient Floor Coverings; 2018.

1.03 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Product Data: Provide data on specified products, describing physical and performance characteristics; including sizes, patterns and colors available; and installation instructions.
- C. Shop Drawings: Indicate seaming plans and floor patterns.
- D. Selection Samples: Submit manufacturer's complete set of color samples for Architect's initial selection.
- E. Verification Samples: Submit two samples, 12 by 12 inch (300 by 300 mm) in size illustrating color and pattern for each resilient flooring product specified.
- F. Concrete Subfloor Test Report: Submit a copy of the moisture and alkalinity (pH) test reports.
- G. Certification: Prior to installation of flooring, submit written certification by flooring manufacturer and adhesive manufacturer that condition of subfloor is acceptable.
- H. Manufacturer's Qualification Statement.
- I. Installer's Qualification Statement.
- J. Maintenance Data: Include maintenance procedures, recommended maintenance materials, and suggested schedule for cleaning, stripping, and re-waxing.
- K. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
 - 1. See Section 016000 Product Requirements, for additional provisions.
 - 2. Extra Wall Base: 24 linear feet (8 linear meters) of each type and color.

1.04 QUALITY ASSURANCE

A. Manufacturer Qualifications: Company specializing in manufacturing specified flooring with minimum three years documented experience.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

B. Installer Qualifications: Company specializing in installing specified flooring with minimum three years documented experience.

1.05 DELIVERY, STORAGE, AND HANDLING

- A. Upon receipt, immediately remove any shrink-wrap and check materials for damage and the correct style, color, quantity and run numbers.
- B. Store all materials off of the floor in an acclimatized, weather-tight space.
- C. Maintain temperature in storage area between 55 degrees F (13 degrees C) and 90 degrees F (72 degrees C).
- D. Protect roll materials from damage by storing on end.
- E. Do not double stack pallets.

1.06 FIELD CONDITIONS

A. Store materials for not less than 48 hours prior to installation in area of installation at a temperature of 70 degrees F (21 degrees C) to achieve temperature stability. Thereafter. maintain conditions above 55 degrees F (13 degrees C).

PART 2 PRODUCTS

2.01 SHEET FLOORING

- A. Luxury Vinyl Tile: LVT-1 Heavy Commercial Luxury Vinyl Tile with Fiberglass
 - Manufacturers: 1.
 - a. Armstrong Flooring, LLC: www.armstrongflooring.com/#sle.
 - b. Mannington Commercial: www.manningtoncommercial.com#sle.
 - ShawContract (Basis of Design). C.
 - Substitutions: See Section 016000 Product Requirements. d.
 - Minimum Requirements: Comply with ASTM F1700 2
 - Wear Layer Thickness: 0.020 inch (0.50 mm) minimum. 3.
 - Total Thickness: 0.197 inch (5 mm) minimum. 4.
 - Static Load Resistance: 750 lbs psi (5,000 kPa) minimum, when tested as specified in 5. ASTM F970.
 - 6. Color: As indicated on drawings.

2.02 RESILIENT BASE

- Resilient Wall Base Type RWB-1: ASTM F1861, Type TV, vinyl, thermoplastic; Style B, Cove. A. 1.
 - Manufacturers:
 - a. Flexco Corporation: www.flexcofloors.com/#sle.
 - Johnsonite, a Tarkett Company: www.johnsonite.com/#sle. b.
 - Mannington Commercial: www.manningtoncommercial.com#sle. C.
 - d. Roppe Corporation: www.roppe.com/#sle. (Basis of Design)
 - Substitutions: See Section 016000 Product Requirements. e.
 - Height: 4 inches (100 mm). 2.
 - Thickness: 0.125 inch (3.2 mm). 3.
 - 4. Finish: Satin.
 - 5. Lenath: Roll.
 - 6. Color: As indicated on drawings.

2.03 ACCESSORIES

- A. Subfloor Filler: White premix latex; type recommended by adhesive material manufacturer.
- Primers, Adhesives, and Seam Sealer: Waterproof; types recommended by flooring В. manufacturer.
- Sealer and Wax: Types recommended by flooring manufacturer. C.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that surfaces are flat to tolerances acceptable to flooring manufacturer, free of cracks that might telegraph through flooring, clean, dry, and free of curing compounds, surface hardeners, and other chemicals that might interfere with bonding of flooring to substrate.
- B. Verify that wall surfaces are smooth and flat within the tolerances specified for that type of work, are dust-free, and are ready to receive resilient base.
- C. Cementitious Subfloor Surfaces: Verify that substrates are ready for resilient flooring installation by testing for moisture and alkalinity (pH).
 - 1. Test as Follows:
 - a. Alkalinity (pH): ASTM F710.
 - b. Internal Relative Humidity: ASTM F2170.
 - c. Moisture Vapor Emission: ASTM F1869.
 - 2. Obtain instructions if test results are not within limits recommended by resilient flooring manufacturer and adhesive materials manufacturer.

3.02 PREPARATION

- Remove existing resilient flooring and flooring adhesives; follow the recommendations of RFCI (RWP).
- B. Prepare floor substrates as recommended by flooring and adhesive manufacturers.
- C. Remove subfloor ridges and bumps. Fill minor low spots, cracks, joints, holes, and other defects with subfloor filler to achieve smooth, flat, hard surface.
- D. Prohibit traffic until filler is fully cured.
- E. Clean substrate.

3.03 INSTALLATION - GENERAL

- A. Starting installation constitutes acceptance of subfloor conditions.
- B. Install in accordance with manufacturer's written instructions.
- C. Adhesive-Applied Installation:
 - 1. Spread only enough adhesive to permit installation of materials before initial set.
 - 2. Fit joints and butt seams tightly.
 - 3. Set flooring in place, press with heavy roller to attain full adhesion.

3.04 INSTALLATION - SHEET FLOORING

A. Lay flooring with joints and seams parallel to longer room dimensions, to produce minimum number of seams. Lay out seams to avoid widths less than 1/3 of roll width; match patterns at seams.

3.05 INSTALLATION - RESILIENT BASE

- A. Fit joints tightly and make vertical. Maintain minimum dimension of 24" between joints.
- B. Install base on solid backing. Bond tightly to wall and floor surfaces.

3.06 CLEANING

- A. Remove excess adhesive from floor, base, and wall surfaces without damage.
- B. Clean, seal, and wax in accordance with manufacturer's written instructions.

3.07 PROTECTION

A. Prohibit traffic on resilient flooring for 48 hours after installation.

FOR REVIEW. NOT FOR CONSTRUCTION

LAHC – WORKFORCE EDUCATION RESOURCE AND DEVELOPMENT CENTER 50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

This page intentionally left blank

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 096813 TILE CARPETING

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Carpet tile, fully adhered.

1.02 RELATED REQUIREMENTS

- A. Section 016116 Volatile Organic Compound (VOC) Content Restrictions.
- B. Section 017419 Construction Waste Management and Disposal: Reclamation/Recycling of new carpet tile scrap and removed carpet tile.
- C. Section 033000 Cast-in-Place Concrete: Restrictions on curing compounds for concrete slabs and floors to receive adhesive-applied flooring. Ref. Str. Dwgs.

1.03 SUBMITTALS

- A. See Section 013000 Administrative Requirements, for submittal procedures.
- B. Product Data: Provide data on specified products, describing physical and performance characteristics; sizes, patterns, colors available, and method of installation.
- C. Shop Drawings: Indicate layout of joints.
- D. Samples: Submit two carpet tiles illustrating color and pattern design for each carpet color selected.
- E. Accessory Samples: Submit two 6 inch (150 mm) long samples of edge strip.
- F. Manufacturer's Installation Instructions: Indicate special procedures and perimeter conditions requiring special attention.
- G. Concrete Subfloor Test Report: Submit a copy of the moisture and alkalinity (pH) test reports.
- H. Manufacturer's Qualification Statement.
- I. Installer's Qualification Statement.
- J. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
 - 1. See Section 016000 Product Requirements, for additional provisions.
 - 2. Extra Carpet Tiles: Quantity equal to 5 percent of total installed of each color and pattern installed.

1.04 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing specified carpet tile with minimum three years documented experience.
- B. Installer Qualifications: Company specializing in installing carpet tile with minimum three years documented experience.

1.05 FIELD CONDITIONS

A. Store materials in area of installation for minimum period of 24 hours prior to installation.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Tile Carpeting:
 - 1. Interface, Inc: www.interface.com/#sle.
 - 2. Mannington Commercial: www.manningtoncommercial.com#sle.
 - 3. Milliken & Company: www.milliken.com/#sle.
 - 4. Mohawk Group: www.mohawkgroup.com/#sle.
 - 5. FLOR An Interface Company.
 - 6. Substitutions: See Section 016000 Product Requirements.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

2.02 MATERIALS

- A. Tile Carpeting, Type CPT-1: Tufted Textured Loop, Tip Shear, manufactured in one color dye lot.
 - 1. Product: REF. FINISH LEGEND manufactured by Milliken Digitize CTB180-218-27.
 - 2. Tile Size: 9.85" x 39.4"
 - 3. Color: REF. FINISH LEGEND.
 - 4. Pattern: REF. FINISH LEGEND.

2.03 ACCESSORIES

- A. Edge Strips: Ref. drawings, color as selected by Architect
- B. Carpet Tile Adhesive: Recommended by carpet tile manufacturer.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that subfloor surfaces are smooth and flat within tolerances specified for that type of work and are ready to receive carpet tile.
- B. Verify that subfloor surfaces are dust-free and free of substances that could impair bonding of adhesive materials to subfloor surfaces.
- C. Cementitious Subfloor Surfaces: Verify that substrates are ready for flooring installation by testing for moisture and alkalinity (pH).
 - 1. Obtain instructions if test results are not within limits recommended by flooring material manufacturer and adhesive materials manufacturer.

3.02 PREPARATION

- A. Prepare floor substrates as recommended by flooring and adhesive manufacturers.
- B. Remove subfloor ridges and bumps. Fill minor or local low spots, cracks, joints, holes, and other defects with subfloor filler.
- C. Apply, trowel, and float filler to achieve smooth, flat, hard surface. Prohibit traffic until filler is cured.
- D. Vacuum clean substrate.

3.03 INSTALLATION

- A. Starting installation constitutes acceptance of subfloor conditions.
- B. Install carpet tile in accordance with manufacturer's instructions.
- C. Blend carpet from different cartons to ensure minimal variation in color match.
- D. Cut carpet tile clean. Fit carpet tight to intersection with vertical surfaces without gaps.
- E. Lay carpet tile in square pattern, with pile direction parallel to next unit, set parallel to building lines.
- F. Locate change of color or pattern between rooms under door centerline.
- G. Fully adhere carpet tile to substrate.
- H. Trim carpet tile neatly at walls and around interruptions.
- I. Complete installation of edge strips, concealing exposed edges.

3.04 CLEANING

- A. See Section 017000 Execution and Closeout Requirements for additional requirements.
- B. Remove excess adhesive without damage, from floor, base, and wall surfaces.
- C. Clean and vacuum carpet surfaces.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 099123 INTERIOR PAINTING

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Surface preparation.
- B. Field application of paints.
- C. Scope: Finish interior surfaces exposed to view, unless fully factory-finished and unless otherwise indicated.
 - 1. Both sides and edges of plywood backboards for electrical and telecom equipment before installing equipment.
 - 2. Mechanical and Electrical:
 - a. In finished areas, paint insulated and exposed pipes, conduit, boxes, insulated and exposed ducts, and hangers, brackets, collars and supports, unless otherwise indicated.
 - b. In finished areas, paint shop-primed items.
 - c. Paint interior surfaces of air ducts and convector and baseboard heating cabinets that are visible through grilles and louvers with one coat of flat black paint to visible surfaces.
 - d. Paint dampers exposed behind louvers, grilles, and convector and baseboard cabinets to match face panels.
- D. Do Not Paint or Finish the Following Items:
 - 1. Items factory-finished unless otherwise indicated; materials and products having factoryapplied primers are not considered factory finished.
 - 2. Items indicated to receive other finishes.
 - 3. Items indicated to remain unfinished.
 - 4. Fire rating labels, equipment serial number and capacity labels, bar code labels, and operating parts of equipment.
 - 5. Stainless steel, anodized aluminum, bronze, terne-coated stainless steel, and lead items.
 - 6. Marble, granite, slate, and other natural stones.
 - 7. Floors, unless specifically indicated.
 - 8. Ceramic and other tiles.
 - 9. Glass.
 - 10. Concrete masonry units in utility, mechanical, and electrical spaces.
 - 11. Concealed pipes, ducts, and conduits.

1.02 RELATED REQUIREMENTS

- A. Section 016116 Volatile Organic Compound (VOC) Content Restrictions.
- B. Section 055000 Metal Fabrications: Shop-primed items.

1.03 DEFINITIONS

A. Comply with ASTM D16 for interpretation of terms used in this section.

1.04 REFERENCE STANDARDS

- A. ASTM D16 Standard Terminology for Paint, Related Coatings, Materials, and Applications; 2024.
- B. MPI (APSM) Master Painters Institute Architectural Painting Specification Manual; Current Edition.
- C. SSPC-SP 1 Solvent Cleaning; 2015, with Editorial Revision (2016).
- D. SSPC-SP 6 Commercial Blast Cleaning; 2007.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

1.05 SUBMITTALS

- A. See Section 013000 Administrative Requirements, for submittal procedures.
- B. Product Data: Provide complete list of products to be used, with the following information for each:
 - 1. Manufacturer's name, product name and/or catalog number, and general product category (e.g., "alkyd enamel").
 - 2. MPI product number (e.g., MPI #47).
 - 3. Cross-reference to specified paint system products to be used in project; include description of each system.

C. Samples: Submit three paper "draw down" samples, 8-1/2 by 11 inches (216 by 279 mm) in size, illustrating range of colors available for each finishing product specified.

- 1. Where sheen is specified, submit samples in only that sheen.
- 2. Where sheen is not specified, discuss sheen options with Architect before preparing samples, to eliminate sheens not required.
- 3. Allow 30 days for approval process, after receipt of complete samples by Architect.
- 4. Paint color submittals will not be considered until color submittals for major materials not to be painted, such as masonry, have been approved.
- D. Samples: Submit two paper chip samples, illustrating range of colors and textures available for each surface finishing product scheduled.
- E. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
 - 1. See Section 016000 Product Requirements, for additional provisions.
 - 2. Extra Paint and Finish Materials: 1 gal (4 L) of each color; from the same product run, store where directed.
 - 3. Label each container with color in addition to the manufacturer's label.

1.06 QUALITY ASSURANCE

A. Manufacturer Qualifications: Company specializing in manufacturing the products specified, with minimum three years documented experience.

1.07 MOCK-UP

- A. See Section 014000 Quality Requirements, for general requirements for mock-up.
- B. Provide panel, 10 ft. long by 10 ft. wide, illustrating paint color, texture, and finish.
- C. Provide door and frame assembly illustrating paint color, texture, and finish.
- D. Locate where directed by Architect.
- E. Mock-up may remain as part of the work.

1.08 DELIVERY, STORAGE, AND HANDLING

- A. Deliver products to site in sealed and labeled containers; inspect to verify acceptability.
- B. Container Label: Include manufacturer's name, type of paint, brand name, lot number, brand code, coverage, surface preparation, drying time, cleanup requirements, color designation, and instructions for mixing and reducing.
- C. Paint Materials: Store at minimum ambient temperature of 45 degrees F (7 degrees C) and a maximum of 90 degrees F (32 degrees C), in ventilated area, and as required by manufacturer's instructions.

1.09 FIELD CONDITIONS

- A. Do not apply materials when surface and ambient temperatures are outside the temperature ranges required by the paint product manufacturer.
- B. Follow manufacturer's recommended procedures for producing best results, including testing of substrates, moisture in substrates, and humidity and temperature limitations.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- C. Do not apply materials when relative humidity exceeds 85 percent, at temperatures less than 5 degrees F (3 degrees C) above the dew point, or to damp or wet surfaces.
- D. Minimum Application Temperatures for Paints: 50 degrees F (10 degrees C) for interiors unless required otherwise by manufacturer's instructions.
- E. Provide lighting level of 80 fc (860 lux) measured mid-height at substrate surface.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Provide paints and finishes from the same manufacturer to the greatest extent possible.
 - 1. If a single manufacturer cannot provide specified products; minor exceptions will be permitted provided approval by Architect is obtained using the specified procedures for substitutions.
 - 2. Substitution of other products by the same manufacturer is preferred over substitution of products by a different manufacturer.

B. Paints:

- 1. Behr Paint Company: www.behr.com/#sle.
- 2. Kelly-Moore Paints: www.kellymoore.com/#sle.
- 3. Pittsburgh Paints: www.ppgpaints.com/#sle.
- 4. Sherwin-Williams Company: www.sherwin-williams.com/#sle.
- 5. Benjamin Moore & Co: https://www.benjaminmoore.com/en-us.
- 6. Tnemec Company, Inc: https://tnemec.com/
- C. Primer Sealers: Same manufacturer as top coats.
- D. Substitutions: See Section 016000 Product Requirements.

2.02 PAINTS AND FINISHES - GENERAL

- A. Paints and Finishes: Ready-mixed, unless intended to be a field-catalyzed paint.
 - 1. Provide paints and finishes of a soft paste consistency, capable of being readily and uniformly dispersed to a homogeneous coating, with good flow and brushing properties, and capable of drying or curing free of streaks or sags.
 - 2. Supply each paint material in quantity required to complete entire project's work from a single production run.
 - 3. Do not reduce, thin, or dilute paint or finishes or add materials unless such procedure is specifically described in manufacturer's product instructions.
- B. Volatile Organic Compound (VOC) Content: See Section 016116.
- C. Flammability: Comply with applicable code for surface burning characteristics.
- D. Sheens: Provide the sheens specified; where sheen is not specified, sheen will be selected later by Architect from the manufacturer's full line.
- E. Colors: To be selected from manufacturer's full range of available colors.
 - 1. Selection to be made by Architect after award of contract.
 - 2. In finished areas, finish pipes, ducts, conduit, and equipment the same color as the wall/ceiling under which they are mounted.

2.03 PAINT SYSTEMS - INTERIOR

- A. Paint I-OP Interior Surfaces to be Painted, Unless Otherwise Indicated: Including gypsum board, concrete masonry units, uncoated steel, shop primed steel, and galvanized steel.
 - 1. Two top coats and one coat primer.
 - 2. Top Coat(s): Interior Latex; MPI #43, 44, 52, 53, 54, or 114.
 - a. Products:
 - 1) Behr Marquee Interior Semi-Gloss Enamel [No.3450]. (MPI #54)
 - 2) Behr Premium Plus Interior Flat [No.1050]. (MPI #53)

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- 3) Behr Premium Plus Interior Semi-Gloss Enamel [No.3050]. (MPI #54)
- 4) Behr Pro i300 Interior Dead Flat Paint [No.PR310]. (MPI #53)
- 5) Behr Pro i300 Interior Semi-Gloss Paint [No.PR370]. (MPI #54)
- 6) Dunn-Edwards Corporation; Suprema Interior Flat. (MPI #53)
- 7) Dunn-Edwards Corporation; Everest Low Odor Zero VOC Interior Flat Paint. (MPI #53)
- Dunn-Edwards Corporation; Versaglo Interior/Exterior Latex Semi-Gloss Paint. (MPI #54)
- 9) Kelly-Moore Paints; 1050 Premium Professional Interior Paints and Enamels, Semi-Gloss. (MPI #54)
- 10) Kelly-Moore Paints; 550 AcryPlex Interior Paint, Flat. (MPI #53)
- 11) Kelly-Moore Paints; 1602 AcryPlex Interior Paints and Enamels, Flat. (MPI #53)
- 12) Kelly-Moore Paints; 1650 AcryPlex Interior Paints and Enamels, Semi-Gloss. (MPI #54)
- 13) Pittsburgh Paints Speedhide Pro-EV Zero Interior Wall and Ceiling Latex, 12-110XI Series, Flat. (MPI #53)
- 14) Pittsburgh Paints Speedhide Pro-EV Zero Interior Latex Enamel, 12-510XI Series, Semi-Gloss. (MPI #54)
- 15) Pittsburgh Paints Speedhide Zero Interior Latex, 6-5110 Series, Flat. (MPI #53)
- 16) Pittsburgh Paints Speedhide Zero Interior Latex, 6-5410 Series, Satin. (MPI #52)
- 17) Pittsburgh Paints Speedhide Zero Interior Latex, 6-5510 Series, Semi-Gloss. (MPI #54)
- 18) Pittsburgh Paints Speedhide Interior Latex, 6-70 Series, Flat. (MPI #53)
- 19) Pittsburgh Paints Speedhide Interior Latex, 6-3511 Series, Satin. (MPI #52)
- 20) Pittsburgh Paints Speedhide Interior Latex, 6-500 Series, Semi-Gloss. (MPI #54)
- 21) Pittsburgh Paints Advantage 900 Interior/Exterior Styrene Acrylic, 919-10 Series, Semi-Gloss. (MPI #54)
- 22) Pittsburgh Paints Copper Armor Interior Latex, 29-1510 Series, Semi-Gloss. (MPI #54)
- 23) Rodda Master Painter Ultra Low VOC Flat, 513601. (MPI #53)
- 24) Sherwin-Williams Air Purifying Interior Acrylic Latex, Semi-Gloss. (MPI #54)
- 25) Sherwin-Williams Solo Series, Semi-Gloss. (MPI #54)
- 26) Sherwin-Williams Superpaint Interior Latex with Air Purifying Technology, Semi-Gloss. (MPI #54)
- 27) Vista Paint Corporation; 7000 Acriglo Semi-Gloss: www.vistapaint.com/#sle. (MPI #54)
- 28) Vista Paint Corporation; 8400 Carefree Semi-Gloss: www.vistapaint.com/#sle. (MPI #54)
- B. Paint I-OP-DF Dry Fall: Metals; exposed structure and overhead-mounted services in utilitarian spaces, including shop primed steel deck, structural steel, and metal fabrications.
 - 1. Shop primer by others.
 - 2. One top coat.
 - Top Coat: Latex Dry Fall; MPI #118, 155, or 226.
 a. Products:
- C. Paint GI-OP-3A Gypsum Board/Plaster, Alkyd, 3 Coat:1. One coat of alkyd primer sealer.
- D. Paint GI-OP-3L Gypsum Board/Plaster, Latex, 3 Coat:
 - 1. One coat of alkyd primer sealer.
 - 2. Eggshell: Two coats of latex enamel.
 - 3. Flat: Two coats of latex enamel.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

2.04 PRIMERS

- A. Primers: Provide the following unless other primer is required or recommended by manufacturer of top coats.
 - 1. Alkali Resistant Water Based Primer; MPI #3.
 - a. Products:
 - 1) Sherwin Williams PrepRite® ProBlock® Int/Ext Latex Primer/Sealer.
 - 2. Interior/Exterior Latex Block Filler; MPI #4.
 - a. Products:
 - 1) Sherwin-Williams ConFlex Block Filler. (MPI #4)
 - 2) Sherwin-Williams Loxon Block Surfacer. (MPI #4)
 - 3) Substitutions: See Section 016000 Product Requirements
 - 3. Interior Latex Primer Sealer; MPI #50.
 - a. Products:
 - 1) SW ProMar 200 Zero VOC Interior Latex Primer, B28 Series.
 - 4. Interior Rust-Inhibitive Water Based Primer; MPI #107.
 - a. Products:
 - 1) Sherwin-Williams Pro-Cryl Universal Primer. (MPI #107)
 - Interior/Exterior Quick Dry Alkyd Primer for Metal; MPI #76.
 - a. Products:
 - 1) Pittsburgh Paints Multiprime Multi-Purpose Primer, 4160 Series. (MPI #76)
 - 2) Sumter Coatings, Inc. Universal Inhibitive Primer.
 - 3) SW Kem Bond HS Universal Alkyd Primer, B50 Series..
 - 4) Substitutions: See Section 016000 Product Requirements

2.05 ACCESSORY MATERIALS

- A. Accessory Materials: Provide primers, sealers, cleaning agents, cleaning cloths, sanding materials, and clean-up materials as required for final completion of painted surfaces.
- B. Patching Material: Latex filler.
- C. Fastener Head Cover Material: Latex filler.

PART 3 EXECUTION

5.

3.01 EXAMINATION

- A. Do not begin application of paints and finishes until substrates have been adequately prepared.
- B. Verify that surfaces are ready to receive work as instructed by the product manufacturer.
- C. Examine surfaces scheduled to be finished prior to commencement of work. Report any condition that may potentially affect proper application.
- D. Test shop-applied primer for compatibility with subsequent cover materials.
- E. Measure moisture content of surfaces using an electronic moisture meter. Do not apply finishes unless moisture content of surfaces is below the following maximums:
 - 1. Gypsum Wallboard: 12 percent.
 - 2. Masonry, Concrete, and Concrete Masonry Units: 12 percent.

3.02 PREPARATION

- A. Clean surfaces thoroughly and correct defects prior to application.
- B. Prepare surfaces using the methods recommended by the manufacturer for achieving the best result for the substrate under the project conditions.
- C. Remove or mask surface appurtenances, including electrical plates, hardware, light fixture trim, escutcheons, and fittings, prior to preparing surfaces or finishing.
- D. Seal surfaces that might cause bleed through or staining of topcoat.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- E. Masonry:
 - 1. Remove efflorescence and chalk. Do not coat surfaces if moisture content, alkalinity of surfaces, or if alkalinity of mortar joints exceed that permitted in manufacturer's written instructions. Allow to dry.
 - 2. Prepare surface as recommended by top coat manufacturer.
- F. Gypsum Board: Fill minor defects with filler compound. Spot prime defects after repair.
- G. Galvanized Surfaces:
- H. Ferrous Metal:
 - 1. Solvent clean according to SSPC-SP 1.
 - 2. Shop-Primed Surfaces: Sand and scrape to remove loose primer and rust. Feather edges to make touch-up patches inconspicuous. Clean surfaces with solvent. Prime bare steel surfaces. Re-prime entire shop-primed item.
 - 3. Remove rust, loose mill scale, and other foreign substances using methods recommended in writing by paint manufacturer and blast cleaning according to SSPC-SP 6 Commercial Blast Cleaning. Protect from corrosion until coated.

3.03 APPLICATION

- A. Remove unfinished louvers, grilles, covers, and access panels on mechanical and electrical components and paint separately.
- B. Apply products in accordance with manufacturer's written instructions and recommendations in "MPI Architectural Painting Specification Manual".
- C. Do not apply finishes to surfaces that are not dry. Allow applied coats to dry before next coat is applied.
- D. Apply each coat to uniform appearance in thicknesses specified by manufacturer.
- E. Vacuum clean surfaces of loose particles. Use tack cloth to remove dust and particles just prior to applying next coat.
- F. Reinstall electrical cover plates, hardware, light fixture trim, escutcheons, and fittings removed prior to finishing.

3.04 CLEANING

A. Collect waste material that could constitute a fire hazard, place in closed metal containers, and remove daily from site.

3.05 PROTECTION

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 102800 TOILET, BATH, AND LAUNDRY ACCESSORIES

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Commercial toilet accessories.
- B. Commercial shower and bath accessories.
- C. Under-lavatory pipe supply covers.
- D. Diaper changing stations.
- E. Utility room accessories.

1.02 RELATED REQUIREMENTS

- A. Section 092116 Non-Structural Framing: Placement of reinforcement for backing plate reinforcement.
- B. Section 093000 Tiling: Ceramic washroom accessories.
- C. Section 224000 Plumbing Fixtures: Under-lavatory pipe and supply covers.

1.03 REFERENCE STANDARDS

- A. ASTM A269/A269M Standard Specification for Seamless and Welded Austenitic Stainless Steel Tubing for General Service; 2022.
- B. ASTM A666 Standard Specification for Annealed or Cold-Worked Austenitic Stainless Steel Sheet, Strip, Plate, and Flat Bar; 2023.
- C. ASTM B456 Standard Specification for Electrodeposited Coatings of Copper Plus Nickel Plus Chromium and Nickel Plus Chromium; 2017 (Reapproved 2022).
- D. ASTM C1036 Standard Specification for Flat Glass; 2021.
- E. ASTM C1048 Standard Specification for Heat-Strengthened and Fully Tempered Flat Glass; 2018.
- F. ASTM C1503 Standard Specification for Silvered Flat Glass Mirror; 2024.
- G. ASTM F2285 Standard Consumer Safety Performance Specification for Diaper Changing Tables for Commercial Use; 2022.

1.04 SUBMITTALS

- A. See Section 013000 Administrative Requirements, for submittal procedures.
- B. Product Data: Submit data on accessories describing size, finish, details of function, and attachment methods.
- C. Samples: Submit two samples of each accessory, illustrating color and finish.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Commercial Toilet, Shower, and Bath Accessories:
 - 1. AJW Architectural Products: www.ajw.com/#sle.
 - 2. American Specialties, Inc: www.americanspecialties.com/#sle.
 - 3. Bradley Corporation: www.bradleycorp.com/#sle.
 - 4. Georgia-Pacific Professional: www.gppro.com/#sle.
 - 5. Kimberly-Clark Corporation; Kimberly-Clark Professional ICON Collection: www.kcprofessional.com/#sle.
 - 6. Bobrick.
 - 7. Substitutions: Section 016000 Product Requirements.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

B. Under-Lavatory Pipe Supply Covers:

1. Plumberex Specialty Products, Inc: www.plumberex.com/#sle.

C. Provide products of each category type by single manufacturer.

2.02 MATERIALS

- A. Accessories General: Shop assembled, free of dents and scratches and packaged complete with anchors and fittings, steel anchor plates, adapters, and anchor components for installation.
- B. Keys: Provide keys for each accessory to Owner; master key lockable accessories.
- C. Stainless Steel Sheet: ASTM A666, Type 304.
- D. Stainless Steel Tubing: ASTM A269/A269M, Grade TP304 or TP316.
- E. Mirror Glass: Annealed float glass, ASTM C1036 Type I, Class 1, Quality Q2, with silvering, protective and physical characteristics complying with ASTM C1503.
- F. Mirror Glass: Tempered safety glass, ASTM C1048; and ASTM C1036 Type I, Class 1, Quality Q2, with silvering as required.

2.03 FINISHES

- A. Stainless Steel: Satin finish, unless otherwise noted.
- B. Chrome/Nickel Plating: ASTM B456, SC 2, satin finish, unless otherwise noted.
- C. Shop Primed Ferrous Metals: Pretreat and clean, spray apply one coat primer and bake.
- D. Back paint components where contact is made with building finishes to prevent electrolysis.

2.04 COMMERCIAL TOILET ACCESSORIES

- A. Mirrors: Stainless steel framed, 1/4 inch (6 mm) thick tempered safety glass; ASTM C1048.
 - 1. Size: As indicated.
 - 2. Frame: 0.05 inch (1.3 mm)angle shapes, with mitered and welded and ground corners, and tamperproof hanging system; satin finish.
 - 3. Backing: Full-mirror sized, minimum 0.03 inch (0.8 mm) galvanized steel sheet and nonabsorptive filler material.
 - 4. Products:
 - a. AJW Architectural Products: www.ajw.com/#sle.
 - b. American Specialties, Inc: www.americanspecialties.com/#sle.
 - c. Bradley.
- B. Grab Bars: Stainless steel, smooth surface.
 - 1. Standard Duty Grab Bars:
 - a. Push/Pull Point Load: 250 pound-force (1112 N), minimum.
 - b. Dimensions: 1-1/2 inch (38 mm) outside diameter, minimum 0.05 inch (1.3 mm) wall thickness, exposed flange mounting, 1-1/2 inch (38 mm) clearance between wall and inside of grab bar.
 - c. Finish: Satin.
 - d. Length and Configuration: As indicated on drawings.
 - e. Products:
 - 1) AJW Architectural Products: www.ajw.com/#sle.
 - 2) American Specialties, Inc: www.americanspecialties.com/#sle.
 - 3) Grabcessories by Livewell Home Safety Solutions, LLC: www.livewellhs.com/#sle.
 - 4) Seachrome Corporation: www.seachrome.com/#sle.
 - 5) Standard Metal Hardware Manufacturing, Ltd; Grab Bars: www.smhardware.com/#sle.
 - 6) Substitutions: Section 016000 Product Requirements.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

2.05 COMMERCIAL SHOWER AND BATH ACCESSORIES

A. Robe Hook: Heavy-duty stainless steel, double-prong, rectangular-shaped bracket and backplate for concealed attachment, satin finish.

2.06 UNDER-LAVATORY PIPE AND SUPPLY COVERS

A. Specified in 224000 - Plumbing Fixtures.

2.07 DIAPER CHANGING STATIONS

- A. Diaper Changing Station: Wall-mounted folding diaper changing station for use in commercial toilet facilities, meeting or exceeding ASTM F2285.
 - 1. Material: Stainless steel.
 - 2. Mounting: Surface.
 - 3. Color: As selected.
 - 4. Minimum Rated Load: 300 pounds (136.1 kg).
 - 5. Products:
 - a. Basis of Design is Koala Kare KB300-01SS Horizontal Surface-Mounted with Stainless Steel Veneer.

2.08 UTILITY ROOM ACCESSORIES

- A. Mop and Broom Holder: 0.05 inch (1.3 mm) thick stainless steel, Type 304, hat-shaped channel.
 - 1. Holders: Three spring-loaded rubber cam holders.
 - 2. Length: 36 inches (900 mm).
 - 3. Products:
 - a. American Specialties, Inc: www.americanspecialties.com/#sle.
- B. Combination Utility Shelf/Mop and Broom Holder: 0.05 inch (1.3 mm) thick stainless steel, Type 304, with 1/2 inch (12 mm) returned edges, 0.06 inch (1.6 mm) steel wall brackets.
 - 1. Mop/broom holders: Three spring-loaded rubber cam holders at shelf front.
 - 2. Length: 36 inches (900 mm).
 - 3. Products:
 - a. American Specialties, Inc: www.americanspecialties.com/#sle.
 - b. Substitutions: 016000 Product Requirements.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify existing conditions before starting work.
- B. Verify exact location of accessories for installation.
- C. See Section 092116 for installation of blocking, reinforcing plates, and concealed anchors in walls and ceilings.

3.02 PREPARATION

- A. Deliver inserts and rough-in frames to site for timely installation.
- B. Provide templates and rough-in measurements as required.

3.03 INSTALLATION

- A. Install accessories in accordance with manufacturers' instructions in locations indicated on drawings.
- B. Install plumb and level, securely and rigidly anchored to substrate.
- C. Mounting Heights: As required by accessibility regulations, unless otherwise indicated.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

3.04 PROTECTION

A. Protect installed accessories from damage due to subsequent construction operations.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 104400 FIRE PROTECTION SPECIALTIES

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Fire extinguishers.
- B. Fire extinguisher cabinets.
- C. Accessories.

1.02 REFERENCE STANDARDS

- A. FM (AG) FM Approval Guide; Current Edition.
- B. NFPA 10 Standard for Portable Fire Extinguishers; 2022.
- C. UL (DIR) Online Certifications Directory; Current Edition.

1.03 SUBMITTALS

- A. See Section 013000 Administrative Requirements, for submittal procedures.
- B. Product Data: Provide color and finish.
- C. Shop Drawings: Indicate locations of cabinets and cabinet physical dimensions.
- D. Manufacturer's Installation Instructions: Indicate special criteria and wall opening coordination requirements.
- E. Manufacturer's Certificate: Certify that products meet or exceed specified requirements.

1.04 FIELD CONDITIONS

A. Do not install extinguishers when ambient temperature may cause freezing of extinguisher ingredients.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Fire Extinguishers:
 - 1. Activar Construction Products Group, Inc. JL Industries; Cosmic Extinguisher Multipurpose Chemical: www.activarcpg.com/#sle.
 - 2. Ansul, a Tyco Business: www.ansul.com/#sle.
 - 3. Kidde, a unit of United Technologies Corp: www.kidde.com/#sle.
 - 4. Nystrom, Inc: www.nystrom.com/#sle.
 - 5. Oval Brand Fire Products; Oval Dry Chemical Fire Extinguisher Multipurpose ABC: www.ovalfireproducts.com/#sle.
 - 6. Potter-Roemer: www.potterroemer.com/#sle.
 - 7. Pyro-Chem, a Tyco Business; _____: www.pyrochem.com/#sle.
 - 8. Substitutions: See Section 016000 Product Requirements.
- B. Fire Extinguisher Cabinets and Accessories:
 - 1. Activar Construction Products Group, Inc. JL Industries: www.activarcpg.com/#sle.
 - 2. Kidde, a unit of United Technologies Corp: www.kidde.com/#sle.
 - 3. Larsen's Manufacturing Co: www.larsensmfg.com/#sle.
 - 4. Nystrom, Inc: www.nystrom.com/#sle.
 - 5. Oval Brand Fire Products: www.ovalfireproducts.com/#sle.
 - 6. Potter-Roemer: www.potterroemer.com/#sle.
 - 7. The Williams Brothers Corporation of America: www.wbdoors.com/#sle.
 - 8. Substitutions: See Section 016000 Product Requirements.
50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

2.02 FIRE EXTINGUISHERS

- A. Fire Extinguishers General: Comply with product requirements of NFPA 10 and applicable codes, whichever is more stringent.
 - 1. Provide extinguishers labeled by UL (DIR) or FM (AG) for purpose specified and as indicated.
- B. Water Type Fire Extinguishers: Stainless steel tank, pressurized, with premixed antifreeze solution, including hose and nozzle.
 - 1. Class: 2-A type.
 - 2. Size: 2.5 gallon (9.4 L).
 - 3. Finish: Polished chrome.
- C. Multipurpose Dry Chemical Type Fire Extinguishers: Carbon steel tank, with pressure gauge.
 1. Class: A:B:C type.
 - 2. Temperature range: Minus 40 degrees F (Minus 40 degrees C) to ____ degrees F (____ degrees C).

2.03 FIRE EXTINGUISHER CABINETS

- A. Cabinet Construction: Non-fire rated.
- B. Cabinet Configuration: Semi-recessed type. Basis of Design: Alpine FC-7012
 1. Trim: Flat square edge, with 2 inch (_____ mm) wide face.
- C. Door: 0.036 inch (0.9 mm) metal thickness, reinforced for flatness and rigidity with roller type catch. Hinge doors for 180 degree opening with two butt hinges.
- D. Door Glazing: Acrylic plastic, clear, 1/8 inch (3 mm) thick, flat shape and set in resilient channel glazing gasket.
- E. Cabinet Mounting Hardware: Appropriate to cabinet, with pre-drilled holes for placement of anchors.
- F. Finish of Cabinet Interior: White colored enamel.

2.04 ACCESSORIES

A. Extinguisher Brackets: Formed steel, galvanized and enamel finished.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify existing conditions before starting work.
- B. Verify rough openings for cabinet are correctly sized and located.

3.02 INSTALLATION

A. Install in accordance with manufacturer's instructions.

3.03 MAINTENANCE

A. See Section 017000 - Execution and Closeout Requirements, for additional requirements relating to maintenance service.

END OF SECTION 104400

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

SECTION 123600 COUNTERTOPS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Countertops for architectural cabinet work.
- B. Wall-hung counters and vanity tops.

1.02 REFERENCE STANDARDS

- A. ANSI A208.1 American National Standard for Particleboard; 2022.
- B. ANSI A208.2 Medium Density Fiberboard (MDF) for Interior Applications; 2022.
- C. ASTM E84 Standard Test Method for Surface Burning Characteristics of Building Materials; 2023d.
- D. AWI (QCP) Quality Certification Program; Current Edition.
- E. AWI/AWMAC/WI (AWS) Architectural Woodwork Standards, 2nd Edition; 2014, with Errata (2016).
- F. AWMAC/WI (NAAWS) North American Architectural Woodwork Standards; 2021, with Errata.
- G. ISFA 2-01 Classification and Standards for Solid Surfacing Material; 2013.
- H. NEMA LD 3 High-Pressure Decorative Laminates; 2005.
- I. PS 1 Structural Plywood; 2023.

1.03 SUBMITTALS

- A. See Section 013000 Administrative Requirements for submittal procedures.
- B. Product Data: Manufacturer's data sheets on each product to be used, including:
 - 1. Preparation instructions and recommendations.
 - 2. Storage and handling requirements and recommendations.
 - 3. Specimen warranty.
- C. Shop Drawings: Complete details of materials and installation ; combine with shop drawings of cabinets and casework specified in other sections.
- D. Selection Samples: For each finish product specified, color chips representing manufacturer's full range of available colors and patterns.
- E. Verification Samples: For each finish product specified, minimum size 6 inches (150 mm) square, representing actual product, color, and patterns.
- F. Test Reports: Chemical resistance testing, showing compliance with specified requirements.
- G. Certificate: Submit labels and certificates required by quality assurance and quality control programs.

1.04 QUALITY ASSURANCE

- A. Installer Qualifications: Company specializing in performing work of the type specified in this section, with not less than three years of documented experience.
- B. Quality Certification:
 - 1. Comply with AWI (QCP) woodwork association quality certification service/program in accordance with requirements for work specified in this section: www.awiqcp.org/#sle.
 - 2. Provide labels or certificates indicating that the installed work complies with AWI/AWMAC/WI (AWS) requirements for grade or grades specified.
 - 3. Provide designated labels on shop drawings as required by certification program.
 - 4. Provide designated labels on installed products as required by certification program.

LAHC – WORKFORCE
EDUCATION RESOURCE AND
DEVELOPMENT CENTER

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

5. Submit certifications upon completion of installation that verifies this work is in compliance with specified requirements.

1.05 DELIVERY, STORAGE, AND HANDLING

- A. Store products in manufacturer's unopened packaging until ready for installation.
- B. Store and dispose of solvent-based materials, and materials used with solvent-based materials, in accordance with requirements of local authorities having jurisdiction.

1.06 FIELD CONDITIONS

A. Maintain environmental conditions (temperature, humidity, and ventilation) within limits recommended by manufacturer for optimum results. Do not install products under environmental conditions outside manufacturer's absolute limits.

PART 2 PRODUCTS

2.01 COUNTERTOPS

- A. Quality Standard: Custom Grade, in accordance with AWI/AWMAC/WI (AWS) or AWMAC/WI (NAAWS), unless noted otherwise.
- B. Solid Surfacing Countertops: Solid surfacing sheet or plastic resin casting over continuous substrate.
 - 1. Flat Sheet Thickness: 1/2 inch (12 mm), minimum.
 - 2. Solid Surfacing Sheet and Plastic Resin Castings: Complying with ISFA 2-01 and NEMA LD 3; acrylic or polyester resin, mineral filler, and pigments; homogenous, non-porous and capable of being worked and repaired using standard woodworking tools; no surface coating; color and pattern consistent throughout thickness.
 - a. Manufacturers:
 - 1) American Bath Group: www.americanbathgroup.com/#sle.
 - 2) Avonite Surfaces: www.avonitesurfaces.com/#sle.
 - 3) Dupont: www.corian.com/#sle.
 - 4) Formica Corporation: www.formica.com/#sle.
 - 5) Meganite, Inc: www.meganite.com/#sle.
 - 6) Relang International, LLC; DURASEIN: www.duraseinusa.com/#sle.
 - 7) Wilsonart: www.wilsonart.com/#sle. (Basis of Design).
 - 8) Substitutions: See Section 016000 Product Requirements.
 - b. Surface Burning Characteristics: Flame spread index of 25, maximum; smoke developed index of 450, maximum; when tested in accordance with ASTM E84.
 - c. Finish on Exposed Surfaces: Polished, gloss rating of 55 to 80.
 - d. Color and Pattern: As indicated on drawings.
 - 3. Other Components Thickness: 1/2 inch (12 mm), minimum.
 - 4. Back and End Splashes: Same sheet material, square top; minimum 4 inches (102 mm) high.

2.02 MATERIALS

- A. Wood-Based Components:
 - 1. Wood fabricated from old growth timber is not permitted.
 - 2. Provide sustainably harvested wood, certified or labeled; see Section 016000 Product Requirements.
 - 3. Provide wood harvested within a 500 mile (805 km) radius of the project site.
- B. Plywood for Supporting Substrate: PS 1 Exterior Grade, A-C veneer grade, minimum 5-ply; minimum 3/4 inch (19 mm) thick; join lengths using metal splines.
- C. Particleboard for Supporting Substrate: ANSI A208.1 Grade 2-M-2, 45 pcf (20 kg/cu m) minimum density; minimum 3/4 inch (19 mm) thick; join lengths using metal splines.
- D. Medium Density Fiberboard for Supporting Substrate: ANSI A208.2.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

- E. Adhesives: Chemical resistant waterproof adhesive as recommended by manufacturer of materials being joined.
- F. Joint Sealant: Mildew-resistant silicone sealant, clear.

2.03 ACCESSORIES

- A. Fixed Top-Mounted Countertop Support Brackets:
 - 1. Material: Steel.
 - 2. Finish: Manufacturer's standard, factory-applied, textured powder coat.
 - 3. Color: Black.
 - 4. Products:
 - a. Centerline Brackets; Front Mounting Countertop Support:
 - www.countertopbracket.com/#sle.
 - b. Substitutions: See Section 016000 Product Requirements.

2.04 FABRICATION

- A. Fabricate tops and splashes in the largest sections practicable, with top surface of joints flush.
 - 1. Join lengths of tops using best method recommended by manufacturer.
 - 2. Fabricate to overhang fronts and ends of cabinets 1 inch (25 mm) except where top butts against cabinet or wall.
 - 3. Prepare all cutouts accurately to size; replace tops having improperly dimensioned or unnecessary cutouts or fixture holes.
- B. Provide back/end splash wherever counter edge abuts vertical surface unless otherwise indicated.
 - 1. Secure to countertop with concealed fasteners and with contact surfaces set in waterproof glue.
 - 2. Height: 4 inches (102 mm), unless otherwise indicated.
- C. Wall-Mounted Counters: Provide skirts, aprons, brackets, and braces as indicated on drawings, finished to match.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Do not begin installation until substrates have been properly prepared.
- B. If substrate preparation is the responsibility of another installer, notify Architect of unsatisfactory preparation before proceeding.
- C. Verify that wall surfaces have been finished and mechanical and electrical services and outlets are installed in proper locations.

3.02 PREPARATION

- A. Clean surfaces thoroughly prior to installation.
- B. Prepare surfaces using the methods recommended by the manufacturer for achieving the best result for the substrate under the project conditions.

3.03 INSTALLATION

- A. Install vanities in accordance with manufacturer's instructions and approved shop drawings
- B. Securely attach countertops to cabinets using concealed fasteners. Make flat surfaces level; shim where required.
- C. Seal joint between back/end splashes and vertical surfaces.

3.04 TOLERANCES

- A. Variation From Horizontal: 1/8 inch in 10 feet (3 mm in 3 m), maximum.
- B. Offset From Wall, Countertops: 1/8 inch (3 mm) maximum; 1/16 inch (1.5 mm) minimum.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

C. Field Joints: 1/8 inch (3 mm) wide, maximum.

3.05 CLEANING

A. Clean countertops surfaces thoroughly.

3.06 PROTECTION

- A. Protect installed products until completion of project.
- B. Touch-up, repair or replace damaged products before Date of Substantial Completion.

END OF SECTION 123600

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

SECTION 323113 CHAIN LINK FENCES AND GATES

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Posts, rails, and frames.
- B. Wire fabric.
- C. Manual gates with related hardware.
- D. Accessories.

1.02 REFERENCE STANDARDS

- A. ASTM A123/A123M Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products; 2017.
- B. ASTM A153/A153M Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware; 2023.
- C. ASTM A392 Standard Specification for Zinc-Coated Steel Chain-Link Fence Fabric; 2011a (Reapproved 2022).
- D. ASTM F567 Standard Practice for Installation of Chain-Link Fence; 2023.
- E. CLFMI CLF-PM0610 Product Manual; 2017.
- F. FS RR-F-191/1D Fencing, Wire and Post Metal (Chain-Link Fence Fabric); 1990.

1.03 SUBMITTALS

A. See Section 013000 - Administrative Requirements, for submittal procedures.

PART 2 PRODUCTS

2.01 COMPONENTS

- A. Line Posts: 1.9 inch (48 mm) diameter.
- B. Corner and Terminal Posts: 2.38 inch (60 mm) diameter.
- C. Top and Brace Rail: 1.66 inch (42 mm) diameter, plain end, sleeve coupled.
- D. Bottom Rail: 1.66 inch (42 mm) diameter, plain end, sleeve coupled.
- E. Fabric: 2 inch (51 mm) diamond mesh interwoven wire, 6 gauge, 0.1920 inch (4.9 mm) thick, top selvage knuckle end closed, bottom selvage twisted tight.
- F. Fabric with Pre-Inserted Slats: 2 inch (51 mm) diamond mesh interwoven wire, 6 gauge, 0.1920 inch (4.9 mm) thick, top selvage knuckle end closed, bottom selvage twisted tight.
 - Privacy Slats: High-density polyethylene (HDPE), woven into fabric.
 a. Visual Barrier: 95 percent.
- G. Tension Wire: 6 gauge, 0.1920 inch (4.9 mm) thick steel, single strand.
- H. Tie Wire: Aluminum alloy steel wire.

2.02 MATERIALS

- A. Posts, Rails, and Frames:
 - 1. Line Posts: Type I round in accordance with FS RR-F-191/1D.
 - 2. Terminal, Corner, Rail, Brace, and Gate Posts: Type I round in accordance with FS RR-F-191/1D.
- B. Wire Fabric:
 - 1. ASTM A392 zinc coated steel chain link fabric.
 - 2. Comply with CLFMI CLF-PM0610.

50% CONSTRUCTION DOCUMENTS APRIL 11, 2025

FRAMEWORK E, LLC PROJ. NO. 2024007

2.03 MANUAL GATES AND RELATED HARDWARE

- A. Hardware for Single Swinging Gates: 180 degree hinges, 2 for gates up to 60 inches (1,525 mm) high, 3 for taller gates; fork latch with gravity drop and padlock hasp.
- B. Hinges: Finished to match fence components.
- C. Latches: Finished to match fence components.

2.04 ACCESSORIES

- A. Caps: Cast steel galvanized; sized to post diameter, set screw retainer.
- B. Fittings: Sleeves, bands, clips, rail ends, tension bars, fasteners and fittings; steel.

2.05 FINISHES

- A. Components (Other than Fabric): Galvanized in accordance with ASTM A123/A123M, at 1.7 ounces per square foot (530 g/sq m).
- B. Hardware: Hot-dip galvanized to weight required by ASTM A153/A153M.
- C. Accessories: Same finish as framing.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verification of Conditions: Verify that areas are clear of obstructions or debris.

3.02 PREPARATION

- A. Removal: Obstructions or debris.
- B. Ground Preparation:

3.03 INSTALLATION

A. Install framework, fabric, accessories and gates in accordance with ASTM F567.

END OF SECTION 323113



Items marked by a shaded background qualify for the Design Select program and ship in 15 days or less. To learn more about Design Select, visit <u>www.acuitybrands.com/designselect</u>.
*See ordering tree for details

WDGE LED Family Overview

design select

ds

Luminaira	Optics	Standard EM, 0°C		Sensor	Approximate Lumens (4000K, 80CRI)								
Luminaire			Cola EM, -20 C		PO	P1	P2	P3	P4	P5	P6		
WDGE1 LED	Visual Comfort	4W			750	1,200	2,000						
WDGE2 LED	Visual Comfort	10W	18W	Standalone / nLight		1,200	2,000	3,000	4,500	6,000			
WDGE2 LED	Precision Refractive	10W	18W	Standalone / nLight	700	1,200	2,000	3,200	4,200				
WDGE3 LED	Precision Refractive	15W	18W	Standalone / nLight	6,000	7,500	8,500	10,000	12,000				
WDGE4 LED	Precision Refractive			Standalone / nLight		12,000	16,000	18,000	20,000	22,000	25,000		

Ordering Information

EXAMPLE: WDGE2 LED P3 40K 80CRI VF MVOLT SRM DDBXD

Series	ries Package		Color Temperature		CRI	Distribution		Voltage	Mounting						
WDGE2 LED	P1 ¹ P2 ¹ P3 ¹	P1SW P2SW P3SW	27K 30K 35K	2700K 3000K 3500K	80CRI 90CRI	VF VW	Visual comfort forward throw Visual comfort	MVOLT 347 ³ 480 ³	Shipp SRM ICW	ed included Surface mounting bracket Indirect Canopy/Ceiling	Shipped AWS PBBW	I separately 3/8inch Architectural wall spacer ^s Surface-mounted back box (top, left,			
	P4 ¹ P5 ¹	Door with small window (SW) is required to accommodate sensors. See page 2 for more details.	40K 50K ²	4000K 5000K			WIDE			Washer brackét (dry/damp locations only) ⁴		right conduit entry). Use when there is no junction box available. ⁵			

Options					
E4WH	Emergency battery backup, Certified in CA Title 20	Standalone Sen	sors/Controls (only available with P1SW, P2SW & P3SW)	DDBXD	Dark bronze
E10WH	Emergency battery backup, Certified in CA Title 20	PIR	Bi-level (100/35%) motion sensor for 8–15' mounting heights. Intended for use on switched circuits with external dusk to dawn switching.	DBLXD	Black Natural
E20WC	MAEDBS (10W, 5°C min) Emergency battery backup, Certified in CA Title 20	PIRH	Bi-level (100/35%) motion sensor for 15–30' mounting heights. Intended for use on switched circuits with external dusk to dawn switching		aluminum
DE	MAEĎBS (18W, -20°C min)	PIR1FC3V	Bi-level (100/35%) motion sensor for 8-15' mounting heights with photocell pre-programmed for dusk to dawn operation.	DSSXD	Sandstone
DS	Dual switching (comes with 2 drivers and 2 light	PIRH1FC3V Networked Sens	Bi-level (100/35%) motion sensor for 15-30' mounting heights with photocell pre-programmed for dusk to dawn operation.	DDBTXD	Textured dark
DMG	engines; see page 3 for details) ⁷ 0–10V dimming wires pulled outside fixture (for use	NLTAIR2 PIR	Embedded wireless controls by nLight with Passive Infrared Occ sensor and on/off photocell for 8-15' mounting heights.	DBLBXD	Textured black
Dirid	with an external control, ordered separately) ⁸	NLTAIR2 PIRH	Embedded wireless controls by nLight with Passive Infrared Occ sensor and on/off photocell for 15-30' mounting heights.	DNATXD	Textured natural aluminum
BCE	Bottom conduit entry for back box (PBBW). lotal of 4 entry points.	NLIAIKEMIZ PIK	photocell for 8-15' mounting heights ⁹	DWHGXD	Textured white
DSLE	Dual Switching (1 Driver, 2 Light Engines)	NLTAIREM2 PIRH	Embedded wireless controls by nLight with UL924 listed emegency operation, Passive Infrared Occ sensor and on/off photocell for 15-30' mounting heights ⁹	DSSTXD	Textured sandstone
CCE	Coastal Construction ⁵	See page 4 for out of b	ox functionality		



FOR REVIEW. NOT FOR CONSTRUCTION

Accessories Ordered and shipped separately

WDGEAWS DDBXD WDGE 3/8inch Architectural Wall Spacer (specify finish)

WDGE2PBBW DDBXD U WDGE2 surface-mounted back box (specify finish)

NOTES

- 1 P1-P5 not available with sensors/controls. Sensors/controls only available with P1SW, P2SW and P3SW.
- 2 50K not available in 90CRI.

Performance Data

- 347V and 480V not available with E4WH, E10WH, E20WC, DS or DSLE.
 4 Not qualified for DLC. Not available with emergency battery backup or sensors/controls.
- 5 For PBBW and AWS with CCE option, require an RFA.
- 6 PE not available in 480V or with sensors/controls.
- 7 DS option not available with E4WH, E10WH, E20WC or sensors/controls.
 8 DMG option not available with sensors/controls.
- 9 Available with MVOLT only and only rated to 25C ambient.

Power Packages: P1, P2, P3, P4, P5

SN-WM

nsors/controls

Small Window (SW) configuration

Default co

Power Packages: P1SW, P2SW, P3SW

Configuration with sensors/controls

Power Packages: P1SW, P2SW, P3SW

Lumen Output Lumen values are from photometric tests performed in accordance with IESNA LM-79-08. Data is considered to be representative of the configurations shown,

within the tolerances allowed by Lighting Facts. Contact factory for performance data on any configurations not shown here.

 Performance
 System
 27K (2700K, 80 CRI)
 30K (3000K, 80 CRI)
 35K (3500K, 80 CRI)

Performance	Performance System Dist Type 27K (2700K, 80 CKI)				50K (5000K, 80 CM)				JJK (JJ00K, 80 CNI)			40K (4000K, 80 CNI)															
Package	Ŵatts	Dist. Type		LPW			G	Lumens	LPW		U	G	Lumens	LPW			G	Lumens	LPW		U			LPW	В	U	
D1 / D1CW/	1014/	VF	1,166	119	0	0	0	1,209	123	0	0	0	1,251	128	0	0	0	1,256	128	0	0	0	1,254	128	0	0	0
PI/PISW	1000	VW	1,197	122	0	0	0	1,241	126	0	0	0	1,284	131	0	0	0	1,289	131	0	0	0	1,286	131	0	0	0
D2 / D2CW/	15.11	VF	1,878	129	1	0	0	1,947	134	1	0	0	2,015	139	1	0	0	2,023	139	1	0	0	2,019	139	1	0	0
PZ/PZ5W	1510	VW	1,927	133	1	0	0	1,997	137	1	0	0	2,067	142	1	0	0	2,075	143	1	0	0	2,071	143	1	0	0
	2214/	VF	2,908	129	1	0	0	3,015	134	1	0	0	3,119	138	1	0	0	3,132	139	1	0	0	3,126	139	1	0	0
F3/F33W	2500	VW	2,983	132	1	0	0	3,093	137	1	0	0	3,200	142	1	0	0	3,213	143	1	0	0	3,206	142	1	0	0
D4	2514	VF	4,096	117	1	0	1	4,247	121	1	0	1	4,394	126	1	0	1	4,412	126	1	0	1	4,403	126	1	0	1
P4	35W	VW	4,202	120	1	0	0	4,357	125	1	0	1	4,508	129	1	0	1	4,526	129	1	0	1	4,517	129	1	0	1
DC	4011/	VF	5,567	115	1	0	1	5,772	119	1	0	1	5,972	123	1	0	1	5,996	124	1	0	1	5,984	124	1	0	1
61	46W	VW	5,711	118	1	0	1	5,921	122	1	0	1	6,127	126	1	0	1	6,151	127	1	0	1	6,139	127	1	0	1

Electrical Load

Performance	Custom Matte		Current (A)									
Package	System watts	120V	208V	240V	277V	347V	480V					
P1 / P1SW	10W	0.082	0.049	0.043	0.038							
	13W					0.046	0.033					
P2 / P2SW	15W	0.132	0.081	0.072	0.064							
	18W					0.056	0.041					
	23W	0.195	0.114	0.100	0.088							
P3 / P35W	26W					0.079	0.058					
D4	35W	0.302	0.175	0.152	0.134							
P4	38W					0.115	0.086					
DE	48W	0.434	0.241	0.211	0.184							
45	52W					0.157	0.119					

Lumen Ambient Temperature (LAT) Multipliers

Use these factors to determine relative lumen output for average ambient temperatures from 0-40 $^\circ C$ (32-104 $^\circ F).$

Amt	bient	Lumen Multiplier				
0°C	32°F	1.03				
10°C	50°F	1.02				
20°C	68°F	1.01				
25°C	77°F	1.00				
30°C	86°F	0.99				
40°C	104°F	0.98				

Lumen Multiplier for 90CRI

ССТ	Multiplier
27K	0.845
30K	0.867
35K	0.845
40K	0.885
50K	0.898

Lumen Output in Emergency Mode (4000K, 80 CRI)

Option	Dist. Type	Lumens				
FAMUL	VF	646				
E4WH	VW	647				
F10W/U	VF	1,658				
EIUWH	VW	1,701				
F20W/C	VF	2,840				
EZUWC	VW	2,913				

Projected LED Lumen Maintenance

Data references the extrapolated performance projections for the platforms noted in a 25°C ambient, based on 10,000 hours of LED testing (tested per IESNA LM-80-08 and projected per IESNA TM-21-11).

To calculate LLF, use the lumen maintenance factor that corresponds to the desired number of operating hours below. For other lumen maintenance values, contact factory.

Operating Hours	0	25,000	50,000	100,000
Lumen Maintenance Factor	1.0	>0.96	>0.95	>0.91



FOR REVIEW. NOT FOR CONSTRUCTION



Emergency Egress Options

Emergency Battery Backup

The emergency battery backup is integral to the luminaire — no external housing required! This design provides reliable emergency operation while maintaining the aesthetics of the product. All emergency battery backup configurations include an independent secondary driver with an integral relay to immediately detect loss of normal power and automatically energize the luminaire. The emergency battery will power the luminaire for a minimum duration of 90 minutes (maximum duration of three hours) from the time normal power is lost and maintain a minimum of 60% of the light output at the end of 90minutes.

Applicable codes: NFPA 70/NEC - section 700.16, NFPA 101 Life Safety Code Section 7.9

The examples below show illuminance of 1 fc average and 0.1 fc minimum in emergency mode with E10WH or E20WC and VF distribution.

Grid = 10ft x 10ft



WDGE2 LED xx 40K 80CRI VF MVOLT E10WH



WDGE2 LED xx 40K 80CRI VF MVOLT E20WC

Dual Switching (DS) Option

The dual switching option offers operational redundancy that certain codes require. With this option the luminaire comes integrated with two drivers and two light engines. These work completely independent to each other so that a failure of any individual component does not cause the whole luminaire to go dark.

Applicable codes: NFPA 70/NEC – section 700.16, NFPA 101 Life Safety Code Section 7.9



Dual Switching Light Engine (DSLE) Option

The dual switching option offers operational redundancy that certain codes require. With this option the luminaire comes integrated with one driver and two light engines. These work completely independent to each other so that a failure of either light engine does not cause the whole luminaire to go dark.

Applicable codes: NFPA 70/NEC – section 700.16, NFPA 101 Life Safety Code Section 7.9





COMMERCIAL OUTDOOR

Control / Sensor Options

SN-WM

9.2

Motion/Ambient Sensor (PIR, PIRH)

Motion/Ambeint sensor (Sensor Switch MSOD) is integrated into the the luminaire. The sensor provides both Motion and Daylight based dimming of the luminaire. For motion detection, the sensor utilizes 100% Digital Passive Infrared (PIR) technology that is tuned for walking size motion while preventing false tripping from the environment. The integrated photocell enables additional energy savings during daytime periods when there is sufficient daylight. Optimize sensor coverage by either selecting PIR or PIRH option. PIR option comes with a sensor lens that is optimized to provide maximum coverage for mounting heights between 8-15ft, while PIRH is optimized for 15-40ft mounting height.

Networked Control (NLTAIR2)

nLight® AIR is a wireless lighting controls platform that allows for seamless integration of both indoor and outdoor luminaires. Five-tier security architecture, 900 MHz wireless communication and app (CLAIRITY™ Pro) based configurability combined together make nLight® AIR a secure, reliable and easy to use platform.





PIRH





Option	Dim Level	vel High Level (when triggered		Motion Time Delay	Ramp-down Time	Ramp-up Time
PIR or PIRH	Motion - 3V (37% of full output) Photocell - 0V (turned off)	10V (100% output)	Enabled @ 5fc	5 min	5 min	Motion - 3 sec Photocell - 45 sec
PIR1FC3V, PIRH1FC3V	Motion - 3V (37% of full output) Photocell - 0V (turned off)	10V (100% output)	Enabled @ 1fc	5 min	5 min	Motion - 3 sec Photocell - 45 sec
NLTAIR2 PIR, NLTAIR2 PIRH (out of box)	Motion - 3V (37% of full output) Photocell - 0V (turned off)	10V (100% output)	Enabled @ 5fc	7.5 min	5 min	Motion - 3 sec Photocell - 45 sec

UL 924 Response – nLight AIR Devices with EM Option

- NLTAIREM2 devices will remain at their high-end trim and ignore wireless lighting control commands, unless a normal-powersensed (NPS) broadcast is received at least every 8 seconds.
- Using the CLAIRITY+ mobile app, NLTAIREM2 devices must be associated with a group that includes a normal power sensing device to receive NPS broadcasts.
- The non-emergency devices, NLTAIR2 PIR and NLTAIR2 PIRH, with version 3.4 or later firmware can be used for normal power sensing.





NLTAIR2 PIR – nLight AIR Motion/Ambient Sensor

D = 7" H = 11" W = 11.5"



PBBW – Surface-Mounted Back Box Use when there is no junction box available.

D = 1.75" H = 9" W = 11.5"



AWS – 3/8inch Architectural Wall Spacer D = 0.38"

H = 4.4"

W = 7.5 "

FEATURES & SPECIFICATIONS

INTENDED USE

Common architectural look, with clean rectilinear shape, of the WDGE LED was designed to blend with any type of construction, whether it be tilt-up, frame or brick. Applications include commercial offices, warehouses, hospitals, schools, malls, restaurants, and other commercial buildings.

CONSTRUCTION

The single-piece die-cast aluminum housing integrates secondary heat sinks to optimize thermal transfer from the internal light engine heat sinks and promote long life. The driver is mounted in direct contact with the casting for a low operating temperature and long life. The die-cast door frame is fully gasketed with a one-piece solid silicone gasket to keep out moisture and dust, providing an IP66 rating for the luminaire.

FINISH

Exterior painted parts are protected by a zinc-infused Super Durable TGIC thermoset powder coat finish that provides superior resistance to corrosion and weathering. A tightly controlled multi-stage process ensures a 3 mils thickness for a finish that can withstand extreme climate changes without cracking or peeling. Standard Super Durable colors include dark bronze, black, natural aluminum, sandstone and white. Available in textured and non-textured finishes.

OPTICS

Well crafted reflector optics allow the light engine to be recessed within the luminaire, providing visual comfort, superior distribution, uniformity, and spacing in wall-mount applications. The WDGE LED has zero uplight and qualifies as a Nighttime Friendly™ product, meaning it is consistent with the LEED® and Green Globes™ criteria for eliminating wasteful uplight.

ELECTRICAL

Light engine consists of high-efficacy LEDs mounted to metal-core circuit boards to maximize heat dissipation and promote long life (up to L91/100,000 hours at 25°C). The electronic driver has a power factor of >90%, THD <20%. Luminaire comes with built in 6kV surge protection, which meets a minimum Category C low exposure (per ANSI/IEEE C62.41.2). Fixture ships standard with 0-10v dimmable driver.

INSTALLATION

A universal mounting plate with integral mounting support arms allows the fixture to hinge down for easy access while making wiring connections. The 3/8" Architectural Wall Spacer (AWS) can be used to create a floating appearance or to accommodate small imperfections in the wall surface. The ICW option can be used to mount the luminaire inverted for indirect lighting in dry and damp locations. Design can withstand up to a 1.5 G vibration load rating per ANSI C136.31.

LISTINGS

CSA certified to U.S. and Canadian standards. Luminaire is IP66 rated. PIR options are rated for wet location. Rated for -40°C minimum ambient. DesignLights Consortium® (DLC) Premium qualified product and DLC qualified product. Not all versions of this product may be DLC Premium qualified or DLC qualified. Please check the DLC Qualified Products List at <u>www.designlights.org/QPL</u> to confirm which versions are qualified. International Dark-Sky Association (IDA) Fixture Seal of Approval (FSA) is available for all products on this page utilizing 2700K and 3000K color temperature only and SRM mounting only.

GOVERNMENT PROCUREMENT

BABA – Build America Buy America: Product qualifies as produced in the United States under the definitions of the Build America, Buy America Act.

Please refer to www.acuitybrands.com/buy-american for additional information.

WARRANTY

5-year limited warranty. This is the only warranty provided and no other statements in this specification sheet create any warranty of any kind. All other express and implied warranties are disclaimed. Complete warranty terms located at:

Note: Actual performance may differ as a result of end-user environment and application. All values are design or typical values, measured under laboratory conditions at 25 °C. Specifications subject to change without notice.

